### Agenda Report



2725 Judge Fran Jamieson Viera, FL 32940

### Consent

F.10. 9/12/2023

### **Subject:**

Phase VII Sideslope Closure CDF Slurry Wall Landfill Change Order No. 2

### **Fiscal Impact:**

Increase in Contract Price of \$1,315,958.81, from original \$9,388,500.00 to \$10,704,458.81.

### Dept/Office:

Solid Waste Management Department

### **Requested Action:**

It is requested that the Board of County Commissioners approve Change Order No. 2 for the Phase VII Sideslope Closure project currently in construction on the Slurry Wall Landfill at the Central Disposal Facility and authorize the Chair to sign the Change Order.

### Summary Explanation and Background:

The Phase VIII sequential closure of the Slurry Wall Landfill at the Central Disposal Facility is currently under construction. This includes the closure of approximately 18 acres on the north, east, and south side slopes of the landfill from elevation 150 to 190, including the installation of a 40-mil geomembrane cover system overlain by a composite drainage net and tied into the previous Phase V and Phase VI closure cover systems, and 24-inches of clean granular fill and sod as a protective cover. The project also includes the construction and tie-in of stormwater collection and control structures and the expansion of the active landfill gas collection system with the installation of 34 landfill gas collection wells and associated piping. The approved budget for FY22-23 was \$15,000,000 with funding coming from a closure escrow fund. The Engineer of Record is Ron Beladi of Neel-Schaffer, Inc. and Southeast Environmental Contracting, Inc. was selected as the lowest responsible qualified bidder at \$9,388,500.00. The FY22-23 CIP budget, project bid tabulation, and Notice of Award are attached.

During construction, it was determined that ending the closure at elevation 190 would leave the Phase VII closure area vulnerable to stormwater erosion from the area above the 190 elevation, resulting in washout of intermediate cover soil and solid waste onto the closed portion of the landfill. To avoid the potential for environmental violations and recurring costs of maintenance, repair, and cleanup it was agreed to extend the closure to the outside edges of the top deck of the landfill, elevation 215. This increases the closure area by approximately 3.5 acres and increases the amount of liner, piping, and granular fill necessary for completion of the project. The total change in contract is an additional \$1,315,958.81 in Contract Price and an additional 28 days in Contract Time. Further, the additional closure work for this portion of the landfill would eventually have been required to finalize all closure activity for the CDF, were it not included at this time.

### Attachments:

F.10. 9/12/2023

- Budget, Bid Tabulation, and Notice of Award
- Change Order No. 2

### **Clerk to the Board Instructions:**

Please return one (1) signed and attested copy to Solid Waste



### FLORIDA'S SPACE COAST

Kimberly Powell, Clerk to the Board, 400 South Street • P.O. Box 999, Titusville, Florida 32781-0999

Talephone: (321) 637-2001 Fax: (321) 264-6972 Kimberly Powell@brevardclerk.us



September 13, 2023

### MEMORANDUM

TO: Tom Mulligan, Solid Waste Management Director

RE: Item F.10., Phase VII Sideslope Closure CDF Slurry Wall Landfill Change Order No. 2

The Board of County Commissioners, in regular session on September 12, 2023, approved and executed Change Order No. 2 for the Phase VII Sideslope Closure Project currently in construction on the Slurry Wall Landfill at the Central Disposal Facility. Enclosed is a fully-executed Change Order.

Your continued cooperation is always appreciated.

Sincerely,

BOARD OF COUNTY COMMISSIONERS

RACHEL M. SADOFF, CLERK

Kimberly Powell, Clerk to the Board

/sm

Encl. (1)

CC:

Finance

Budget

## Fiscal Year 2022-2023 Capital Improvements Program

Program Name	Description	Funding Source	Total Cost
Disposal	U.S. 192	Assessments	\$1,000,000
Disposal	Titusville Transfer Station	Assessments	\$500,000
Disposal	South Landfill Expansion Cell 2	Impact Fees	\$1,100,000
Disposal	CDF Cell 1 Gas System	Assessments	\$500,000
Disposal	CDF Cell 3	Assessments	\$500,000
Disposal	CDF Closure	Escrow	\$15,000,000
Disposal	Sarno Landfill Closure	Escrow	\$16,000,000
Disposal	South Landfill Cell 1 Closure	Escrow	\$6,157,321

\$34.60



# **BID TABULATION SHEET: AWARD RECOMMENDATION**

Bid Title: Phase VII Side slope closure CDF Slurry Wall Landfill

Bid No: B-6-23-19

January 30, 2023 @ 5:00 pm THROUGH: OPENING DATE & TIME: 1/18/2023 @ 11:00 AM January 24, 2023 POSTING TIME/DATE:

**POSTED BY: James Norris** 

VENDOR	VENDOR CITY/STATE	BID PRICE
Southeast Environmental Construction	Hahira, GA	\$9,388,500.00
Belair	New Brighton, MN	\$11,079,813.40
Thalle Construction	Hillsborough, NC	\$20,156,000.00

Intended Award: Southeast Environmental Construction

Brevard County encourages prompt and fair handling of all complaints and disputes with the business community. Filing of any disputes and Bid tabulations with award recommendations are posted to VendorLink at www.myvendorlink.com or DemandStar at www.demandstar.com. appeals shall be in accordance with procedures specified in bid documents.

Approval initials



**AWARD AMOUNT** 

**Purchasing Services** 2725 Judge Fran Jamieson Way Building C, Room 303 Viera, Florida 32940

### NOTICE OF AWARD

DATE: 2/9/2023

B-6-23-19 Phase VII Sideslope Closure CDF Slurry Wall Landfill

**VENDOR CITY AND** 

**ITEMS** 

PROCUREMENT ANALYST: James Norris

**VENDOR** 

		SIAIE	AVVARDED	
South	neast Environmental Contracting, Inc.	Hahira, GA	ALL	\$9,388,500.00
	BOARD AWARDAGENDA ATTACHED	)		
⊠ (Per Se	APPROVED AWARD (NON-BOARD AG ctions III.E. & III.I. & J., BCC-25, PROCURE		rs, Purchasing Mar	nager
	DED BY A COMMITTEE CONSISTING OF s Department Director; and Tom Mulligan			Edward Fontanin, Utility
FOR P	URCHASING USE ONLY:			
$\boxtimes$	ONE-TIME PURCHASE			
	ANNUAL BID:  EFFECTIVE DATE: ENDIN  RENEWAL OPTION  One year  Other	NG DATE: ner (fill in)		
	Prompt Payment Discount Offered Yes Performance and payment bonds received Release Cashier's or Certified Check Re	ed with construction contra		
	SPECIAL INSTRUCTIONS TO AWARDS Please provide certificate of insurance. Please provide performance and paymer OTHER:			

### **CHANGE ORDER FORM**

NO.	Two (2)	1969
DATE:	August 28, 2023	FLORIDA
PROJECT BID NUMBER:	B-6-23-19	
PROJECT NAME:	CDF Slurry Wall Land	Ifill Phase VII Sideslope Closure
CONTRACTOR NAME:	Southeast Environmer	tal Contracting, Inc. (SEC)
AGREEMENT DATE:	March 13, 2023	
The following changes are here  CONTRACT PRICE SUMM	·	CT DOCUMENTS:

### **CONTRACT TIME SUMMARY:**

CURRENT Contract Price as Adjusted by Previous Change Orders:

FINAL Contract Price Incorporating Above Changes:

NET INCREASE/(DECREASE) in Price Resulting from this Change Order:

**ORIGINAL Contract Price:** 

ORIGINAL Contract Time (days):

CURRENT Contract Time as Adjusted by Previous Change Orders (days):

NET INCREASE/(DECREASE) in Time Resulting from this Change Order (days):

28 days

FINAL Contract Time Incorporating Above Changes (days):

NEW DATE FOR SUBSTANTIAL COMPLETION

January 25, 2024

NEW DATE FOR FINAL COMPLETION

March 25, 2024

### CHANGES ORDERED:

### I. GENERAL

This Change Order is necessary to cover changes in the Work and Time to be performed under this Contract. The GENERAL CONDITIONS, SUPPLEMENTARY CONDITIONS, SPECIFICATIONS and all parts of the Project Manual listed in Article 1, Definitions, of the GENERAL CONDITIONS apply to and govern all Work under this Change Order.

\$ 9,388,500.00

\$ 9, 388,500.00

\$1,315,958.81

\$10,704,458.81

### II. REQUIRED CHANGES:

See attached documents and related correspondence. The changes are necessary to stabilize the side slopes above the limits of final closure. The changes included in this Change Order No. 1 are described below:

- A. The additional work will include grading of the solid waste above the current construction limit (elevation 190 NAVD) to top deck area elevation 215 NAVD, which will result in installation of an additional 3.5-acre final closure final cover (leveling course, 40-mil LLDPE geomembrane, installation of composite drainage net and 24-inches of clean cover soil with sod), extension of stormwater letdown pipes and installation of four new inlets, and extension of landfill gas collection pipes to the new limits of closure. Please include in your proposal to extend the letdown pipes and landfill gas header piping to the proposed anchor trench locations.
- B. The project requires exposure of the existing stub-outs up slope of the existing stormwater inlets and connect the new letdown pipes to the limits of construction. The excavation at a few of the inlets shows the pipe trench was not previously installed after the stub-outs. This requires the previous closure cover along the alignment of the new letdown pipe be opened and build a trench for installation of the letdown piping. Reference CCIR-6 Response. Please prepare a detailed proposal for cutting the pipe trench in areas where needed in order to extend the letdown piping. The proposal should detail the work required to excavate the waste along the proposed trench, install new liner and CDN for the letdown pipe to be installed as shown in the attached detail A. The pipe and connections to the existing stubouts were previously included in the contract. The proposal should include all cost to the Contractor for filling, grading and restoring the previously closed area and sodding the affected area.

Change Order Requested By:	X	X	
	Brevard County	Contractor	Engineer

### JUSTIFICATION FOR CHANGES:

III.

- An updated topographic survey of the Slurry Wall Landfill (SWL) indicated an area on top of the contract closure construction area will be vulnerable to erosion and washouts and will require to be stabilized and closed as part of this project. The adjustments to the closure cover system and final grading plan are based on site conditions at the time of construction. Adjustments to the final closure cover area are intended to prevent erosion and washout of solid waste on the newly closed side slope areas. In addition, extension of the stormwater letdown pipes, inlets and landfill gas piping are included in the new limits of closure.
- Increase in Contract Time for construction of new 3.5-acre closure areas.
- IV. METHOD OF PAYMENT/EFFECT TO CONTRACTOR'S SCHEDULE OF VALUES:

Contract Value adjustments are based on unit costs in bid and Contractor's schedule of values. Contract Time adjustments are based on the General Conditions of the Contract Documents.

### V. RECOMMENDATIONS, ACCEPTANCE, AND APPROVAL

The aforementioned change, and work affected thereby, is subject to all provisions of the original Contract not specifically changed by this Change Order; and,

This change order includes not only all direct costs of contractor such as labor, material, job overhead, and profit markup but also includes any costs for modifications or changes in sequence of work to be performed, delays, rescheduling, disruptions, extended direct overhead or general overhead, acceleration, material or other escalation which includes wages, and other impact costs. It is expressly understood and agreed that the approval of the Change Order shall have no effect on the original Contract other than matters expressly provided herein.

By signing this change order agreement, the Contractor hereby releases the County, its agents, and employees from any and all liabilities under this Contract for further equitable adjustments and /or claims associated with this change order.

ENGINEER'S RECOMMENDATION	CONTRACTOR'S ACCEPTANCE
Re.	FIA
Authorized Signature	Authorized Signature
Ron Beladi, P.E.	Earl Holmes
Name	Name
Vice President	President, SEC
Title	Title
August 28, 2023	_August 28, 2023
Date	Date

OWNER'S APPROVAL

BREVARD COUNTY, FLORIDA

ttest;

Solid Waste Management Department or Board Chair if requires Board approval

This 12th day of September

.2023

\*\*\* END OF CHANGE ORDER FORM \*\*\*

### Central Disposal Facility Slurry Wall Landfill Phase VII Closure Brevard County Solid Waste Management Department PROJECT NO. P-6-23-19

**Closure Extension** 

### **PART A**



DESCRIPTION	UNIT	QTY	UNI	T PRICE (\$)		VALUE (\$)
1. General						
c. Field Survey	LS	1	\$	5,000.00	\$	5,000.00
d. Laboratory Testing and Reporting Services	LS	1	\$	9,950.00	\$	9,950.00
e. Administration/ O&P and Direct Expense						
1. Bonds	LS	1	\$	20,565.25	\$	20,565.2
2. Insurance	LS	1	\$	26,419.77	\$	26,419.7
4. Temporary Facilities	LS	1	\$	4,000.00	\$	4,000.0
5. Health and Safety and Other Requirements	LS	1	\$	4,000.00	\$	4,000.0
Project Record Documents	LS	1	\$	3,980.00	\$	3,980.0
General Subtotal					\$	73,915.0
2. Earthwork						
a. Subgrade Preparation and General Grading	ac	3.545	\$	33,000.00	\$	116,985.0
3. Gas Piping						
a. Landfill Gas Header 16" materials	LF	300	\$	65.00	\$	19,500.0
b. Landfill Gas Header 16" installation	LF	300	\$	124.00	\$	37,200.0
c. Landfill Gas Header 12" materials	LF	40	\$	55.00	\$	2,200.0
d. Landfill Gas Header 12" installation	LF	40	\$	100.00	\$	4,000.0
e. LFG pipe 6"	LF	160	\$	40.00	\$	6,400.0
f. LFG pipe 4"	LF	120	\$	30.00	\$	3,600.0
Gas Piping Subtotal					\$	72,900.0
4. Stormwater						
d. 24" Stormwater Letdown piping and Connections	LF	480	\$	185.00	\$	88,800.0
Stormwater Subtotal					\$	88,800.0
5. Liner System						74
a. HDPE Geomembrane material	SF	154,420	\$	0.45	\$	69,489.0
b. HDPE Geomembrane installation	SF	154,420	\$	0.31	\$	47,870.2
c. Composite Drainage Net (CDN) material	SF	154,420	\$	0.90	\$	138,978.1
d. Composite Drainage Net (CDN) installation	SF	154,420	\$	0.40	\$	61,768.0
iner System Subtotal					\$	318,105.6
5. Final Grade Treatment						
a. Sodding	SF	154,420	\$	0.30	\$	46,326.0
b. erosion control	МО	1	\$	2.488.89	\$	2,488.8
Final Grade Treatment Subtotal					\$	48,814.9
7. UNIT PRICE PORTION					_	
I. Granular Fill from Offsite Sources- In Place	CY	14,299	\$	28.00	\$	400,372.0
2. Solid Waste Grading	CY	6,264	\$	7.00	\$	43,848.0
B. ADDED ITEM					Ť	,.
I. Landfill Gas Well Boots	EA	7	\$	1,290,00	\$	9,030,0
Unit Price Subtotal	<del> </del>		-	1,200,00	\$	453,250.0
TOTAL		-	_		\$	1,172,770.5

Earl Holmes, President

Southeast Environmental Contracting, Inc.

1810 Lee Road Orlando, FL 32810



### **PART B**

### Inlet pipe trench correction at 8 inlets

inlet pipe trench correction at 8 inlets						
<ol> <li>Removal of the protective cover to expose the geosynthetics, 40'x60' 5 each</li> </ol>	16	exc crew hours	\$	1,070.50	\$	17,128.00
Cut and peel back the geosynthetics.	8	liner crew hours	\$	338.75	\$	2,710.00
3. Excavate waste.	16	exc crew hours	\$	1,070.50	\$	17,128.00
Grade and place granular fill pipe bedding.	8	exc crew hours	\$	1,070.50	\$	8,564.00
5. Add 30" pipe for stub outs.	18	lf	\$	200.00	\$	3,600.00
6. Backfill	8	exc crew hours	Ś	1,070.50	\$	8,564.00
7. Replace and add geosynthetics.	16	liner crew hours	\$	338.75	\$	5,420.00
Replace and add protective cover.	16	exc crew hours	\$	1,070.50	\$	17,128.00
9. Sodding.	12,000	sf	\$	0.30	Ś	3,600.00
10. Add 24" pipe to top anchor trench	250	lf	\$	185.00	\$	46,250.00
11. 30" ADS 11.25 degree fittings plus allowed mark up	8	ea	\$	784.72	\$	6,277.74
11. 30 A03 11.23 degree fittings plus dilowed mark up	3	Ca	Ą	total	ė	136,369.74
		allowed mark up 5%		totai	\$	6,818.49
		mowed mark up 378				·
				total	\$	143,188.23
Fuercation are unbarreled access				total	\$	143,188.23
Excavation crew breakdown	1	L				
excavator	1	hour	\$	98.00	\$	98.00
excavator dozer	1	hour	\$	98.00 112.50	\$	98.00 112.50
excavator dozer operator- 2 each	1 1	hour hour	\$ \$	98.00 112.50 100.00	\$ \$ \$	98.00 112.50 300.00
excavator dozer operator- 2 each labor - 2 each	1 1 1	hour hour hour	\$ \$ \$	98.00 112.50 100.00 87.50	\$ \$ \$	98.00 112.50 300.00 87.50
excavator dozer operator- 2 each labor - 2 each per diem / housing - 4 each	1 1 1	hour hour hour hour	\$ \$ \$ \$	98.00 112.50 100.00 87.50 120.00	\$ \$ \$ \$	98.00 112.50 300.00 87.50 360.00
excavator dozer operator- 2 each labor - 2 each	1 1 1	hour hour hour	\$ \$ \$	98.00 112.50 100.00 87.50 120.00 112.50	\$ \$ \$ \$ \$	98.00 112.50 300.00 87.50 360.00 112.50
excavator dozer operator- 2 each labor - 2 each per diem / housing - 4 each	1 1 1	hour hour hour hour	\$ \$ \$ \$	98.00 112.50 100.00 87.50 120.00	\$ \$ \$ \$	98.00 112.50 300.00 87.50 360.00
excavator dozer operator- 2 each labor - 2 each per diem / housing - 4 each	1 1 1	hour hour hour hour	\$ \$ \$ \$	98.00 112.50 100.00 87.50 120.00 112.50	\$ \$ \$ \$ \$	98.00 112.50 300.00 87.50 360.00 112.50
excavator dozer operator- 2 each labor - 2 each per diem / housing - 4 each dozer	1 1 1 1	hour hour hour hour	\$ \$ \$ \$	98.00 112.50 100.00 87.50 120.00 112.50	\$ \$ \$ \$ \$	98.00 112.50 300.00 87.50 360.00 112.50
excavator dozer operator- 2 each labor - 2 each per diem / housing - 4 each dozer	1 1 1	hour hour hour hour hour	\$ \$ \$ \$	98.00 112.50 100.00 87.50 120.00 112.50 total	\$ \$ \$ \$ \$ \$	98.00 112.50 300.00 87.50 360.00 112.50 1,070.50
excavator dozer operator- 2 each labor - 2 each per diem / housing - 4 each dozer  Liner crew breakdown labor - 5 each	1 1 1 1 1	hour hour hour hour hour	\$ \$ \$ \$	98.00 112.50 100.00 87.50 120.00 112.50 total	\$ \$ \$ \$ \$	98.00 112.50 300.00 87.50 360.00 112.50 1,070.50

Earl Holmes, President

Southeast Environmental Contracting, Inc.

1810 Lee Road Orlando, FL 32810

127

### **REQUEST FOR PROPOSAL**

REQUEST FOR PROPE	OSAL (RFP) NO.			
RFP Prepared By:	Ron Beladi		Project Manager	
mi rieparca by.	(Name)		(Title)	
	()		(mac)	
Date Prepared:	August 17, 2023			
			<del></del>	
PROJECT I	DATA		CONTRACT DATA	
	ise VII Sequential Closure		Contract Document Page Number:	
Location: Central Disposal Facility, Brevard County  Drawing Number:				
			Specification Section/Number:	
li-				
RFP DISTRIBUTION	BY ENGINEER:			
Owner's Home Office	e: No. Copies	Date :	Sent:	
Attn.: Tom Mulligan				
Contractor's Home	Office: No. Copies	Date :	Sent:	
Attn.: Reinaldo Gon:	zales			
Owner's Field Office		Date :	Sent:	
Engineer's Field Offi		Date :		
Contractor's Field O		Date :		
Other:	No. Copies	Date :	Sent:	
A.L. 8				
Attn.:				
laasa mrayida tha i	undorsianod o unonosol	for the following she	i- the	
		_	ange in the work within ten (10) calendar day	,
			clearly delineate the scope of the proposed	
			timate of time and costs broken down by	
			rofit. Any amount included for subcontracted	
			cepted and approved by the Owner, a chang	e
rder will be issued	for changes in the work	k of the Contract in a	ccordance with the Contract Documents.	
Type of Change Proposed:				
гіорозса.		х		
<del>7</del>	(Deletion of Work	(Addition of Work)	(Revision of Work) (Other)	
	,	y manner trothy	(other)	

Please see reverse side for a detailed description of the proposed change in Work.

128

### **DESCRIPTION OF PROPOSED CHANGE IN WORK:**


An updated topographic survey of the Slurry Wall Landfill (SWL) indicated an area on top of the contracted closure construction area will be vulnerable to erosion and washouts and will require to be stabilized or closed as part of this project. The adjustments to the closure cover system and final grading plan are based on site conditions at the time of construction. Adjustments to the final closure cover area are intended to prevent erosion and washout of solid waste on the newly closed side slope areas. In addition, extension of the stormwater letdown pipes, inlets and landfill gas piping are included to the new limits of closure.

Please prepare a detailed proposal for extension of the closure construction area to the limits shown on the attached drawing. The additional work includes, but not limited to, solid waste grading and preparation of the new areas for installation of the Leveling Course, 40-mil LLDPE liner, CDN and 24-inches of protective cover with sod. The LFG laterals and collection pipes are to be extended to new limits, new stormwater inlets installed at the 210-ft terrace and letdown pipes extended and capped.

The proposal should include all cost to the Contractor that is outside of his current contract for filling, grading and restoring the previously closed area and sodding the affected area.

ATTA	ACHMENTS:	
	Description of Item Attached	No. of Copies
1.		
2.		
3.		
4.		
5.		

**END OF REQUEST FOR PROPOSAL FORM** 



nn\_ond\_Closure/Phase Vii Construction Drowings/Conformed/CRADE EXTENSION/Pr. VII EXTENSION COMBINED dwg

### **REQUEST FOR PROPOSAL**

REQUEST FOR PRO	POSAL (RFP) FOR PROPOS	SED CHANGE NO.	_1		
RFP Prepared By:	Ron Beladi		Project N	Manager	
ropa.ca sy.	(Name)		(Title)	иоподел	
	,		(1.13.2)		
Date Prepared:	July 16, 2023				
PROJECT	DATA		CONTRACT D	PATA	
Name: CDF-SWL PI	nase VII Sequential Closure	e	Contract Document Page		
	Disposal Facility, Brevard C		Drawing Number:		
Owner's Bid Numb	Owner's Bid Number: Specification Section/Number:				
RFP DISTRIBUTION	I BY ENGINEER:				
Owner's Home Off	ice: No. Copies	Date :	Sent:		
Attn - Tom Mulliga	_				
Attn.: Tom Mulliga		Date 5	ent:		
Contractor 3 nome	. Office. Two. copies	)   Date:	Jenc.		
Attn.: Reinaldo Go	nzales				
Owner's Field Office		Date 9	ent:		
Engineer's Field Of			ent		
Contractor's Field	Office: No. Copies	Date S	ient:		
Other:	No. Copies	Date 9	ont:		
other.	No. copies	Date.	Jene.		
Attn.:					
				nin ten (10) calendar days	
from the above da	te of this request. The	e written proposal must	clearly delineate the	scope of the proposed	
		oroviding an itemized es			
				cluded for subcontracted	
				by the Owner, a change	
order will be issued	d for changes in the w	ork of the Contract in a	ccordance with the C	Contract Documents.	
Town of Charles					
Type of Change Proposed:					
г горозец.		X			
5	(Deletion of Work	(Addition of Work)	(Revision of	Work) (Other)	
		,	( <u>-</u>	, (53)	

Please see reverse side for a detailed description of the proposed change in Work.

### **DESCRIPTION OF PROPOSED CHANGE IN WORK:**

The project requires exposure of the existing stub-outs up slope of the existing stormwater inlets and connect the new letdown pipes to the limits of construction. The excavation at a few of the inlets shows the pipe trench was not installed after the stub-outs. This requires the previous closure cover along the alignment of the new letdown pipe be opened and build a trench for installation of the letdown piping. Reference CCIR-6 Response.

Please prepare a detailed proposal for cutting the pipe trench in areas where needed in order to extend the letdown piping. The proposal should detail the work required to excavate the waste along the proposed trench, install new liner and CDN for the letdown pipe to be installed as shown in the attached detail A. The pipe and connections to the existing stub-outs were previously included in the contract.

In addition, please include in your proposal detailed cost breakdown to extend the letdown pipe to the proposed anchor trench as shown in the attached drawing B.

The proposal should include all cost to the Contractor that is outside of his current contract for filling, grading and restoring the previously closed area and sodding the affected area.

ATTA	CHMENTS:	
	Description of Item Attached	No. of Copies
1.	Detail A- CCIR No. 6 Response	
2.	Detail B- CCIR No. 6 Response	-
3.		0
4.		6
5.		

**END OF REQUEST FOR PROPOSAL FORM** 

N.T.S.

NS.13322 133

CCIR - 6A

SHEET NO. SCALE PROJ. NO. **EXTEND STUB OUTS** CCIR-6

EXISTING ANCHOR TRENCH REMOVE EXISTING LINER AND CDN TO THE EXISTING ANCHOR TRENCH EXISTING LINER AND CDN XXXXXXXXXX EXISTING INLET


### STUB OUT EXTENSION NOTES:

- EXPOSE THE UPSLOPE STUB OUT ON EXISITING INLET STRUCTURES. CLEAN AND PREPARE AROUND THE EXISITING STUBOUT FOR CONNECTION TO THE EXCAVATE A PIPE TRENCH (DETAIL-30) UPSLOPE FROM STRUCTURES B-9, A-9, V-11, U-11, T-11, M-7, L-7, AND K-9 TO THE EXISITING ANCHOR TRENCH. NEW PIPE. PROTECT THE FABRIFORM FROM DAMAGE.
  - INSTALL LINER SYSTEM FOR THE ENTIRE OPEND UP TRENCH AND WELD TO THE EXISITNG LINER.
    - CONNECT THE NEW LETDOWNPIPE TO THE STUB-OUT USING SPLIT COUPLER (DETAIL 32)
      - BACKFILL, COVER AND SOD TO MATCH THE PREVIOUSLY CLOSED AREA AS REQUIRED.





NEEL-SCHAFFER CDF - SLURRY WALL LANDFILL
PHASE VII SIDESLOPE CLOSURE
SOLID WASTE MANAGEMENT DEPARTMENT
BREVARD COUNTY, FLORIDA



CCIR - 6

**EXTEND STUB OUTS** 

NS. 13325. 134 §

N.T.S.

SCALE: PROJ.

CCIR - 6B

SHEET NO.

NEEL-SCHAFFER CDF - SLURRY WALL LANDFILL
PHASE VII SIDESLOPE CLOSURE
SOLID WASTE MANAGEMENT DEPARTMENT
BREVARD COUNTY, FLORIDA