



Agenda Report

2725 Judge Fran Jamieson
Way
Viera, FL 32940

Consent

F.5.

10/25/2022

Subject:

Resolution to adopt the North Merritt Island Hydrologic and Hydraulic Study and Stormwater Model.

Fiscal Impact:

None

Dept/Office:

Natural Resources Management Department

Requested Action:

Adopt the Resolution accepting the North Merritt Island (NMI) Hydrologic and Hydraulic Study (HHS) and Model (Model) for use in the NMI Area in accordance with Chapter 62, Article X, Division 5, entitled Floodplain Protection.

Summary Explanation and Background:

Brevard County has documented increasing flooding impacts in the NMI area from tropical storms, hurricanes, and other storm events. This has resulted in damage to homes, negative effects on septic systems, and sections of major roads flooding, sometimes until impassable and blocking property access.

Recommendation 7 of the draft NMI Small Area Study proposes that Brevard County significantly improve the current Federal Emergency Management Agency (FEMA) stormwater model for NMI. It was further recommended that the Model be used to demonstrate whether proposed development would result in any adverse flooding impacts to properties or infrastructure.

Discussions of NMI-specific flood modelling study occurred at the August 2 and 15, 2018, Board meetings. On August 21, 2018, the Board approved the proposed upgrade of the NMI Model. This study was completed by Singhofen & Associates, Inc., under Task Order No. 20-4663-001-HHM.

The study spans 38 square miles, from the Barge Canal north to Nasa Parkway. An integrated surface water-groundwater model was created for this specific watershed. The Model will be used for analysis of current and future flooding conditions, and will be helpful as a base model when evaluating potential flood control and natural system improvement projects.

Section 62-3724(4) establishes stormwater criteria on NMI for the area from Hall Road, north to State Road 405, excluding federally owned lands (Area). Section 62-3724(4)(b) requires engineers of record to certify that proposed development will not increase flood stages, and will not increase the duration of the peak flood stages within the Area. Certification must be accompanied by a report supporting the certification. This report must include full engineering data and analysis, in compliance with good engineering practices, and any and

all applicable standards, criteria, and regulatory requirements, including the hydraulic and hydrologic modelling and analysis demonstrating that there is no impact. The HHS and Model, if approved, will serve as that required hydraulic and hydrologic modeling and analysis.

Section 62-3724(4)(d) allows a waiver from compensatory storage where the engineer of record certifies that the proposed design does not increase peak flood stage or duration, based on a stormwater model accepted by the Board of County Commissioners. Any such stormwater model must be based on best available data addressing, at minimum: water storage, water volume, groundwater elevations, peak stages, and peak rates for the Area. The HHS and Model, if approved, will serve as that required model.

This model will be updated as future development occurs thus it will remain current, retaining relevance as best available data as well as modeling for use by development interests as those development opportunities are considered. This model will allow for County staff and development interests to build upon the model as well as consider potential improvements to the drainage system without requiring a costly foundational recreation of the model in order to demonstrate the effects of a proposed development or other improvement.

Clerk to the Board Instructions:

None



Kimberly Powell, Clerk to the Board, 400 South Street • P.O. Box 999, Titusville, Florida 32781-0999

Telephone: (321) 637-2001

Fax: (321) 264-6972

Kimberly.Powell@brevardclerk.us

October 26, 2022

MEMORANDUM

TO: Virginia Barker, Natural Resources Management Director

RE: Item F.5., Resolution to Adopt the North Merritt Island Hydrologic and Hydraulic Study and Stormwater Model

The Board of County Commissioners, in regular session on October 25, 2022, approved and adopted Resolution No. 22-144, accepting the North Merritt Island (NMI) Hydrologic and Hydraulic Study (HHS) and Model for use in the NMI area in accordance with Chapter 62, Article X, Division 5, entitled Floodplain Protection. Enclosed is a certified copy of the Resolution.

Your continued cooperation is always appreciated.

Sincerely,

**BOARD OF COUNTY COMMISSIONERS
RACHEL M. SADOFF, CLERK**

Donna Scott
for: Kimberly Powell, Clerk to the Board

/tr

Encl. (1)

RESOLUTION NO: 2022-144

Resolution of the Board of County Commissioners to Adopt the North Merritt Island Hydrologic and Hydraulic Study and Model

WHEREAS, on December 5, 2019, the Board of County Commissioners of Brevard County, Florida (Board) adopted Section 62-3724, Development regulations, subsection (4), Code of Ordinances of Brevard County, Florida, for use in the North Merritt Island area; and

WHEREAS, Section 62-3723, General provisions, subsection (2), code of Ordinances of Brevard County, Florida, requires that "[d]evelopment within floodplain areas shall not have adverse impacts upon adjoining properties;" and,

WHEREAS, Section 62-3724, Development regulations, subsection (2)(a), Code of Ordinances of Brevard County, Florida, requires that "[d]evelopment within an estuarine floodplain shall not negatively impact adjacent properties or receiving water body quality;" and,

WHEREAS, Section 62-3724, Development regulations, subsection (4)(d), Code of Ordinances of Brevard County, Florida, states that "[a] waiver from the compensatory storage requirement may be granted by the county manager or designee where the engineer of record certifies that the proposed design does not increase peak flood stage or duration, based on a stormwater model accepted by the board of county commissioners. Any such stormwater model shall be based on best available data addressing, at minimum: water storage, water volume, groundwater elevations, peak stages, and peak rates for the area;" and,

WHEREAS, Consultant, Singhofen and Associates, Inc., produced a detailed Hydrologic and Hydraulic study and model of the North Merritt Island area suitable for use; and

WHEREAS, the use of the model could contribute to significantly improved stormwater management on North Merritt Island with the demonstration of project impacts.

NOW, THEREFORE, BE IT RESOLVED BY THE BOARD OF COUNTY COMMISSIONERS OF BREVARD COUNTY, FLORIDA, that:

The Board accepts the North Merritt Island Hydrologic and Hydraulic Study and Model, produced by Singhofen and Associates, Inc., and any future updates to the Model as approved by Brevard County Stormwater Program, for use in the North Merritt Island area in accordance with Chapter 62, Article X, Division 5, entitled Floodplain Protection.

Exhibit 1 is the North Merritt Island Hydrologic and Hydraulic Modeling and Study report, dated June 2022, and completed under Agreement No. 20-4663-001-HHM. This

report describes the purpose of this model and the required developmental data and processes.

This Resolution shall take effect immediately upon adoption.

DONE, ORDERED AND ADOPTED this 25th day of October, 2022.

BOARD OF COUNTY COMMISSIONERS
OF BREVARD COUNTY, FLORIDA

By: 

Kristine Zonka, Chair


approved by Board on: October 25, 2022

ATTEST:


Rachel M. Sadoff, Clerk

EXHIBIT 1

North Merritt Island H&H Modeling Study Report



June 2022



**CERTIFICATION BY A
REGISTERED PROFESSIONAL ENGINEER**

PROJECT NAME: North Merritt Island H&H Modeling Study Report - FINAL

I HEREBY CERTIFY THAT THE MATERIAL AND DATA CONTAINED IN THIS DOCUMENT WAS PREPARED UNDER THE SUPERVISION AND DIRECTION OF THE UNDERSIGNED, WHOSE SEAL AS A REGISTERED PROFESSIONAL ENGINEER IN THE STATE OF FLORIDA IS AFFIXED BELOW.

NAME: Allyson G. Hunt, P.E., CFM
COMPANY NAME: Singhofen & Associates, Inc.
ADDRESS: 11723 Orpington Street, Suite 100
Orlando, Florida 32817
TELEPHONE NUMBER: (407) 679-3001



Digitally signed
by Allyson G
Hunt
Date:
2022.06.30
16:30:40 -04'00'

This item has been electronically signed and sealed by Allyson G. Hunt, P.E., CFM, on 06/30/2022 using a SHA authentication code.

Printed copies of this document are not considered signed and sealed and the SHA authentication code must be verified on any electronic copies.

FLORIDA REGISTRATION NUMBER: 78531
CORPORATE CERTIFICATION NUMBER: 5112

Table of Contents

1.0	Introduction and Purpose	1
1.1	Authorization.....	1
1.2	Project Location and General Description.....	1
1.3	Purpose and Objectives.....	1
1.4	General Scope of Work.....	1
1.5	Electronic Deliverables	2
2.0	Data Collection.....	4
2.1	Existing Model and Infrastructure Data	4
2.2	Hydrologic & Hydraulic Data Collection.....	4
2.2.1	Soil Data:	4
2.2.2	Land Use Characterization	4
2.2.3	Rainfall Data	7
2.2.4	Stage Gage Data	7
2.3	Reference Documents	8
2.4	Groundwater Data Collection	10
2.4.1	SJRWMD Gage Data.....	10
2.4.2	East-Central Florida Transient Expanded Model.....	10
2.5	Field Survey Data	10
2.6	Digital Terrain Model.....	12
3.0	Watershed Inventory and Surface Water Model Development.....	13
3.1	Digital Terrain Model Development.....	13
3.1.1	Horizontal and Vertical Datum	13
3.1.2	Existing Topographic Information.....	13
3.1.3	Hydro-Corrections.....	13
3.1.4	Topographic Voids / Areas of New Development.....	15
3.1.5	QA/QC Process Description.....	19
3.2	Hydrologic Features.....	19
3.2.1	Subbasin Delineation Process	19
3.2.2	Land Use Characterization	20
3.2.3	Soil Characterization.....	20
3.2.4	Hydrologic Parameterization	21
3.3	Hydraulic Features.....	22
3.3.1	Preliminary Model Network Development Process.....	22
3.3.2	Hydraulic Parameterization	22
3.3.3	QA/QC Process Description.....	24
3.4	Overland Flow Model Features	24
3.4.1	Overland Flow Region Development.....	24

3.4.2	Breaklines & Interpolated Breaklines	24
3.4.3	Channel Features	27
3.4.4	Channel Control Volumes	27
3.4.5	Pond Control Volumes	28
3.4.6	Coves	28
3.4.7	2D Weirs	29
3.4.8	Interface Nodes	29
3.4.9	Roughness in 2D Areas	29
3.4.10	QA/QC Process Description	29
3.5	Boundary Conditions	29
4.0	Groundwater Model Development	31
4.1	Groundwater Region Development	31
4.2	Breaklines & Breakpoints	32
4.3	Groundwater Parameterization	32
4.4	Boundary Conditions	33
5.0	Field Data Acquisition Summary	35
5.1	Field Verification Efforts	35
5.2	Survey Needs Assessment	36
6.0	Model Calibration and Verification	38
6.1	Statistical Metrics	38
6.2	Model Calibration	40
6.2.1	Parameter Adjustments	40
6.3	Calibration Analysis	41
6.3.1	Gage SG1 Sykes Creek at Sea Ray Dr. – Calibration Results	42
6.3.2	Gage SG2 East Hall Rd. North – Calibration Results	43
6.3.3	Gage SG3 East Hall Rd. Pump House – Calibration Results	46
6.3.4	Gage SG4 East Hall Rd. Barge Canal Ditch – Calibration Results	47
6.3.5	Gage SG5 Chase Hammock at Judson Rd. – Calibration Results	48
6.3.6	Gage SG6 Crisafulli at Judson Rd. – Calibration Results	51
6.3.7	Gage SG7 East Crisafulli at Joseph Ct. – Calibration Results	53
6.3.8	Gage SG8 N Courtenay at Pine Island – Calibration Results	55
6.3.9	Gage SG9 Pine Island 1 Mile North of North Courtenay – Calibration Results	57
6.3.10	Gage SG10 Pine Island Harvey Grove Pump – Calibration Results	59
6.3.11	Gage SG11 Pine Island West – Calibration Results	61
6.3.12	Gage SG12 PICA South – Calibration Results	63
6.3.13	Gage SG13 W Hall Rd. West at N. Tropical Trail – Calibration Results	64
6.3.14	Gage SG17 PICA Basin – Calibration Results	66
6.3.15	Gage SG18 PICA Riverside – Calibration Results	68

North Merritt Island H&H Modeling Study

Table of Contents

6.3.16	Gage SG19 PICA North – Calibration Results	70
6.4	Verification Analysis.....	72
6.4.1	Gage SG1 Sykes Creek at Sea Ray Dr. – Verification Results	72
6.4.2	Gage SG2 East Hall Rd. North – Verification Results	73
6.4.3	Gage SG3 East Hall Rd. Pump House – Verification Results.....	75
6.4.4	Gage SG4 East Hall Rd. Barge Canal Ditch – Verification Results	76
6.4.5	Gage SG5 Chase Hammock at Judson Rd. – Verification Results.....	77
6.4.6	Gage SG6 Crisafulli at Judson Rd. – Verification Results	79
6.4.7	Gage SG7 East Crisafulli at Joseph Ct. – Verification Results	81
6.4.8	Gage SG8 N Courtenay at Pine Island – Verification Results	83
6.4.9	Gage SG9 Pine Island 1 Mile North of North Courtenay – Verification Results	85
6.4.10	Gage SG10 Pine Island Harvey Grove Pump – Verification Results	87
6.4.11	Gage SG11 Pine Island West – Verification Results	89
6.4.12	Gage SG12 PICA South – Verification Results	91
6.4.13	Gage SG13 W Hall Rd. West at N. Tropical Trail – Verification Results	93
6.4.14	Gage SG17 PICA Basin – Verification Results	95
6.4.15	Gage SG18 PICA Riverside – Verification Results.....	96
6.4.16	Gage SG19 PICA North – Verification Results.....	99
6.5	Calibration / Verification Conclusions	101
7.0	Existing Conditions Analysis.....	102
7.1	Existing Conditions Model Updates.....	102
7.2	Critical Duration Analysis	103
7.3	Existing Conditions Analysis and Floodplain Generation.....	108
7.3.1	Design Storm Simulations.....	108
7.3.2	Floodplain Mapping	108
8.0	Discussion.....	109
8.1	Floodplain Discussion	109
8.2	Groundwater Discussion	111

Appendices

- Appendix A North Merritt Island HydroDEM Update Memo (prepared by Atkins, 2020)
- Appendix B ICPR4 Lookup and Reference Tables
- Appendix C Development of Input Rainfall and Stage Conditions Data for North Merritt Island (prepared by Applied Ecology, Inc., 2021)
- Appendix D Field Data Collection Memorandum (prepared by Atkins, 2020)

List of Figures

Figure 1.1: Vicinity Map of the NMI Watershed	3
Figure 2.1: Soils Map	5
Figure 2.2: Landuse Map	6
Figure 2.3: Spatial Location of Reference Documents	9
Figure 2.4: SJRWMD Well Location	10
Figure 2.5: ECTFX Model Domain	11
Figure 2.6: Cross Section Survey Locations	11
Figure 3.1: Missing Topographic Information	13
Figure 3.2: Channel Hydro-Correction Based on Surveyed Cross Section	14
Figure 3.3: Natural Ponding Hydro-Correction	14
Figure 3.4: Hydro-Corrections in Existing Stormwater Ponds	15
Figure 3.5: Topographic Voids on Original 2007 Digital Terrain	16
Figure 3.6: Example of Topographic Void	17
Figure 3.7: Corrected Topographic Void of New Development	18
Figure 3.8: Corrected Topographic Void of New Channel Excavation	18
Figure 3.9: Effective vs. Expanded Model Domain and ERP Update Areas	20
Figure 3.10: Roadway Breaklines	25
Figure 3.11: Channel Breaklines	25
Figure 3.12: Pond Breaklines	26
Figure 3.13: Breaklines in Ridges/Troughs	26
Figure 3.14: Interpolated Breaklines	26
Figure 3.15: Channel Feature	27
Figure 3.16: Channel Control Volume on DEM	27
Figure 3.17: Pond Control Volumes 2D Region	28
Figure 3.18: Pond Control Volumes 1D Basin	28
Figure 3.19: Cove and Cove Point	29
Figure 3.20: Boundary Node and Line Locations	30
Figure 4.1: Groundwater Regions	31
Figure 4.2: Groundwater Breakpoint & Breakline Placement	32
Figure 4.3: ECFTX Groundwater Data Grid	33
Figure 4.4: Groundwater Boundary Stage Line Locations	34
Figure 5.1: North Merritt Island Field Data Collection Sites	35
Figure 6.1: Brevard County Gage Locations	39
Figure 6.2: SG1 Sykes Creek at Sea Ray Dr. Calibration#1 Comparisons	42
Figure 6.3: SG2 East Hall Rd. North Calibration#1 Comparisons	44
Figure 6.4: SG2 East Hall Rd. North Calibration#2 Comparisons	45
Figure 6.5: SG3 East Hall Rd. North Calibration#1 Comparisons	46
Figure 6.6: SG4 East Hall Rd. Barge Canal Ditch Calibration#1 Comparisons	47
Figure 6.7: Gage SG5 Chase Hammock at Judson Rd. Calibration#1 Comparisons	49
Figure 6.8: Gage SG5 Chase Hammock at Judson Rd. Calibration#2 Comparisons	50
Figure 6.9: Gage SG6 Crisafulli at Judson Rd. Calibration#1 Comparisons	51
Figure 6.10: Gage SG6 Crisafulli at Judson Rd. Calibration#2 Comparisons	52

North Merritt Island H&H Modeling Study

Table of Contents

Figure 6.11: Gage SG7 East Crisafulli at Joseph Ct. Calibration#1 Comparisons	53
Figure 6.12: Gage SG7 East Crisafulli at Joseph Ct. Calibration#2 Comparisons	54
Figure 6.13: Gage SG8 N Courtenay at Pine Island Calibration#1 Comparisons	55
Figure 6.14: Gage SG8 N Courtenay at Pine Island Calibration#2 Comparisons	56
Figure 6.15: Gage SG9 Pine Island 1 Mile North of North Courtenay Calibration#1 Comparisons	57
Figure 6.16: Gage SG9 Pine Island 1 Mile North of North Courtenay Calibration#2 Comparisons	58
Figure 6.17: Gage SG10 Pine Island Harvey Grove Pump Calibration#1 Comparisons	59
Figure 6.18: Gage SG10 Pine Island Harvey Grove Pump Calibration#2 Comparisons	60
Figure 6.19: Gage SG11 Pine Island West Calibration#1 Comparisons	61
Figure 6.20: Gage SG11 Pine Island West Calibration#2 Comparisons	62
Figure 6.21: Gage SG12 PICA South Calibration #1 Comparisons	63
Figure 6.22: Gage SG13 W Hall Rd. West at N. Tropical Trail Calibration #1 Comparisons.....	64
Figure 6.23: Gage SG13 W Hall Rd. West at N. Tropical Trail Calibration #2 Comparisons.....	65
Figure 6.24: Gage SG17 PICA Basin Calibration #1 Comparisons	67
Figure 6.25: Gage SG18 PICA Riverside Calibration #1 Comparisons.....	68
Figure 6.26: Gage SG18 PICA Riverside Calibration #2 Comparisons.....	69
Figure 6.27: Gage SG19 PICA North Calibration #1 Comparisons.....	70
Figure 6.28: Gage SG19 PICA North Calibration #2 Comparisons.....	71
Figure 6.29: Gage SG1 Sykes Creek at Sea Ray Dr. Verification #1 Comparisons.....	72
Figure 6.30: Gage SG2 East Hall Rd. North Verification #1 Comparisons.....	73
Figure 6.31: Gage SG2 East Hall Rd. North Verification #2 Comparisons.....	74
Figure 6.32: Gage SG3 East Hall Rd. Pump House Verification #1 Comparisons	75
Figure 6.33: Gage SG4 East Hall Rd. Barge Canal Ditch Verification #1 Comparisons.....	76
Figure 6.34: Gage SG5 Chase Hammock at Judson Rd. Verification #1 Comparisons	77
Figure 6.35: Gage SG5 Chase Hammock at Judson Rd. Verification #2 Comparisons	78
Figure 6.36: Gage SG6 Crisafulli at Judson Rd. Verification #1 Comparisons.....	79
Figure 6.37: Gage SG6 Crisafulli at Judson Rd. Verification #2 Comparisons.....	80
Figure 6.38: Gage SG7 East Crisafulli at Joseph Ct. Verification #1 Comparisons.....	81
Figure 6.39: Gage SG7 East Crisafulli at Joseph Ct. Verification #2 Comparisons.....	82
Figure 6.40: Gage SG8 N Courtenay at Pine Island Verification #1 Comparisons.....	83
Figure 6.41: Gage SG8 N Courtenay at Pine Island Verification #2 Comparisons.....	84
Figure 6.42: Gage SG9 Pine Island 1 Mile North of North Courtenay Verification #1 Comparisons.....	85
Figure 6.43: Gage SG9 Pine Island 1 Mile North of North Courtenay Verification #2 Comparisons.....	86
Figure 6.44: Gage SG10 Pine Island Harvey Grove Pump Verification #1 Comparisons.....	87
Figure 6.45: Gage SG10 Pine Island Harvey Grove Pump Verification #2 Comparisons.....	88
Figure 6.46: Gage SG11 Pine Island West Verification #1 Comparisons	89
Figure 6.47: Gage SG11 Pine Island West Verification #2 Comparisons	90
Figure 6.48: Gage SG12 PICA South Verification #1 Comparisons	92
Figure 6.49: Gage SG13 W Hall Rd. West at N. Tropical Trail Verification #1 Comparisons	93
Figure 6.50: Gage SG13 W Hall Rd. West at N. Tropical Trail Verification #2 Comparisons	94
Figure 6.51: Gage SG17 PICA Basin Verification #1 Comparisons	95
Figure 6.52: Gage SG18 PICA Riverside Verification #1 Comparisons	97
Figure 6.53: Gage SG18 PICA Riverside Verification #2 Comparisons	98

Figure 6.54: Gage SG19 PICA North Verification #1 Comparisons	99
Figure 6.55: Gage SG19 PICA North Verification #2 Comparisons	100
Figure 7.1: NOAA Trident Pier Gage Datum Information	103
Figure 7.2: Critical Duration Analysis (10-year event)	105
Figure 7.3: Critical Duration Analysis (25-year event)	106
Figure 7.4: Critical Duration Analysis (100-year event)	107
Figure 8.1: 10-Year, 24-hr Floodplain along E. Crisafulli Rd.	109
Figure 8.2: 10-Year, 24-hr Floodplain along W. Crisafulli Rd.	109
Figure 8.3: 10-Year, 24-hr Floodplain along E. Hall Rd.	109
Figure 8.4: FEMA vs. 100-year, 24-hr Floodplain Comparison	110
Figure 8.5: Plan and Profile of Groundwater Model Results at Hall Road	111
Figure 8.6: Groundwater Time-Series Graph for Nodes 13444, 15366, and 15379 from 2017 Calibration / Verification Model results	112

List of Tables

Table 2.1: Land Use Composition Summary	7
Table 3.1: NRCS Soil Data Parameters	21
Table 3.2: Summary of Structural Model Elements by Type	22
Table 3.3: Manning's n Lookup Table for Channels	23
Table 3.4: Manning's n Lookup Table for Pipes	23
Table 3.5: Structural Weir Coefficients	23
Table 3.6: Weir Coefficients	24
Table 5.1: Summary of Structures Requiring Survey and/or Maintenance	36
Table 6.1: Statistical Metrics	38
Table 6.2: Calibration Simulation #2 Additional Boundary Conditions	41
Table 6.3: Calibration Statistical Metrics SG1	43
Table 6.4: Calibration Statistical Metrics SG2	45
Table 6.5: Calibration Statistical Metrics SG3	47
Table 6.6: Calibration Statistical Metrics SG4	48
Table 6.7: Calibration Statistical Metrics SG5	50
Table 6.8: Calibration Statistical Metrics SG6	52
Table 6.9: Calibration Statistical Metrics SG7	54
Table 6.10: Calibration Statistical Metrics SG8	56
Table 6.11: Calibration Statistical Metrics SG9	58
Table 6.12: Calibration Statistical Metrics SG10	60
Table 6.13: Calibration Statistical Metrics SG11	62
Table 6.14: Calibration Statistical Metrics SG12	64
Table 6.15: Calibration Statistical Metrics SG13	66
Table 6.16: Calibration Statistical Metrics SG17	67
Table 6.17: Calibration Statistical Metrics SG18	69
Table 6.18: Calibration Statistical Metrics SG19	71
Table 6.19: Verification Statistical Metrics SG1	73

North Merritt Island H&H Modeling Study

Table of Contents

Table 6.20: Verification Statistical Metrics SG2.....	74
Table 6.21: Verification Statistical Metrics SG3.....	76
Table 6.22: Verification Statistical Metrics SG4.....	77
Table 6.23: Verification Statistical Metrics SG5.....	78
Table 6.24: Verification Statistical Metrics SG6.....	80
Table 6.25: Verification Statistical Metrics SG7.....	82
Table 6.26: Verification Statistical Metrics SG8.....	84
Table 6.27: Verification Statistical Metrics SG9.....	86
Table 6.28: Verification Statistical Metrics SG10.....	88
Table 6.29: Verification Statistical Metrics SG11.....	91
Table 6.30: Verification Statistical Metrics SG12.....	92
Table 6.31: Verification Statistical Metrics SG13.....	94
Table 6.32: Verification Statistical Metrics SG17.....	96
Table 6.33: Verification Statistical Metrics SG18.....	98
Table 6.34: Verification Statistical Metrics SG19.....	100
Table 7.1: Summary of Drainage Structure Updates for Post-2017 Improvements.....	102
Table 7.2: Critical Duration Storm Rainfall Amounts (inches).....	103
Table 7.3: Critical Duration Storm Analysis Summary.....	104
Table 7.4: Design Storm Rainfall Amounts (inches).....	108

Abbreviations and Acronyms

The following is a list of acronyms and /or abbreviations used throughout this report:

1D / 2D	1 or 2 Dimensional
AEI	Applied Ecology, Inc.
CFWI	Central Florida Water Initiative
CMS	Coastal Modeling System
County	Brevard County Natural Resources Management Department
DEM	Digital Elevation Model
District	Southwest Florida Water Management District
ECTFX	East-Central Florida Transient Expanded
ERP	Environmental Resource Permit
FDEP	Florida Department of Environmental Protection
FDOT	Florida Department of Transportation
FEMA	Federal Emergency Management Agency
FIPS	Federal Information Processing Standards
ft	Feet/Foot
GDB	Geodatabase
GIS	Geographic Information System
GWIS	Geographic Watershed Information System
GW-SW	Groundwater-Surface Water
H&H	Hydrologic & Hydraulic
h:v	Horizontal:Vertical
i.e.	That is
ICPR	Interconnected Channel and Pond Routing
IRL	Indian River Lagoon
JEA	Jones Edmunds and Associates, Inc.
KM	Kilometer
LDC	Land Development Code
LiDAR	Light Detection And Ranging
LU	Lookup (Table)
M&E	Morgan & Eklund, Inc.
MAE	Mean Absolute Error
ME	Mean Error
MLLW	Mean-Lower-Low Water
NASA	National Aeronautics and Space Administration
NAD	North American Datum
NAVD88	North American Vertical Datum of 1988
NEXRAD	Next Generation Weather Radar
NGVD	National Geodetic Vertical Datum
NGVD29	National Geodetic Vertical Datum of 1929

NHD	USGS National Hydrography Dataset
NMI	North Merritt Island
NOAA	National Oceanic and Atmospheric Administration
NRCS	Natural Resources Conservation Service
NSE	Nash-Sutcliffe Efficiency
NWL	Normal Water Level
QA	Quality Assurance
QA/QC	Quality Assurance / Quality Control
QC	Quality Control
RMSE	Root Mean Square Error
SAI	Singhofen & Associates, Inc.
SF	Square Feet/Foot
SFWMD	South Florida Water Management District
SJRWMD	St. Johns River Water Management District
Sq.	Square
SR	State Road
SW-GW	Surface Water-Groundwater
SWAMP	Stormwater Asset Management Program
SWFWMD	Southwest Florida Water Management District
T _c	Time of Concentration
USGS	United States Geological Survey
YR	Year

1.0 Introduction and Purpose

1.1 Authorization

The North Merritt Island H&H Modeling Study is being performed by Singhofen & Associates Inc. (SAI) for the Brevard County Natural Resources Management Department (County) under Agreement No. 20-4663-001-HHM.

1.2 Project Location and General Description

The North Merritt Island (NMI) Watershed is located in Brevard County and spans approximately 38 square miles, from the Barge Canal north to Nasa Parkway (see **Figure 1.1**). The watershed is bound by NASA's Kennedy Space Center to the north and by the Merritt Island National Wildlife Refuge to the east.

The NMI watershed drains into three areas: the Indian River Lagoon (IRL) to the west, the Banana River to the east, and the Canaveral Barge Canal to the south through the Sykes Creek. Much of the watershed area is being converted to suburban landscape that has changed the natural drainage patterns. Dual ridges run north-south along N. Courtney Pkwy/SR 3 to the west and the federal property to the east, creating a broad low-lying depressional area that encompasses much of the island. This depressional area is relatively flat and provides little relief, relying primarily on man-made drainage works such as sub-division ponds and open cut ditches to interconnect low lying areas to their ultimate outfalls. Compounding the lack of relief are the generally poorly drained soils that are dominant except for select areas along the higher elevation ridges, and a shallow groundwater table. Although retrofit projects have been undertaken by the County to some degree of success, flood duration and extent can be compounded by issues outside of the County's control. Due to the interconnected nature of the IRL and Banana River with the groundwater and surface water within the watershed, increases in the boundary/tailwater conditions can result in adverse impacts by removing natural soils storage, taking over natural and man-made storage, and inhibiting discharge by reducing the already limited hydraulic gradient. These issues, along with storm surge, can compound to cause extended periods of inundation for property owners that can be surrounded by flood waters that cannot be solved with portable pumps, as the water has nowhere to go.

1.3 Purpose and Objectives

This project involves the development of an integrated surface water-groundwater (SW-GW) model (ICPR4) for the NMI watershed. The completed model will yield results for analysis of current and future flooding conditions and will serve as a base model to evaluate potential flood control and natural system improvement projects and other physical changes to watershed. The model will also consider historical conditions in the IRL and Banana River as boundary conditions for the NMI watershed.

This is accomplished by completing the following objectives:

- Collect and review pertinent data from the County and/or local communities
- Acquire field data measurements
- Develop a detailed hydrologic and hydraulic (H&H) model to characterize storm events throughout the watershed, including 1D, 2D, and groundwater features
- Calibrate and verify hydrologic and hydraulic (H&H) model

1.4 General Scope of Work


This memorandum summarizes the data collection and model development work completed for the project to date. The electronic deliverable is included on a hard drive accompanying this Model Development Memorandum. The general scope of work for these tasks is presented below:

- **Task 1: Data Collection and Review** – This task includes collecting and reviewing data pertinent to the model development efforts from the applicable agencies and developing a data catalog to store all data collected for the project along with spatial representation of the data where applicable.

- **Task 2: Watershed Evaluation – Initial Desktop Model Element Development** – This task includes the spatial development of the model network and establishing boundary conditions. Subtasks include digital elevation model (DEM) modifications for topographic voids and hydro-corrections, existing model data migration and quality control (QC), model network development of 1D, 2D, and groundwater features, and coastal boundary evaluation/trend analysis.
- **Task 3: Field Data Acquisition** – This task involves conducting field reconnaissance to verify drainage patterns and structure information at identified locations, identifying survey and maintenance needs as well.
- **Task 4: Model Hydraulic and Hydrologic Parameterization** – This task involved parameterizing the model network developed under Task 2.
- **Task 5: Model Setup, Execution, Debug, and Stabilization** – Only Subtask 5.1 is included in this phase of the work. Subtask 5.1 involves generating the Interconnected Channel and Pond Routing version 4 (ICPR4) model from the project Geographic Watershed Information System (GWIS) geodatabase.

1.5 Electronic Deliverables

This memorandum accompanies electronic data related to the development of the existing conditions North Merritt Island watershed model. This data includes: ICPR4 H&H model, model features in GIS (GWIS format), supporting model data in GIS (soils, landuse, etc.), the topographic digital elevation model (DEM), data collection portion of the North Merritt Island study including GIS features and reference documents (i.e., plans, reports, surveys, etc.) that are being used to develop the preliminary model elements. The project deliverables are submitted within the following directory structure:



North Merritt Island H&H Modeling Study

Section 1.0 – Introduction and Purpose




Figure 1.1: Vicinity Map of the NMI Watershed

2.0 Data Collection

2.1 Existing Model and Infrastructure Data

Model Data: Several ICPR3 models along with accompanying GIS data were provided by the County to serve as a base for the model development efforts. The following information was provided:

- **NMI_BREVARD_w_NASA.ICP:** This is the most current H&H model of the NMI watershed as of the start of this project, which includes updates conducted by DRMP. This model will serve as a basis for the ICPR4 model development.
- **With_Hall&Chase&Crisafulli_Pumps.ICP:** Design model for the Hall Road, Chase Hammock, and Crisafulli Road pump station projects. This ICPR3 model was based on the *NMI_BREVARD_w_NASA.ICP* model. It should be noted that of the three pump station designs included in this model, only the Hall Road pump station was constructed.
- **NMI_Brevard.gdb:** This is the model spatial geodatabase accompanying the NMI watershed model (*NMI_BREVARD_w_NASA.ICP*).
- **DRMP_Node.shp, DRMP_Reach.shp, Sub-basins.shp:** These shapefiles reflect the additional model features incorporated as part of the DRMP updates.

It should be noted that the GIS files provided were incomplete when compared to the model. The spatial datasets were missing over 30 basins and more than 10 nodes and links. Data included in the *NMI_BREVARD_w_NASA.ICP* model is assumed to be correct as-is, as directed by the County.

County Stormwater Infrastructure Database: The County provided the current Stormwater Asset Management Program (SWAMP) database, a geospatial database of stormwater features throughout the County. The SWAMP geodatabase (*Natural_Resources.gdb*) includes spatial location, geometry, size information, and elevation data where available. The County has indicated that all vertical information in the SWAMP database is in NAVD88 and is accurate.

In accordance with direction from the County, where data discrepancies exist between the ICPR3 model and the SWAMP database, the model information is to take precedence. Field verification will be conducted where necessary to resolve significant discrepancies based on engineering judgement.

2.2 Hydrologic & Hydraulic Data Collection

Data collected related to the hydrological characteristics of the watershed are summarized below. An electronic copy of this data is provided with the electronic deliverable accompanying this report.

2.2.1 Soil Data: Soil layers from the United States Department of Agriculture Natural Conservation Resources Service (NRCS) were obtained for this project (2019). The soils layer indicates that only 7% of the soils within the watershed are well-drained, type-A soils. Over 80% of the soils within the watershed are hydrologic soil group A/D, B/D, or C/D. These soils are well-drained to moderately drained during dry conditions and poorly drained during wet conditions. A soils map of the current NRCS soils data is included as **Figure 2.1**.

2.2.2 Land Use Characterization: Land use data (2014) was obtained from SJRWMD. The data set was updated by the SAI Team based upon a review of the 2020 high-resolution aerial imagery. The land use classifications are based on the Florida Land Use, Land Cover Classification System. The land use for the watershed is presented in **Figure 2.2**. The land use breakdown for the study area is provided in **Table 2.1**.

North Merritt Island H&H Modeling Study

Section 2.0 – Data Collection




Figure 2.1: Soils Map

North Merritt Island H&H Modeling Study

Section 2.0 – Data Collection




Figure 2.2: Landuse Map

Table 2.1: Land Use Composition Summary

Landuse	Total Area (acres)	% of Watershed
Residential	2,869	13.2%
Commercial and Services	216	1.0%
Institutional and Build-up	688	3.2%
Open Land	82	0.4%
Agriculture	1,391	6.4%
Rangeland	5,075	23.3%
Upland Forests	1,510	6.9%
Water	1,319	6.1%
Wetlands	8,272	38.0%
Disturbed Land	38	0.2%
Transportation, Communications, Utilities	331	1.5%

2.2.3 Rainfall Data: Both rain gage and Next Generation Weather Radar (NEXRAD) radar rainfall data were obtained to evaluate predicted rainfall within the watershed. Rain gage data was obtained in 15-minute intervals from the SJRWMD for rain gages located at Ransom Road and Kiwanis Park. NOAA rain gages located at Cape Canaveral, Rockledge, and Merritt Island were obtained in daily intervals, and rain gage data from the KSC Spaceport Weather Archive was obtained for the North Merritt Island Field Mill in hourly intervals. NEXRAD radar rainfall estimates were obtained from SJRWMD in 1-hour intervals (3.7 km² pixel grid), and from NOAA for the KMLB Melbourne station in 5-minute intervals (0.15 km² grid).

This information will be used during model calibration and forecasting efforts. Details on the processing of the above data for use in this study will be discussed in the Model Calibration Summary Memorandum.

2.2.4 Stage Gage Data: Historical stage data was collected to establish boundary conditions for the watershed model and for future calibration/validation efforts. After significant evaluation of available water level datasets and sensors, it was decided that the most scientifically valid approach was to provide two timeseries of stage level conditions bounding the study area on the east (Banana River Lagoon) and the west (Indian River Lagoon). In order to provide this information, data was collected from the following sources:

- Brevard County Stormwater Program: Staff gage data within the study area, including daily surface water stage levels.
- United States Geological Survey (USGS) National Water Information System: Haulover Canal stage levels (15-minute intervals)
- NOAA: Trident Pier Data continuous Atlantic Ocean elevation dataset
- SJRWMD: Indian River Lagoon continuous sensor stage data for Titusville, Cocoa Beach, Banana River, Indian Harbor Beach, and Melbourne

Detailed information on the processing of this data will be included in **Section 3.5** of this report.

2.3 Reference Documents

SAI obtained reference documents associated with 203 Environmental Resource Permits (ERPs) including for example, record drawings, construction plans, reports, and survey data. The ERP data was downloaded from the SJRWMD WMIS website. Each of these data sets were cataloged and saved in the reference documents folder (Support_Data\1_Watershed_Evaluation\Reference_Documents*). The reference documents were named using the following naming convention:

NMI_XXX_YY_Z

- "XXX" represents a sequential reference number assigned to the data
- "YY" represents the document type code
 - RD = record drawings/as-builts
 - CP = construction plans
 - RPT = report
 - SD = survey drawing or survey data
 - GIS = GIS files
 - MD = model data
 - PHO = aerial orthophotos
 - MI = miscellaneous information
 - MPI = miscellaneous permit information
- "Z" represents the sequence number (01, 02, etc.) for ERPs with more than one of the same document type code.

Many ERPs have several different document types. When this happens, the one with the most reliable or beneficial data is referenced; in most cases this will be a record drawing, unless there are no record drawings/as-builts available. Some ERPs may contain both record drawings and construction plans, or multiple sets of construction plans.

Each reference document is represented spatially in the reference documents geodatabase, included in the electronic deliverables accompanying this report. A polygon was drawn to show the approximate extents of each reference document. Reference document polygons are shown in **Figure 2.3**.

North Merritt Island H&H Modeling Study

Section 2.0 – Data Collection




Figure 2.3: Spatial Location of Reference Documents

2.4 Groundwater Data Collection

Groundwater-Surface Water (GW-SW) interaction has been observed in the NMI watershed. As such, the model developed for this study will be an integrated GW-SW model. Data collection for the groundwater characteristics within the watershed included obtaining regional groundwater model data and gage data.

2.4.1 SJRWMD Gage Data: Gage data was obtained from the SJRWMD Upper Floridan Aquifer Well located at Kings Park in Merritt Island (ID: BR2115). Data was collected for the surficial aquifer (POR 3/12/2009-8/11/2020) and for the upper Floridan (POR 12/4/1985-8/11/2020). See **Figure 2.4**.



Figure 2.4: SJRWMD Well Location

2.4.2 East-Central Florida Transient Expanded Model: The East-Central Florida Transient Expanded (ECTFX) MODFLOW Model was prepared in February 2020 as part of the Central Florida Water Initiative (CFWI). The CFWI was a collaborative effort between the SJRWMD, SFWMD, SWFWMD, FDEP, and other public agencies and stakeholders. Although the CFWI includes only Central Florida counties, the model boundaries extend east into and beyond Brevard County, including the North Merritt Island watershed. **Figure 2.5** on the following page is an excerpt from the ECTFX February 2020 Report depicting the model extents.

2.5 Field Survey Data

The County requested that the SAI Team obtain survey data for several channel systems throughout the watershed that had recently been dredged and/or cleared of vegetation. This included a total of eight (8) channel cross sections throughout the watershed, including ditches along Hall Road, Judson Road, Pine Island Road, and Chase Hammock Road. This work was conducted in August 2020 by Morgan & Eklund, Inc. (M&E). Cross sections provided included both the ground surface and bottom of muck elevations at each cross section. **Figure 2.6** on the following page shows the location of the 8 cross sections. The survey data is included in the electronic deliverable accompanying this report.

North Merritt Island H&H Modeling Study

Section 2.0 – Data Collection




Figure 2.5: ECTFX Model Domain



Figure 2.6: Cross Section Survey Locations

2.6 Digital Terrain Model

The County provided LiDAR-derived terrain data for the NMI watershed dated 2007 (flight dates: 09/15/2007 - 09/30/2007). This Digital Elevation Model (DEM), titled *1_ftNMI.tif*, along with associated LiDAR data files and supporting features (i.e., breaklines, hydrographic features) will serve as the base terrain data for this study.

The NMI Study model will address SW-GW interactions within the region. The model will rely heavily on representative terrain data. As such, the DEM as provided will require manual modifications for several reasons:

- **Missing Data:** The original DEM surface provided by the County did not include topographic information for the Indian River Lagoon, Banana River Lagoon, Barge Canal, and several channel features directly connected to these waterbodies.
- **Hydro-Corrections:** The existing DEM provided by the County did not include bathymetric data within waterbodies (ponds and wetlands) as well as channel features.
- **Areas of New Development:** The existing DEM is based on data collected in 2007. Several areas of new development have occurred since then, resulting in new fill and stormwater facilities.

The approach to conducting the referenced DEM modifications is discussed in **Section 3** of this Study.

3.0 Watershed Inventory and Surface Water Model Development

3.1 Digital Terrain Model Development

The County provided LiDAR terrain data for the NMI watershed dated 2007 (flight dates: 09/15/2007 - 09/30/2007). This Digital Elevation Model (DEM), titled 1_ftNMI.tif, along with associated LiDAR data files and supporting features (i.e., breaklines, hydrographic features) served as the base for all DEM modifications conducted as part of the study.

3.1.1 Horizontal and Vertical Datum: Topographic data was provided in the North American Vertical Datum of 1988 (NAVD88) for vertical information (feet) and in the North American Datum (NAD) of 1983 for horizontal (feet). A conversion factor of -1.30 feet was used to convert data in NGVD29 to NAVD88. All topographic data were projected in State Plane Florida East FIPS 0901 (Feet – HARN).

3.1.2 Existing Topographic Information: The DEM provided by the County was based on LiDAR flown in September 2007 and has a grid resolution of 5-feet. The surface extends from NASA Parkway to the north to SR 528 to the south but does not include the water surface in the Indian River Lagoon, Banana River, and connected waters.

3.1.3 Hydro-Corrections: The 2007 DEM elevations within wetlands and waterbodies reflect the water surface at the time the region was flown. Hydro-corrections were made to estimate bathymetry data in these areas of the watershed to better represent key features and to promote better interaction between the surface water and groundwater model elements. Hydro-correction efforts are summarized below. For additional detail on these efforts, please refer to the *North Merritt Island HydroDEM Update Memo (Atkins, September 2020)* provided in **Appendix A**.

Boundary Waterbodies: The original DEM surface provided by the County did not include any topographic information for the Indian River Lagoon, Banana River Lagoon, Canaveral Barge Canal, and several channel features directly connected to these waterbodies. **Figure 3.1** depicts the areas missing topographic information, shown in green.



Figure 3.1: Missing Topographic Information

North Merritt Island H&H Modeling Study

Section 3.0 – Watershed Inventory and Surface Water Model Development

Data extracted from NOAA navigational charts and datum information for the Trident Pier were used to estimate topographic information for the IRL and Banana River. NOAA navigational charts provided depths, which were referenced to the Mean-Lower-Low Water (MLLW) elevation. Using the Trident Pier to establish a reference elevation for the MLLW, a datum conversion factor of -2.83 feet was used to convert the navigational depths to an elevation in NAVD88.

Channel Hydro-Corrections: Channel areas were extended below the water surface to allow groundwater interaction. Interior DEM channel updates were based on channel invert elevations and geometry, as determined from cross section survey data provided by Morgan & Eklund, the existing ICPR3 model, and the SWAMP database. An example of channel hydro-corrections is shown below in **Figure 3.2**.




Figure 3.2: Channel Hydro-Correction Based on Surveyed Cross Section

Natural Ponding Hydro-Corrections: In areas identified in the DEM as natural ponding areas, updates were based on the extent of open water shown in the DEM and aerial imagery to estimate the extent and depth of ponded water. For the majority of these areas, a depth of 3-feet was assumed, which is consistent with nearby canals and provides sufficient connection for the groundwater model to interact with the surface water elements. The exception to this assumption is the interconnected lakes west of the Pine Island Stormwater Facility, where a depth of 5-feet was used based on connected channel inverts. The DEM was then tapered down from a 0-ft depth at the water's edge to the approximated depth at the center. An example of these hydro-corrections is shown below in **Figure 3.3**.




Figure 3.3: Natural Ponding Hydro-Correction

Developed Area Hydro-Corrections: As with wetlands, the DEM surface in stormwater ponds is reflective of the water surface at the time of the LiDAR flight. To encourage groundwater interaction, ponds in developed areas were extracted down from the water surface using a uniform assumption based on County and WMD development criteria. It was assumed that the water surface shown in the DEM was close to the established normal water level (NWL) for each pond. Using the standard criteria of a 5:1 (horizontal:vertical) pond slope and the water surface polygon associated with the 2007 DEM, the SAI Team extracted down the ponds in developed areas uniformly using the criteria below:

- 5:1 (h:v) slope from the water surface to 2-ft below the water surface
- 2:1 (h:v) slope from 2-ft below the water surface down for another 6-ft, resulting in a total pond depth of 8-feet below the water surface.

This approach allowed for a streamlined process of estimating bathymetry data for stormwater ponds in developed areas and is consistent with development criteria for the region. Exceptions for key locations were made, such as the Pine Island Conservation Area ponds, which were extracted down from the water surface based on construction plan and as-built survey data. **Figure 3.4** shows an example of extracted stormwater ponds in a developed area of the watershed.




Figure 3.4: Hydro-Corrections in Existing Stormwater Ponds

3.1.4 Topographic Voids / Areas of New Development: A 2D water surface model relies heavily on accurate terrain data. Given the age of the DEM available for the watershed, identifying areas of new development and topographic voids was critical. For the purposes of this evaluation, topographic voids are defined as those areas where available digital topographic information (2007 DEM) does not accurately describe the terrain as it exists today. Topographic voids result from such things as land alterations, new development, and missing data. Identified topographic voids and areas of new development within the watershed are depicted in **Figure 3.5**. An example of a topographic void is shown in **Figure 3.6**.

North Merritt Island H&H Modeling Study

Section 3.0 – Watershed Inventory and Surface Water Model Development




Figure 3.5: Topographic Voids on Original 2007 Digital Terrain




Figure 3.6: Example of Topographic Void

Evaluation of ground cover changes was conducted by comparing the DEM to aerial imagery in a systematic fashion by visually panning through the watershed while displaying both the DEM and aerials for a side-by-side comparison. Using 2020 aerial imagery to match the date-certain established in the scope of work, SAI identified 13 total topographic voids. Of these, eight were considered areas of new development, four were considered areas of land excavation, such as stormwater pond expansion or construction, and one was caused by tree cover obscuring an existing pond. The identified topographic voids within the watershed are provided in the *Topographic_Voids.gdb* geodatabase.

Topographic voids were manually corrected for this study. For each topographic void, construction plans or record drawings (if available) were georeferenced and storage areas were delineated. Delineated contours were used as breaklines to “burn-in” the storage ponds into the existing terrain data. To account for fill placed in new development areas, a minimum fill elevation – typically the top of bank elevation for stormwater ponds – was established and applied to the rest of the development. Examples of corrected topographic voids are shown in **Figures 3.7 and 3.8**.




Figure 3.7: Corrected Topographic Void of New Development



Figure 3.8: Corrected Topographic Void of New Channel Excavation

3.1.5 QA/QC Process Description: Several QC checks were performed on the revised DEM at various points throughout the revision process. These checks included systematic visual inspections of the watershed and geospatial tools used to compare two DEM data sets. At each DEM modification, the “Minus” tool was utilized in GIS to compare the previous DEM grid with the updated grid to quickly identify differences between the two and help focus visual inspections. Comments related to the DEM modifications were stored in an internal Comments GDB to ensure they were adequately addressed.

3.2 Hydrologic Features

Hydrologic Features of North Merritt Island include features that contribute to the conversion of rainfall into runoff and subsequent infiltration into the groundwater domain. In the North Merritt Island ICPR4 model, rainfall enters the model domain globally as a design storm simulation or on grid for calibration events. Runoff in Mapped Basin areas utilizes a unit hydrograph and time of concentration to load stormwater to modeled nodes. In areas outside of Mapped Basins, including 2D overland flow regions and pond or channel control volumes, runoff is loaded directly onto those features. The following subsections cover the model delineation process, soil / land use characterization, and hydrologic parametrization and simulations.

3.2.1 Subbasin Delineation Process: The effective North Merritt Island model domain included 473 basins. These basins were delineated based upon an evaluation of the terrain, simulating ridge line, and separating out areas of storage. As part of this model update process, the model domain was expanded to the edge of the Indian River Lagoon and Banana River, integrating 1D and 2D areas, and new ERP data. In total, over 750 unique areas were delineated in the updated model and the model domain was expanded from 20.5-sq. miles to 34-sq. miles. The Expanded model domain is seen in **Figure 3.9** along with the Effective Model domain and the ERP update Areas.




Figure 3.9: Effective vs. Expanded Model Domain and ERP Update Areas

3.2.2 Land Use Characterization: Land Use data characterization is presented in **Section 2.2** and includes land use updates based upon visual observation from 2020 aerial imagery consistent with ERP model update areas. For the ICPR4 model development, the pervious and impervious areas were separated. Pervious areas infiltrate into the soil column as soil storage allows, while impervious areas directly runoff after an initial abstraction is filled. The ICPR input table by land use code and description along with the percentage impervious, and initial abstraction used over each land use is included in the Impervious Data Set in the ICPR4 model and summarized in **Table B.1 (Appendix B)**. It should be noted that the water and wetland land use types area characterized as 0% impervious. This is because ICPR4 will only apply evaporation to “pervious” surfaces. Further, the rainfall excess for water and wetland land use types will remain high due to the underlying soil feature, which typically corresponds to high groundwater table.

3.2.3 Soil Characterization: To take advantage of stormwater infiltration into the ground and the potential re-emergence of water into wetlands, watershed soils are characterized by their infiltration capacity/soil storage, and hydraulic conductivity. The soils presented in **Section 2.2** in their general categories are presented in **Table B.2 (Appendix B)** as categorized by MUKEY. This characterization is used to uniquely parameterize the soils applying the Green-Ampt Rainfall Excess method.

3.2.4. Hydrologic Parameterization:

Time of Concentration: Times of concentration (T_c) were calculated for each 1D basin in accordance with TR-55 methodology (NRCS, 1986). Sheet flow was limited to 150-feet and a minimum T_c value of 10-minutes was implemented.

Rainfall Excess Method: The NRCS unit hydrograph method was used to convert precipitation excess into a runoff hydrograph within 1D basins. A synthetic unit hydrograph with a shape factor of 256 for all modeled basins was used, consistent with the effective model and considered appropriate for areas with mild slopes and relatively flat terrain, such as those in this watershed.

The original study utilized the NRCS curve number method to determine rainfall excess. Although the curve number method can be used in ICPR4 for surface modeling, it cannot be used for integrated surface water – groundwater modeling or continuous simulations because it does not track soil moisture and evapotranspiration. The Green-Ampt methodology will be used for hydrology initially. During the calibration period, the Vertical Layers approach may also be used.

To determine infiltration and rainfall excess, the soil data was used to first develop the initial/un-calibrated Green-Ampt and Vertical Layer soil parameters for the vadose zone. The Green-Ampt data were processed using the NRCS Soil Data Viewer ArcGIS plugin. All data were based on weighted averages using the dominant component. The Vertical Layers data were processed using the most recent NRCS SSURGO data for Brevard County published on June 8, 2020. The dominant soil component was also used for the Vertical Layers data development. Data used from the NRCS soils data for the model development are included in **Table 3.1** below.

Table 3.1: NRCS Soil Data Parameters

Green-Ampt	Vertical Layers
Percent Clay	Percent Clay
Percent Sand	Percent Sand
Percent Organic Matter	Percent Organic Matter
Bulk Density (1/3 Bar)	Bulk Density (Oven Dried)
Saturated Hydraulic Conductivity	Saturated Hydraulic Conductivity
Moisture Content (1/3 Bar & 15 Bars)	Moisture Content (1/3 Bar & 15 Bars)
Depth to Water Table	Depth to Water Table

The data in **Table 3.1** were used to develop the following Green-Ampt and Vertical Layers soil parameters.

- *Saturated Vertical Hydraulic Conductivity (ft/day):* Based on NRCS Soil Data
- *Saturated Moisture Content (L^3/L^3):* Eq. 2.15 ICPR4 Technical Reference (June 2018)
- *Residual Moisture Content (L^3/L^3):* Eq. 2.17 ICPR4 Technical Reference (June 2018)
- *Initial Moisture Content (L^3/L^3):* Set initially equal to field capacity
- *Field Capacity (L^3/L^3):* Moisture Content at 1/3 Bar
- *Wilting Point (L^3/L^3):* Moisture Content at 15 Bar
- *Pore Size Index:* Eq. 2.18 ICPR4 Technical Reference (June 2018)
- *Bubble Pressure (in):* Eq. 2.19 ICPR4 Technical Reference (June 2018)
- *Depth to Water Table (ft):* Based on NRCS soil data. This data is not used for the simulation when groundwater is being modeled.

The raw and processed soil data is provided in reference document *NMI_220*. For more details on the soil data development, refer to the *ICPR 4 User's Manual* under Base Data → Lookup Tables → Rainfall Excess Sets.

3.3 Hydraulic Features

Hydraulic routing in the NMI Watershed is performed using ICPR4 integrated surface water and ground water model including 1D and 2D model features. This section highlights the 1D hydraulic elements, model development process and hydraulic parameterization. The 1D model portion includes nodes simulating storage areas and links which represent the conveyance system between storage elements. Refer to **Exhibit 1** for a depiction of the 1D elements of the NMI watershed model network.

3.3.1 Preliminary Model Network Development Process: Using the SWAMP database to identify significant structures connecting elements, the effective ICPR3 model network was modified to incorporate structural elements that were not previously included. Then, based upon ERP data and as-built plans, the model network was updated and expanded to incorporate key structural elements and storage areas within each development. **Table 3.2** summarized the structural elements included in this model, including channels, culverts, drop structures, pumps, and structural weirs. It was noted that in the effective model, many of the depressional areas were modeled using only natural overflow weirs. Where appropriate, these areas were updated to include a structural overflow such as a drop structure or structural weir based on data in SWAMP or ERP documents. It is also of note that the reduction in natural weirs from the effective model to the updated model is due to inclusion of the 2D region which replaced many of these elements.

Table 3.2: Summary of Structural Model Elements by Type

Link Type	Effective ICPR3 Model	ICPR4 Model Update
Pipe	160	363
Drop Structure	11	86
Structural Weir	4	21
Natural Weir	809	752
Channel	165	243
Pump Station	3	7

3.3.2 Hydraulic Parameterization: Hydraulic parameterization utilized available information from ERPs and digital topography to supplement the County's SWAMP features database and field reconnaissance. Highlights of hydraulic parameterization are presented below.

Storage Representation: Lakes, ponds and wetland areas were represented by stage/area relationships assigned to model nodes. These stage/area relationships were developed utilizing the updated digital terrain data discussed in **Section 3.1**. Storage was calculated using GIS at 0.25-foot vertical increments. Channel storage was excluded from basin storage calculations based on the approximate channel cross-section extents and channel alignment.

Node Initial Water Conditions: Groundwater node, overland flow node, and 1D node initial stages are based on a "hot start" simulation for 2017. The hot start simulation starts on 01/01/2017 0.00 hours and ends on 12/31/2017 0.00 hrs. The hot start simulation results on 12/31/2017 0.00 hours were extracted from the results and used to specify the initial stages. For 1D nodes, the initial stages were extracted from the tabular node time series results. Initial stages for the groundwater and overland flow nodes were established using exported surfaces from the hot start simulation results/animations on 12/31/2017 0.00 hours.

Channel Cross Sections: Channels in the effective model were mainly simulated as trapezoidal sections with limited areas represented by irregular cross-sections, mainly in the undeveloped area near the Banana River. All effective model cross-sections were incorporated into the terrain as bathymetry points along with the channel survey data described in **Section 2.5**. The updated model then used the updated terrain to cut irregular cross-sections for every channel reach.

North Merritt Island H&H Modeling Study

Section 3.0 – Watershed Inventory and Surface Water Model Development

Manning's roughness coefficients were then applied to each section. The initial assumption based upon field visits and aerial imagery was that channels can be simulated with a Manning's n value of 0.045, corresponding to a lightly vegetated channel section. During the calibration process this assumption will be revisited with roughness adjusted as appropriate using the range of values in **Table 3.3** below.

Table 3.3: Manning's n Lookup Table for Channels

Channel Description	Manning's Value
Very Clean	0.025 - 0.03
Light Vegetation	0.03-0.07
Medium/Heavy Vegetation	0.06-0.15

Drainage Structure Parameterization: Structural conveyance elements including pipes, drop structures and structural weirs are modeled in ICPR4 based upon element size, invert, and roughness factors. Data for the structural elements originated from either the effective model, Brevard County's SWAMP database, ERP as-built data, portions of the NASA model developed by JEA, survey, or field observations. The highest priority of data was assumed to be Brevard County's SWAMP database, followed by field survey, ERP as-builts, NASA model, then field observations.

The Manning's roughness values applied to these elements are based upon the pipe's material using the values referenced in **Table 3.4**. It should be noted that the bridges in the original model were converted in the effective ICPR3 model to pipe elements of appropriate opening and assigned a Manning's value of 0.056, to reflect that these elements have a vegetated or bare earth bottom rather than a traditional concrete pipe element. These bridge structures were left as culvert model elements in the ICPR4 updated model.

Entrance and exit loss coefficients were set to a default of 0.5 and 1.0 respectively unless site conditions warranted alternate values such as multiple pipes in series or smooth entrance conditions would serve to limit the losses.

Weir structures, either as part of a pond control structure or structural overflow from a pond, were also included. The weir coefficients used for structural weirs are presented in **Table 3.5** and vary depending upon whether the element was sharp crested or broad crested.

Table 3.4: Manning's n Lookup Table for Pipes

Pipe Material	Manning's Value
PVC	0.0
RCP	0.012
CMP	0.024
Bridge Approx.	0.056

Table 3.5: Structural Weir Coefficients

Weir Type	Crest Type	Weir Coefficient
Structural Weir (Drop Structure)	Sharp Crested	3.2
Structural Weir	Broad Crested	3.0

Overland Flow Weirs: To connect model nodes that are not otherwise connected via structural elements, or in conditions when the capacity of the structural element is exceeded, an overland weir is used to simulate the conveyance and represent natural overland flow or road overtopping conditions between sub-basins. These irregular weir features are characterized by cross sectional data and a weir coefficient. The cross-sectional data used to characterize the overland weir connection was extracted from the terrain using the ICPR4 internal cross section processor. Weir coefficients were determined from literature based on flow type and ground cover as shown in **Table 3.6**; whereby the weir coefficient and resultant flow over a natural section is lower than its roadway counterpart, due to the increased roughness along the flow path.

Table 3.6: Weir Coefficients

Weir Type	Ground Cover	Weir Coefficient
Natural Overland	Grass or Light Woods	2.0
Roadway Overtopping	Gravel or Paved Surface	2.6

3.3.3 QA/QC Process Description: Model elements were compared against source data of the element for accuracy. Where deviations or model inconsistencies were found, the internal reviewer would place a spatial comment point at the location of the element being commented upon. Adjustments to the model element and/or source documentation were then made and subsequently back-checked, and adjusted if required, by the internal reviewer. In addition, a peer-review approach was implemented that allowed other members of the SAI Team to review the spatial layout of the 1D model elements. An internal “Comments” geodatabase was employed to track comments from other Team members and their response/resolution to ensure all internal QC comments were addressed prior to finalizing the 1D model network.

3.4 Overland Flow Model Features

This section of the report details the development of 2D overland flow features used in the NMI ICPR4 model. **Exhibit 2** shows the extent of the 2D region and some of the 2D features used in the model.

3.4.1 Overland Flow Region Development: Overland flow model elements were used in undeveloped areas characterized largely by overland flow, as well as in areas where significant interaction with the groundwater was anticipated. The overland flow region boundary encompasses the area to be modeled as overland flow. This region boundary is somewhat coarse to simplify the mesh generation and avoid small triangle lengths in the mesh.

3.4.2 Breaklines & Interpolated Breaklines: The breakline feature class is comprised of polylines that are utilized in the overland flow mesh generation. Breaklines force the creation of flow paths (i.e., triangle edges) in the mesh along the breakline. Breakline placement generally defines the following types of topographic features:

- **Roadways** – Breaklines were placed at along the centerline of roadways and along the adjacent swales (See **Figure 3.10**). In some cases, control volumes were drawn along the centerline and breaklines were limited to the roadway swales.
- **Ditches/Channels** – Breaklines were placed along the centerline of minor swales and ditches that were not modeled with a 1D channel link to provide conveyance within the 2D overland portion of the watershed (See **Figure 3.11**).
- **Within Ponds and Wetlands** – Breaklines were drawn within stormwater ponds and large wetland areas to ensure the groundwater mesh was aligned with the surface water mesh for groundwater-surface water interaction within the waterbodies (See **Figure 3.12**).

North Merritt Island H&H Modeling Study

Section 3.0 – Watershed Inventory and Surface Water Model Development

- Significant ridges or troughs – The vertices and edges of the generated mesh should include ridges and troughs to ensure stormwater is not artificially trapped in depressions or allowed to flow unimpeded through high spots. These features add definition to the mesh to ensure appropriate flow paths and overflow elevations are included in the routing (See **Figure 3.13**).

Interpolated breaklines are a special case of breaklines that can be used to simplify obstructions in the DEM such as small culvert crossings within swales and ditches. The “interpolated” option directs the model to ignore DEM elevations between the endpoints of the breakline during mesh construction. With this option in effect, elevations at the mesh vertices created along the breakline are based on interpolated values calculated based on the elevations at the start and end points of the breakline rather than actual DEM elevations between the endpoints. See **Figure 3.14** for visualization of interpolated breaklines.



Figure 3.10: Roadway Breaklines




Figure 3.11: Channel Breaklines




Figure 3.12: Pond Breaklines




Figure 3.13: Breaklines in Ridges/Troughs




Figure 3.14: Interpolated Breaklines

3.4.3 Channel Features: This feature class represents channels or streams in the 2D model area (See **Figure 3.15**). Channel features are generally drawn along the channel flowline and are associated with channel control volumes (see **Section 3.4.4**). Channel features are used by the model to calculate flow at entry points from adjacent, individual 2D mesh links. The entry point locations are used to interpolate water surface elevations along the 1D channel based on water surface elevations at the ends of the 1D link. The interpolated elevations then serve as “local” boundary conditions for 2D link flow calculations between the overland low region and the channel itself. Channel features are included in the project’s geodatabase in the “OF_Channel” feature class.

3.4.4 Channel Control Volumes: This feature class represents control volumes in the 2D region which are assigned to 1D nodes along a 1D channel. Channel control volumes are developed based on terrain and survey data and generally extend halfway upstream and downstream along the channel links. They represent the spatial extent of 1D channels and span the extent of the cross-sectional data, often from top of bank to top of bank (See **Figure 3.16**). Each vertex along the channel control volume becomes an entry point where water can move between the 2D overland flow area and the 1D system, as explained above in **Section 3.4.3**, however, overland flow links are not included along the edges of the polygon. Channel control volumes are also incorporated within the 1D mapped basins where surface-water groundwater interaction is anticipated.




Figure 3.15: Channel Feature




Figure 3.16: Channel Control Volume on DEM

3.4.5 Pond Control Volumes: This feature class represents control volumes that are assigned to 1D nodes used to model storage areas in the 2D region assuming “level pool” conditions (See **Figures 3.17 and 3.18**). In most cases, a pond control volume represents stormwater ponds, natural ponds, lakes, or “non-flowing” wetland areas where ponding is expected. Pond control volumes are also incorporated in low-lying areas within the 1D mapped basins where surface-water groundwater interaction is anticipated. As with channel control volumes, each vertex along the pond control volume becomes an entry point where water can move between the 2D overland flow area and the 1D system. Storage in pond control volumes is provided using stage-area relationships derived from terrain data.




Figure 3.17: Pond Control Volumes 2D Region




Figure 3.18: Pond Control Volumes 1D Basin

3.4.6 Coves: This feature class is used to identify coves along channels (See **Figure 3.19**). Coves represent lateral, offline level-pool storage areas along a channel. They are associated with channel control volume features. The model uses these features to set elevations in the cove for calculations of flow between the overland flow region and the channel/cove system in much the same way as channel control volumes. The water surface elevation in the cove is based on an interpolated elevation along the associated channel feature. An interpolation point is included with the cove features to identify the location along the channel that is used for this interpolation.




Figure 3.19: Cove and Cove Point

3.4.7 2D Weirs: 2D weirs can be used to model overflow across roadways, berms, or walls inside of the 2D overflow region. The vertices along the 2D weir lines communicate directly with the mesh to allow flow from one side of the weir to the other. 2D weir inverts for the NMI model are based on the DEM elevations along the weir line, however inverts for 2D weirs can also be manually set by the user. The use of a 2D weir simplifies the mesh in areas where multiple breaklines would otherwise be required.

3.4.8 Interface Nodes: This feature class represents locations that require an interface between the 2D overland flow areas and 1D hydraulic elements (weirs, pipes, control structures, etc.). The interface nodes are defined where pipes discharge into the overland flow mesh or at locations where other hydraulic features connect to 1D storage areas (i.e., control volumes) to the overland flow mesh. These nodes are included in the project geodatabase in the “OF_Node” feature class.

3.4.9 Roughness in 2D Areas: Manning’s roughness is assigned within the 2D overflow region based on landcover. The model uses this data to determine lag time and generate hydrographs for the 2D surface, and to route flow through the 2D links (i.e., triangle sides within the mesh). This is through the use of a Lookup Table (enter LU table name here if it exists) in the model. **Table B.3 (Appendix B)** presents the Manning’s roughness coefficients for the Roughness Data Set within the model for varying landcover types.

3.4.10 QA/QC Process Description: Internal QA/QC was performed throughout the model network development process. The SAI Team held weekly progress meetings which were used to discuss any issues, questions, or to obtain input from other Team members on the best approach for a particular area. This allowed for real-time collaboration on modeling approach and level of detail. As with QA/QC efforts detailed earlier in **Section 3.3.3**, A “Comments” geodatabase was employed to track comments and their response/resolution to ensure all internal QC comments were addressed prior to finalizing the model network.

3.5 Boundary Conditions

Boundary conditions were established to represent boundary nodes at each major outfall into the IRL and Banana River. In total, there are 12 boundary nodes: seven located in the IRL and five located in the Banana River. In addition, there are 13 boundary stage lines for the overland flow region. Boundary stage lines allow for interpolation between two boundary node points and serve as boundary conditions for the overland 2D mesh. Boundary elements are shown in **Figure 3.20**.

North Merritt Island H&H Modeling Study

Section 3.0 – Watershed Inventory and Surface Water Model Development

Boundary information for the continuous simulation is based on historical water elevations from Hurricane Irma in 2017 within the IRL and Banana River. The boundary data were established using the Coastal Modeling System (CMS-Flow) model to simulate water levels throughout 2017, including Hurricane Irma. The CMS model has been previously calibrated and was also compared to 2017 values from the USGS monitoring station at Haulover Canal. Please refer to the *Development of Input Rainfall and Stage Conditions Data for North Merritt Island* (Applied Ecology, Inc., 2021) included as **Appendix C** for more information on the development of boundary stage data for the NMI model. This report also discusses rainfall data for Hurricane Irma and anticipated rainfall under future conditions.

Boundary information for discrete storm events will be established during future phases of the NMI watershed evaluation.



Figure 3.20: Boundary Node and Line Locations

4.0 Groundwater Model Development

4.1 Groundwater Region Development

A total of seven (7) groundwater regions were created as part of the ICPR4 model development. In general, groundwater region boundaries were split along channel features that were mostly and continuously inundated. When the water pierces the ground surface while the surface is inundated, a known head condition is placed at the corresponding groundwater nodes. The known head condition is derived from water surface elevations in the surface model component. Therefore, when two groundwater regions share a common edge along a water feature, both regions use the same known head condition. The reason for using multiple groundwater regions is to speed up the computations. Multiple regions are processed in parallel.




Figure 4.1: Groundwater Regions

4.2 Breaklines & Breakpoints

Groundwater breaklines and breakpoints were placed to refine the groundwater mesh. Groundwater breakpoints used a point spacing pattern that was two times the spacing of the overland flow breakpoints. The groundwater breakpoints were also placed so they aligned with the overland flow breakpoints. Groundwater breaklines are consistent with the overland flow breaklines that were placed in recharge areas where groundwater/surface water interaction is anticipated. Generally, these are along the bottom of channels and ponds.




Figure 4.2: Groundwater Breakpoint & Breakline Placement

4.3 Groundwater Parameterization

Groundwater parameters were based on data from the East-Central Florida Transient Expanded (ECFTX) Model. Data extracted from the ECFTX model includes:

- Surficial Aquifer Base
- Surficial Aquifer Saturated Hydraulic Conductivity
- Surficial Aquifer Porosity
- Confining Layer Bottom Elevation
- Confining Layer Saturated Hydraulic Conductivity

A 1,250-ft X 1,250-ft gridded map layer was also created from the ECFTX model data to parameterize the groundwater (**Figure 4.3**). Corresponding porosity and saturated hydraulic lookup tables were developed based on each map layer zone. The model specific information can be found in the provided ICPR4 model and the ECFTX model (Reference Document NMI_216).




Figure 4.3: ECFTX Groundwater Data Grid

4.4 Boundary Conditions

The boundary conditions for the groundwater model are consistent with those for the overland flow region. The boundary conditions were incorporated into the model using 14 groundwater boundary stage lines as shown in **Figure 4.4**.




Figure 4.4: Groundwater Boundary Stage Line Locations

5.0 Field Data Acquisition Summary

5.1 Field Verification Efforts

Field data collection in the North Merritt Island Watershed occurred at sites where data evaluated from SWAMP database or ERP documentation was inconsistent or absent. Field crews photographed and documented each hydraulic feature visited noting condition, material, and dimensions for the 85 sites identified. As appropriate crews also verified drainage patterns where available digital data proved inconclusive or did not provide enough information to determine the drainage pattern. Depending upon the field observations, recommendations were made to provide immediate maintenance and/or provide a survey of the observed structures. **Figure 5.1** provides a spatial view of structures visited, highlighting those with additional survey needs. See **Appendix D** for the complete Field Data Collection Memorandum, which includes field observations and representative photos of each site visited.




Figure 5.1: North Merritt Island Field Data Collection Sites

5.2 Survey Needs Assessment

Based upon the field review of structural elements, 28 sites were identified as needing survey to characterize the structure beyond the data that was available from field reconnaissance, and 32 structures where maintenance is recommended. The structures where survey data and/or maintenance activities is recommended are listed in **Table 5.1**. A complete listing of all sites visited along with the date of the field visit, survey needs, and maintenance needs, are provided in the Field Data Collection Memorandum included in **Appendix D**.

Table 5.1: Summary of Structures Requiring Survey and/or Maintenance

Link Name	Link Type	SWAMP ID	Date Visited	Survey Required	Maintenance Required
DSykesS_1	Drop Structure	BCE611CS012		Y	
DSykesS_2	Drop Structure	BCE611CS010		Y	
DSykesS_3	Drop Structure	BCE611CS008		Y	
PB2020_1	Pipe	P016D634021022	03-Nov-20		Y
PB4040_1	Pipe	233634CU47AB	03-Nov-20	Y	Y
WB3060_1	Weir	Not in SWAMP	03-Nov-20		Y
PC1080_1	Pipe	NO FEATURE CODE	03-Nov-20		Y
PC1092_1	Pipe	Not in SWAMP	03-Nov-20	Y	Y
PC1130_1	Pipe	Not in SWAMP	03-Nov-20	Y	Y
PC1160_1	Pipe	In SWAMP wo feature code	03-Nov-20	Y	Y
PD1070_1	Pipe	0000CU0000	03-Nov-20		Y
PDD1002_1	Pipe	BC233624CU009	03-Nov-20	Y	Y
PDD1010_1	Pipe	BC233624CU008	03-Nov-20	Y	
PDD3315_1	Pipe	P015D623029030	03-Nov-20		Y
PDD3335_1	Pipe	P021D623042041	03-Nov-20		Y
PDD3345_1	Pipe	P012D623024023	03-Nov-20		Y
PDD3405_1	Pipe	P007D623013014	03-Nov-20		Y
PEE1060_1	Pipe	P094D634135133	03-Nov-20		Y
PEE3020_1	Pipe	In SWAMP wo feature code	03-Nov-20	Y	
PEE3040_1	Pipe	In SWAMP wo feature code	03-Nov-20	Y	Y
PEE3280_1	Pipe	Not in SWAMP	03-Nov-20	Y	Y
PEE4160_1	Pipe	P161E603217218	03-Nov-20	Y	Y
PEE5060_1	Pipe	P023E610033034	03-Nov-20	Y	Y
PEE5060_2	Pipe	P025E610039040	03-Nov-20	Y	Y
PF2110_1	Pipe	NO FEATURE CODE	03-Nov-20		Y
DFF1230_1	Drop Structure	BCE611CS096	05-Nov-20		Y
PFF1060_1	Pipe	P088E602133134	05-Nov-20	Y	
PFF1180_1	Pipe	P042E611074075	05-Nov-20		Y
PFF1210_1	Pipe	P045E611079080	05-Nov-20		Y
PGG1010_1	Pipe	P001E601011010	05-Nov-20	Y	
PGG1060_2	Pipe	Not in SWAMP	05-Nov-20		Y
PGG1150_1	Pipe	P014E612021022	05-Nov-20		Y
DL1790_1	Drop Structure	BCD625CS099	05-Nov-20	Y	
PL1345_1	Pipe	BC233625CU010	03-Nov-20	Y	Y

North Merritt Island H&H Modeling Study

Section 5.0 – Field Data Acquisition Summary

PM2970_1	Pipe	P006D624008007	03-Nov-20		Y
PM2980_1	Pipe	0000CU0000	03-Nov-20	Y	Y
PM3000_1	Pipe	0000CU0000	03-Nov-20	Y	Y
PO2960_1	Pipe	Not in SWAMP	03-Nov-20	Y	
PO3030_2	Pipe	BC233636CU003	05-Nov-20	Y	
PPI2010_1	Pipe	0000CU0000	03-Nov-20	Y	Y
PPI2010_2	Pipe	0000CU0000	03-Nov-20	Y	Y
PR3200_1	Pipe	0000CU0000	03-Nov-20	Y	
DS1140_1	Drop Structure	0000SC0000	03-Nov-20	Y	
PU4220_1	Pipe	0000CU0000	03-Nov-20	Y	Y

6.0 Model Calibration and Verification

The North Merritt Island ICPR4 calibration/verification analysis was comprised of a continuous simulation for the year 2017. The model was calibrated to a single historical event (Hurricane Irma: 08/31/2017-09/29/2017) and then verified using two subsequent storm events that occurred between 10/01/2017-11/03/2017. The model results were compared to the recorded stage measurements at the 16 active Brevard County gages (**Figure 6.1**). Gage readings were only available for the calibration/validation period (08/31/2017 thru 11/03/2017). Additionally, all gage readings were recorded manually by Brevard County staff. The gage records are provided in reference document NMI_222.

6.1 Statistical Metrics

Comparisons between the measured and model data include the following statistical metrics:

- Coefficient of Determination (R^2)
- Nash-Sutcliffe Model Efficiency Coefficient (NSE)
- Mean Error (ME)
- Mean Absolute Error (MAE)
- Root Mean Square Error (RMSE)
- Ratio “RMSE/Standard Deviation (Observed)” (RSR)
- ME, MAE and RMSE within ½ Standard Deviation (Observed)

Calibration targets were established for the modeling effort to assess the accuracy of the model data versus measured data. These targets are consistent with the calibration targets set in the *ICPR4 Hydrologic Modeling Support for Johns and Avalon Lakes* report (03/26/2021) by Streamline Technologies, Inc. (SLT) for the St. Johns River Water Management District (SJRWMD). Moriasi, et al. (2007, 2015) provides guidance on performance ratings with categories of “Very Good”, “Good”, “Satisfactory” and “Not Satisfactory”. **Table 6.1** is derived from those two references and from SLT’s modeling experience in Florida.

Table 6.1: Statistical Metrics

Metric	Very Good	Good	Satisfactory	Not Satisfactory
Coefficient of Determination (R^2)	$R^2 > 0.85$	$0.75 < R^2 \leq 0.85$	$0.60 \leq R^2 < 0.75$	$R^2 < 0.60$
Nash-Sutcliffe Efficiency (NSE)	$NSE > 0.80$	$0.70 < NSE \leq 0.80$	$0.50 < NSE \leq 0.70$	$NSE \leq 0.50$
Mean Error (ME) ft	$ ME \leq 0.25'$	$0.25' < ME \leq 0.5'$	$0.50' < ME \leq 1.0'$	$ ME > 1.0'$
Mean Absolute Error (MAE) ft	$MAE \leq 0.50'$	$0.50' < MAE \leq 0.75'$	$0.75' < MAE \leq 1.5'$	$0.75' < MAE \leq 1.5'$
Root Mean Square Error (RMSE) ft	$RMSE \leq 0.75'$	$0.75' < RMSE \leq 1.00'$	$1.00' < RMSE \leq 2.00'$	$RMSE > 2.00'$
Ratio “RMSE/SD-Observed” (RSR)	$RSR \leq 0.50$	$0.50 < RSR \leq 0.60$	$0.60 < RSR \leq 0.70$	$RSR > 0.71$
½ Standard Deviation (Observed) ft	3 ME , MAE, RMSE	2 ME , MAE, RMSE	1 ME , MAE, RMSE	0 ME , MAE, RMSE

The following notes were taken from Moriasi, et al. (2007, 2015).

R^2 – The coefficient of determination, R^2 , is widely used in hydrologic modeling studies and describes the degree of collinearity between simulated and observed data. It is oversensitive to high extreme values and insensitive to additive and proportional differences between model predictions and measured data. The slope and y-intercept of the best-fit regression line can indicate how well simulated data match measured data. The slope indicates the relative relationship between simulated and measured values. The y-intercept indicates the presence of a lag or lead between model predictions and measured data, or that data sets are not perfectly aligned. The intercept should be close to zero and the gradient close to 1.0 for good agreement.

NSE – The Nash-Sutcliffe efficiency, NSE, is a normalized magnitude of the residual variance (“noise”) compared to the measured data variance (“information”). NSE indicates how well the plot of observed versus simulated data fits the 1:1 line. It is widely used and is good for continuous simulations. NSE cannot identify model bias and cannot be used to identify differences in timing and magnitudes of peaks and shape of recession curves. NSE is sensitive to extreme values due to the squared differences.

North Merritt Island H&H Modeling Study

Section 6.0 – Model Calibration and Verification




Figure 6.1: Brevard County Gage Locations

ME, MAE & RMSE – These parameters work well for long-term continuous simulations and are commonly used in model performance evaluation. They are reported in the same units as the model output and easy to interpret. Singh et al (2004) stated that RMSE and MAE values less than half the standard deviation of the observed data may be considered low and that either is appropriate for model evaluation.

RSR – RSR includes a scaling/normalization factor and consequently removes some of the arbitrariness of setting a target value for RMSE. One disadvantage is that it gives more weight to high values when compared to low values. It has not been widely used in hydrologic modeling literature since it is a relatively new statistical performance measure.

6.2 Model Calibration

The calibration period of record for this study is from 08/31/2017 – 09/29/2017 (Hurricane Irma). The calibration analysis includes comparisons between measured and modeled results for each of the 16 staff gages with adjustments to the model input as needed. The rainfall data and boundary condition information for the study area was provided by Applied Ecology, Inc (AEI). For details on these data, refer to Sections 2 and 3 of this report. The subsequent section discusses the parameter adjustments performed as part of the calibration analysis as well as the final results for the calibration simulations.

6.2.1 Parameter Adjustments

Initial Stages: The initial stages for the surface and groundwater nodes were established by running a preliminary simulation with estimated initial stages at the onset (01/01/2017 0.00 hrs). The results from the preliminary simulation at 12/31/2017 23.00 hrs were then used to specify the initial stages for the remaining calibration simulations at 01/01/2017 0.00 hrs. The initial conditions were not modified for the final calibration simulation mainly because it was determined that the initial conditions had no noticeable effect on the calibration-verification analysis and the calibration-verification storm events occurred much later in 2017 (September-October). Essentially, the “spin up” period prior to these calibration-verification storm events was sufficient for the modeled stages to represent actual field conditions during the calibration-verification period.

Green-Ampt Parameter Adjustments: During the initial calibration simulation for Hurricane Irma, infiltration and recharge to the groundwater appeared extremely high for pervious areas based on comparisons with observed staff gage data. This resulted in modeled stages well below the observed stages at all gage locations except SG1 which is located along the Barge Canal and is tidally influenced.

It was determined that the low runoff volumes were caused by the relatively high vertical saturated hydraulic conductivities that were based on the NRCS soils parameters. Consequently, several iterations with lower vertical saturated hydraulic conductivity values were evaluated. Based on the analysis, it appears the NRCS data drastically overestimate vertical saturated hydraulic conductivity for the study area. Therefore, the Green Ampt vertical conductivities were reduced approximately two orders of magnitude for the modeled and measured stages to be comparable. The calibrated Green-Ampt parameters are provided in the calibrated model included with this submittal.

Groundwater Parameter Adjustments: The calibration effort indicated that the initial values used for the horizontal saturated hydraulic conductivity (Ksat) for the groundwater were too high. As a result, the Ksat value for each groundwater conductivity zone was lowered to a uniform value of 5 ft/day.

Boundary Conditions: While the boundary data are the best available information, the time-stage data for the boundary conditions were based on the hydrodynamic model results provided by AEI. The calibration results showed that the stage-hydrographs recovered much faster than what was observed in the field. The model network was reviewed along with the input parameters for any warranted changes to the input data. While the model network was revised and changes made to the model input/parameters (i.e., increasing Manning’s n for channels), the subsequent calibration simulation results showed little to no impact on the stage hydrograph recovery at the gage locations. As a result, the boundary conditions were then evaluated.

Several calibration simulations were conducted with varying increases in the boundary stages. Based on that calibration analysis, it was determined a uniform adjustment of +6.0-inches to all boundary conditions yielded the best accuracy between the model results and measure data at the gage locations. The change to the boundary conditions was discussed with staff at AEI and it was verified that this was an acceptable parameter adjustment for the calibration-verification analysis.

Pump Rating Curve Links Conditions: The pump rating curves at Pine Island and the Mosquito Impoundment were adjusted to match the pump operation, as best as possible, during the calibration and verification storm events. At Pine Island, the pump rating curve links (RPI1030_2 & RPI1030_1) were adjusted to account for the initial drawdown observed in the gage data prior to Hurricane Irma. A temporary pump (Link PICA_Temp) was also added to the model based on discussions with County staff.

At SG3 East Hall Road Pump House, the pumping rates for the pump rating curve links (RO6A & RO6) were reduced by 50% based on model calibration results. Additionally, a temporary pump (Link Hall_Temp_Pump) was incorporated into the calibration-verification model. This temporary pump was in place during the calibration-verification period per the County staff.

It is important to note that, per discussions with County staff, there were several manual adjustments to pump operation at both locations that are not reflected on the pump logs. Consequently, an additional calibration-verification simulation was developed by placing time-stage nodes in the vicinity of gages SG1, SG4 and SG17 to mimic the actual pump operation and its effects on water levels upstream of the pumps. The locations that were converted to time-stage nodes are listed in **Table 6.2**. Essentially, this simulation was developed to confirm that if the pump operation data were available, the calibration-verification comparisons would be more accurate.

Table 6.2: Calibration Simulation #2 Additional Boundary Conditions

Gage	Nodes Convert to Time/Stage
SG1	NHH1010
	NHH1020
	NHH1030
	NHH1040
	NHH1050
SG4	NFF2020
SG17	NPI1030

6.3 Calibration Analysis

As previously mentioned, there are a total of 16 active gages within the study area. The calibration period of record is from 08/31/2017 – 09/29/2017 (Hurricane Irma). The calibration analysis included comparisons between measured and modeled results for each of these staff gages. The results of the final calibration analysis results are provided in the subsequent sections. Note that there are two calibration analyses for each gage unless otherwise stated. Calibration #1 is the simulation that includes the final parameter adjustments and the adjusted boundary conditions provided by AEI. Calibration #2 is identical to Calibration #1 except the internal boundary conditions at the locations specified in **Table 6.2** were incorporated into the model. Each analysis includes comparisons between the gage, denoted by the “SG” prefix, and the node in the model used for the comparisons.

6.3.1 Gage SG1 Sykes Creek at Sea Ray Dr. – Calibration Results

Gage SG1 Sykes Creek is located along the Barge Canal at the far south end of the study area. The stage hydrograph comparisons at this location are provided in **Figure 6.2**. As shown in the figure, the modeled and simulated results compare very well with stages generally within 4.1-inches of one another. The peak stages for the measured (1.72-ft, NAVD88) and simulated (1.48-ft, NAVD88) differ by just 2.9 inches. No comparisons for the Calibration #2 simulation are necessary at this location because it is one of the locations that was converted to a time-stage node for that analysis.




Figure 6.2: SG1 Sykes Creek at Sea Ray Dr. Calibration#1 Comparisons

The statistical comparisons between measured and modeled data are provided in **Table 6.3** below. As shown, all metrics are classified as either “Very Good” or “Satisfactory” which indicates the model is representative at this gage location. Keep in mind that this area is sensitive to the water levels in both the Indian River and Banana River. Consequently, if gage data were available in the Banana River and Indian River at the Barge Canal, it is anticipated that the model results would be improved even further.

Table 6.3: Calibration Statistical Metrics SG1

Metric Parameter	Calibration Simulation #1	Quality #1
R²	0.742	Satisfactory
NSE	0.524	Satisfactory
ME	-0.249	Very Good
MAE	0.339	Very Good
RMSE	0.371	Very Good
RSR	0.678	Satisfactory
1/2 Standard Deviation Obs.	1	Satisfactory

Note: Number of pair data (observed and simulated) = 30

6.3.2 Gage SG2 East Hall Rd. North – Calibration Results

Gage SG2 is located just upstream of the East Hall Road Pump House. The stage hydrograph comparisons for the Calibration #1 and Calibration #2 are provided in **Figure 6.3** and **Figure 6.4**, respectively. Both calibration simulations compare very well for the maximum measured stage. Calibration #1 modeled peak stage (2.64-ft, NAVD88) is only 3.2-inches above the measured peak stage (2.37-ft, NAVD88). The model tends to recover slightly faster than the measured data. But overall, the model compares very well to the measured data. Calibration #2 modeled peak stage (2.53-ft, NAVD88) is only 1.9-inches above the measured peak stage. Additionally, the staging hydrographs are virtually identical between the measured and modeled stages as would be expected.




Figure 6.3: SG2 East Hall Rd. North Calibration#1 Comparisons




Figure 6.4: SG2 East Hall Rd. North Calibration#2 Comparisons

The statistical metrics for both calibration simulations are provided in **Table 6.4** below. Both sets of simulation results compare well to the measured data with all metrics classified as very good. However, Calibration #2 compares better for every statistical metric.

Table 6.4: Calibration Statistical Metrics SG2

Metric Parameter	Calibration Simulation #1	Quality #1	Calibration Simulation #2	Quality #2
R²	0.963	Very Good	0.992	Very Good
NSE	0.853	Very Good	0.985	Very Good
ME	0.219	Very Good	0.032	Very Good
MAE	0.257	Very Good	0.056	Very Good
RMSE	0.295	Very Good	0.094	Very Good
RSR	0.377	Very Good	0.121	Very Good
1/2 Standard Deviation Obs.	3	Very Good	3	Very Good

Note: Number of pair data (observed and simulated) = 30

6.3.3 Gage SG3 East Hall Rd. Pump House – Calibration Results

Gage SG3 is located just west of the East Hall Rd. Pump House. The Calibration #1 stage hydrograph comparisons are provided in **Figure 6.5**. Based on the hydrographs, there is good correlation between the measured and modeled stages. The modeled stages are generally within ~3-inches of the measured stages. Additionally, there is only a minor difference (1.2-inches) between model peak stage (2.46-ft, NAVD88) and measured peak stage (2.36-ft, NAVD88). No comparisons were conducted for at this gage for Calibration #2 since node NFF2020 was converted to a time-stage node for that analysis.




Figure 6.5: SG3 East Hall Rd. North Calibration#1 Comparisons

The statistical metrics for this gage provided in **Table. 6.5** show very good correlation between the measured and modeled stage data.

Table 6.5: Calibration Statistical Metrics SG3

Metric Parameter	Calibration Simulation #1	Quality #1
R ²	0.968	Very Good
NSE	0.872	Very Good
ME	0.227	Very Good
MAE	0.249	Very Good
RMSE	0.274	Very Good
RSR	0.352	Very Good
1/2 Standard Deviation Obs.	3	Very Good

Note: Number of pair data (observed and simulated) = 30

6.3.4 Gage SG4 East Hall Rd. Barge Canal Ditch – Calibration Results

Gage SG4 is located just southwest of the East Hall Rd. Pump House. The Calibration #1 stage hydrograph comparisons are provided in **Figure 6.6**. The difference between the simulated peak stage (2.46-ft, NAVD88) and measured peak stage (2.34-ft, NAVD88) is approximately 1.4-inches. No comparisons were conducted for this particular gage for Calibration #2 since this location was converted to a time-stage node for that analysis.




Figure 6.6: SG4 East Hall Rd. Barge Canal Ditch Calibration#1 Comparisons

Additionally, the statistical metrics provided in **Table 6.6** show very good correlation between the measured and modeled stage data.

Table 6.6: Calibration Statistical Metrics SG4

Metric Parameter	Calibration Simulation #1	Quality #1
R²	0.970	Very Good
NSE	0.876	Very Good
ME	0.216	Very Good
MAE	0.238	Very Good
RMSE	0.265	Very Good
RSR	0.347	Very Good
1/2 Standard Deviation Obs.	3	Very Good

Note: Number of pair data (observed and simulated) = 30

6.3.5 Gage SG5 Chase Hammock at Judson Rd. – Calibration Results

The SG5 gage is located just north of the Judson Rd. and Chase Hammock Rd. intersection along the north-south drainage ditch. Stage hydrograph comparisons for Calibration #1 and Calibration #2 are shown in **Figure 6.7** and **Figure 6.8**, respectively. Both calibration simulations compare very well for the maximum measured stage. Calibration #1 modeled peak stage is 2.78-ft (NAVD88), which is approximately 3.4-inches above the measured peak stage (2.50-ft, NAVD88). Calibration #2 modeled peak stage is 2.69-ft, which is 2.3-inches above the measured peak stage.

The statistical metrics for this gage provided in **Table 6.7** range from good to very good for Calibration #1. **Table 6.7** shows very good correlation between the measured and modeled stage data for Calibration #2. The improvement from Calibration #1 to Calibration #2 is mostly due to the recovery leg of the hydrograph. It should be noted that stages recover faster in the Calibration #1 results compared to the measured data. The Calibration #2 stage results, however, are much more consistent with the measured data. This indicates the pump operation at gages SG17 and SG4 influences the recovery at the gage location.




Figure 6.7: Gage SG5 Chase Hammock at Judson Rd. Calibration#1 Comparisons




Figure 6.8: Gage SG5 Chase Hammock at Judson Rd. Calibration#2 Comparisons

Table 6.7: Calibration Statistical Metrics SG5

Metric Parameter	Calibration Simulation #1	Quality #1	Calibration Simulation #2	Quality #2
R²	0.943	Very Good	0.977	Very Good
NSE	0.710	Good	0.916	Very Good
ME	0.347	Good	0.174	Very Good
MAE	0.378	Very Good	0.198	Very Good
RMSE	0.421	Very Good	0.226	Very Good
RSR	0.529	Good	0.285	Very Good
1/2 Standard Deviation Obs.	2	Good	3	Very Good

Note: Number of pair data (observed and simulated) = 30

6.3.6 Gage SG6 Crisafulli at Judson Rd. – Calibration Results

The SG6 gage is located just north of the Judson Rd. and E. Crisafulli Rd. intersection along the north-south drainage ditch. The stage hydrograph comparisons for Calibration #1 and Calibration #2 are provided in **Figure 6.9** and **Figure 6.10**, respectively. The Calibration #1 modeled peak stage is 2.88-ft (NAVD88), which is approximately 3.1-inches above the measured peak stage (2.62-ft, NAVD88). The Calibration #2 modeled peak stage is 2.83-ft, which is 2.5-inches above the measured peak stage.




Figure 6.9: Gage SG6 Crisafulli at Judson Rd. Calibration#1 Comparisons




Figure 6.10: Gage SG6 Crisafulli at Judson Rd. Calibration#2 Comparisons

While the statistical metrics for this gage provided in **Table 6.8** are all classified as very good, the table shows that the SG6 Calibration #2 simulation tends to compare better to the measured stages. Similar to SG5 comparisons, the improvement from Calibration #1 to Calibration #2 is also related to the recovery leg of the stage hydrograph. As shown, the Calibration #2 stage results are much more consistent to the measured data for the recovery leg of the hydrograph after the peak of the storm event. This also indicates the pump operation at gages SG17 and SG4 influences the recovery at this the gage location.

Table 6.8: Calibration Statistical Metrics SG6

Metric Parameter	Calibration Simulation #1	Quality #1	Calibration Simulation #2	Quality #2
R²	0.946	Very Good	0.969	Very Good
NSE	0.889	Very Good	0.956	Very Good
ME	0.176	Very Good	0.043	Very Good
MAE	0.254	Very Good	0.140	Very Good
RMSE	0.278	Very Good	0.175	Very Good
RSR	0.327	Very Good	0.206	Very Good
1/2 Standard Deviation Obs.	3	Very Good	3	Very Good

Note: Number of pair data (observed and simulated) = 30

6.3.7 Gage SG7 East Crisafulli at Joseph Ct. – Calibration Results

The SG7 gage is located west of the Joseph Ct. and E. Crisafulli Rd. intersection. The stage hydrograph comparisons for Calibration #1 and Calibration #2 are provided in **Figure 6.11** and **Figure 6.12**, respectively. The Calibration #1 modeled peak stage is 2.94-ft (NAVD88), which is approximately 3.4-inches above the measured peak stage (2.66-ft, NAVD88). The Calibration #2 modeled peak stage is 2.89-ft, which is 2.8-inches above the measured peak stage.




Figure 6.11: Gage SG7 East Crisafulli at Joseph Ct. Calibration#1 Comparisons




Figure 6.12: Gage SG7 East Crisafulli at Joseph Ct. Calibration#2 Comparisons

The statistical metrics are provided in **Table 6.9**. The statistical comparisons for both simulations show very good correlation between the measured and modeled data. There is only a slight difference between the two simulations with Calibration #2 being marginally better compared to Calibration #1.

Table 6.9: Calibration Statistical Metrics SG7

Metric Parameter	Calibration Simulation #1	Quality #1	Calibration Simulation #2	Quality #2
R²	0.964	Very Good	0.975	Very Good
NSE	0.919	Very Good	0.961	Very Good
ME	0.142	Very Good	0.023	Very Good
MAE	0.217	Very Good	0.131	Very Good
RMSE	0.237	Very Good	0.165	Very Good
RSR	0.280	Very Good	0.194	Very Good
1/2 Standard Deviation Obs.	3	Very Good	3	Very Good

Note: Number of pair data (observed and simulated) = 30

6.3.8 Gage SG8 N Courtenay at Pine Island – Calibration Results

Gage SG8 is located south of the Judson Rd. and N. Courtney Parkway intersection. The stage hydrograph comparisons for Calibration #1 and Calibration #2 are provided below in **Figure 6.13** and **Figure 6.14**, respectively. The Calibration #1 modeled peak stage is 2.85-ft (NAVD88), which is approximately 3.0-inches above the measured peak stage (2.60-ft, NAVD88). The Calibration #2 modeled peak stage is 2.80-ft, which is 2.4-inches above the measured peak stage.




Figure 6.13: Gage SG8 N Courtenay at Pine Island Calibration#1 Comparisons




Figure 6.14: Gage SG8 N Courtenay at Pine Island Calibration#2 Comparisons

The statistical metrics are provided in **Table 6.10**. The statistical comparisons for both simulations show very good correlation between the measured and modeled data. There is only a slight difference between the two simulations with Calibration #2 being marginally better compared to Calibration #1.

Table 6.10: Calibration Statistical Metrics SG8

Metric Parameter	Calibration Simulation #1	Quality #1	Calibration Simulation #2	Quality #2
R²	0.937	Very Good	0.962	Very Good
NSE	0.908	Very Good	0.955	Very Good
ME	0.131	Very Good	0.006	Very Good
MAE	0.233	Very Good	0.143	Very Good
RMSE	0.256	Very Good	0.179	Very Good
RSR	0.298	Very Good	0.209	Very Good
1/2 Standard Deviation Obs.	3	Very Good	3	Very Good

Note: Number of pair data (observed and simulated) = 30

6.3.9 Gage SG9 Pine Island 1 Mile North of North Courtenay – Calibration Results

Gage SG9 is located along Pine Island Rd. about 1 mile north of North Courtney Parkway. The stage hydrograph comparisons for Calibration #1 and Calibration #2 are provided below in **Figure 6.15** and **Figure 6.16**, respectively. The Calibration #1 modeled peak stage is 2.73-ft (NAVD88), which is 3-inches above the measured peak stage (2.48-ft, NAVD88). The peak stage for Calibration #2 is 2.66-ft (NAVD88) which is 2.2-inches above the measured peak stage.




Figure 6.15: Gage SG9 Pine Island 1 Mile North of North Courtenay Calibration#1 Comparisons




Figure 6.16: Gage SG9 Pine Island 1 Mile North of North Courtenay Calibration#2 Comparisons

The statistical metrics are provided in **Table 6.11**. The statistical comparisons for both simulations show very good correlation between the measured and modeled data. Calibration #2 tends to compare better because the recovery leg of the stage hydrograph is more consistent with measured data for that simulation.

Table 6.11: Calibration Statistical Metrics SG9

Metric Parameter	Calibration Simulation #1	Quality #1	Calibration Simulation #2	Quality #2
R²	0.893	Very Good	0.953	Very Good
NSE	0.867	Very Good	0.949	Very Good
ME	0.138	Very Good	0.042	Very Good
MAE	0.272	Very Good	0.169	Very Good
RMSE	0.316	Very Good	0.195	Very Good
RSR	0.359	Very Good	0.221	Very Good
1/2 Standard Deviation Obs.	3	Very Good	3	Very Good

Note: Number of pair data (observed and simulated) = 30

6.3.10 Gage SG10 Pine Island Harvey Grove Pump – Calibration Results

Gage SG10 is located about 3,000-ft east of the Pine Island Grove Pumps along Pine Island Rd. The stage hydrograph comparisons for Calibration #1 and Calibration #2 are provided below in **Figure 6.17** and **Figure 6.18**, respectively. The Calibration #1 modeled peak stage is 2.44-ft (NAVD88), which is approximately 3.6-inches above the measured peak stage (2.14-ft, NAVD88). The peak stage for Calibration #2 is 2.29-ft (NAVD88), which is 1.8-inches above the measured peak stage. While the modeled peak stage estimates are comparable for both calibration simulations, the recovery legs of the stage hydrograph are quite different.




Figure 6.17: Gage SG10 Pine Island Harvey Grove Pump Calibration#1 Comparisons




Figure 6.18: Gage SG10 Pine Island Harvey Grove Pump Calibration#2 Comparisons

The statistical metrics are provided in **Table 6.12**. While the statistical metrics for the Calibration #1 simulation are acceptable ranging from good to very good, the Calibration #2 results have very good correlation between the measured and modeled data. This indicates that the stage recovery at this gage is noticeably affected by the pump operations at Pine Island.

Table 6.12: Calibration Statistical Metrics SG10

Metric Parameter	Calibration Simulation #1	Quality #1	Calibration Simulation #2	Quality #2
R²	0.753	Good	0.979	Very Good
NSE	0.704	Good	0.975	Very Good
ME	0.170	Very Good	0.039	Very Good
MAE	0.347	Very Good	0.083	Very Good
RMSE	0.430	Very Good	0.126	Very Good
RSR	0.535	Good	0.156	Very Good
1/2 Standard Deviation Obs.	2	Good	3	Very Good

Note: Number of pair data (observed and simulated) = 30

6.3.11 Gage SG11 Pine Island West – Calibration Results

Gage SG11 is located about 580-ft east of the Pine Island Grove Pumps along Pine Island Rd. The stage hydrograph comparisons for Calibration #1 and Calibration #2 are provided below in **Figure 6.19** and **Figure 6.20**, respectively. Like the comparisons for SG10, the modeled and measured peak stages compare quite well. The Calibration #1 modeled peak stage is 2.11-ft (NAVD88), which is approximately 0.1-inches above the measured peak stage (2.10-ft, NAVD88). The peak stage for Calibration #2 is 2.02-ft (NAVD88), which is ~1.0-inch below the measured peak stage. Additionally, the recovery legs of the stage hydrographs are quite different between the two simulations. Notice that Calibration #2 is much more consistent with the measure data. This indicates that the stage recovery at SG11 is sensitive to the pumping rates at Pine Island. Note that node NPI1030 was converted to a time-stage node for the Calibration #2 analysis. The comparisons for Calibration #2 were included in this section to show how the stages upstream of the gage are fairly consistent with stages at the pump location (SG17 at node NPI1030).




Figure 6.19: Gage SG11 Pine Island West Calibration#1 Comparisons




Figure 6.20: Gage SG11 Pine Island West Calibration#2 Comparisons

This is even more evident when looking at the statistical metrics in **Table 6.13**. Specifically, Calibration #2 has very good correlation between the measured and modeled stages while Calibration #1 has four parameters that are classified as satisfactory. This comparison demonstrates how sensitive the upstream stages are to the pumping operations at Pine Island.

Table 6.13: Calibration Statistical Metrics SG11

Metric Parameter	Calibration Simulation #1	Quality #1	Calibration Simulation #2	Quality #2
R²	0.678	Satisfactory	0.993	Very Good
NSE	0.595	Satisfactory	0.984	Very Good
ME	0.217	Very Good	0.060	Very Good
MAE	0.390	Very Good	0.060	Very Good
RMSE	0.485	Very Good	0.096	Very Good
RSR	0.626	Satisfactory	0.123	Very Good
1/2 Standard Deviation Obs.	1	Satisfactory	3	Very Good

Note: Number of pair data (observed and simulated) = 30

6.3.12 Gage SG12 PICA South – Calibration Results

Gage SG12 is located at the downstream side of the Pine Island Pump House. The stage hydrograph comparison for Calibration #1 is provided below in **Figure 6.21**. Like the comparisons for SG11, the modeled and measured peak stages compare quite well. The Calibration #1 modeled peak stage is 2.11-ft (NAVD88), which is 0.6-inches above the measured peak stage (2.06-ft, NAVD88). Like SG11, the stage hydrograph recovers faster than the measured stage data after the peak. This is also attributed to the unknown pumping operations at the Pine Island Harvey Grove Pumps. No comparisons were conducted for Calibration #2 since node NPI1030 was converted to a time-stage node for that analysis.




Figure 6.21: Gage SG12 PICA South Calibration #1 Comparisons

The statistical metrics shown in **Table 6.14** show that the model results are acceptable when compared to the measured data.

Table 6.14: Calibration Statistical Metrics SG12

Metric Parameter	Calibration Simulation #1	Quality #1
R^2	0.701	Satisfactory
NSE	0.662	Satisfactory
ME	0.138	Very Good
MAE	0.349	Very Good
RMSE	0.460	Very Good
RSR	0.572	Good
1/2 Standard Deviation Obs.	2	Good

Note: Number of pair data (observed and simulated) = 30

6.3.13 Gage SG13 W Hall Rd. West at N. Tropical Trail – Calibration Results

Gage SG13 is located at the southeast corner of the W. Hall Rd. and N. Tropical Trail intersection. The stage hydrograph comparisons for Calibration #1 and Calibration #2 are provided below in **Figure 6.22** and **Figure 6.23**, respectively. The statistical metrics are provided in **Table 6.15**.




Figure 6.22: Gage SG13 W Hall Rd. West at N. Tropical Trail Calibration #1 Comparisons




Figure 6.23: Gage SG13 W Hall Rd. West at N. Tropical Trail Calibration #2 Comparisons

As seen in the figures above, the model results for both simulations are nearly identical. Additionally, the model tends to agree well with the lower recorded stages for both simulations. Conversely, the model tends to overpredict maximum conditions. Three of the statistical metrics are not satisfactory based on the study criteria. However, four of the statistical metrics were in acceptable ranges with three being very good.

One important item to note is that County staff estimated peak stages at this location during Hurricane Irma to be approximately 6.2-ft (NAVD88) based on field observations. However, this elevation was not recorded in the gage logs. Based on the model results, the maximum overall stage simulated during Hurricane Irma occurred approximately on Sept 9, 2017, at 2:45 am was 5.93-ft which shows the model is within 3.2-inches of the estimated stage based on the field observations for Calibration #1. Though this calibration report was intended to compare with surveyed flood levels, comparison with the field observations does indicate that the model provides a fairly good estimate for the overall peak stage.

Several calibration iterations were conducted to improve the comparisons at this location, but all had little impact. Ideally, a new survey would be conducted to verify the pipe dimensions, materials, inverts, and site conditions. However, the drainage at this location was improved (RefDoc NMI_221_CP) after the 2017 calibration/verification events and prior to the start of this study. Given that the hydraulic network has been upgraded since 2017, no further changes were made to the model to calibrate to this gage.

Table 6.15: Calibration Statistical Metrics SG13

Metric Parameter	Calibration Simulation #1	Quality #1	Calibration Simulation #2	Quality #2
R²	0.394	Not Satisfactory	0.402	Not Satisfactory
NSE	-1.144	Not Satisfactory	-1.239	Not Satisfactory
ME	-0.117	Very Good	-0.093	Very Good
MAE	0.290	Very Good	0.316	Very Good
RMSE	0.501	Very Good	0.512	Very Good
RSR	1.437	Not Satisfactory	1.468	Not Satisfactory
1/2 Standard Deviation Obs.	1	Satisfactory	1	Satisfactory

Note: Number of pair data (observed and simulated) = 27

6.3.14 Gage SG17 PICA Basin – Calibration Results

Gage SG17 is located on the east side of the access road to the Pine Island Harvey Grove Pumps. The stage hydrograph comparisons for Calibration #1 are provided below in **Figure 6.24**. Like the comparisons for SG11 and SG12, the modeled and measured peak stages compare quite well. The Calibration #1 modeled peak stage is 2.11-ft (NAVD88), which is approximately 1.1-inches above the measured peak stage (2.02-ft, NAVD88). However, the model's stage recovery tends to be much faster than what was measured in the field. As previously stated, the actual pump operation data during the calibration period was unavailable. Consequently, the modeled pumping rate at this location was based on the pump station's design plans. However, stage hydrograph comparisons indicate that the actual pump operation during the calibration period were quite different than the designed pumping rates. Specifically, the pumping rate appears to be much lower during the calibration storm event. This shows that the pumping operation at Pine Island influences the recovery of the drainage system upstream of the access road. Regardless of differences in the recovery leg, the statistical metrics (**Table 6.16**) range from satisfactory to very good, indicating that the model reasonably represents what physically occurred during Hurricane Irma.

No comparisons were conducted for this particular gage for Calibration #2 since this was a location in the model that was converted to a time-stage node for that analysis.




Figure 6.24: Gage SG17 PICA Basin Calibration #1 Comparisons

Table 6.16: Calibration Statistical Metrics SG17

Metric Parameter	Calibration Simulation #1	Quality #1
R²	0.695	Satisfactory
NSE	0.648	Satisfactory
ME	0.157	Very Good
MAE	0.363	Very Good
RMSE	0.472	Very Good
RSR	0.584	Good
1/2 Standard Deviation Obs.	2	Good

Note: Number of pair data (observed and simulated) = 30

6.3.15 Gage SG18 PICA Riverside – Calibration Results

SG18 is located downstream of the Pine Island Harvey Grove Pumps access road. The stage hydrograph comparisons for Calibration #1 and Calibration #2 are provided below in **Figure 6.25** and **Figure 6.26**, respectively. The Calibration #1 modeled peak stage is 1.83-ft (NAVD88), which is approximately 0.8-inches below the measured peak stage (1.90-ft, NAVD88). The peak stage for Calibration #2 is 1.88-ft (NAVD88), which is 0.08-inches below the measured peak stage.




Figure 6.25: Gage SG18 PICA Riverside Calibration #1 Comparisons




Figure 6.26: Gage SG18 PICA Riverside Calibration #2 Comparisons

The statistical metrics provided in **Table 6.17** show very good correlation between the measured and modeled stage data.

Table 6.17: Calibration Statistical Metrics SG18

Metric Parameter	Calibration Simulation #1	Quality #1	Calibration Simulation #2	Quality #2
R²	0.971	Very Good	0.938	Very Good
NSE	0.923	Very Good	0.883	Very Good
ME	-0.093	Very Good	-0.135	Very Good
MAE	0.136	Very Good	0.176	Very Good
RMSE	0.165	Very Good	0.203	Very Good
RSR	0.274	Very Good	0.302	Very Good
1/2 Standard Deviation Obs.	3	Very Good	3	Very Good

Note: Number of pair data (observed and simulated) = 30

6.3.16 Gage SG19 PICA North – Calibration Results

SG19 is located within the northern Pine Island impoundment. The stage hydrograph comparisons for Calibration #1 and Calibration #2 are provided below in **Figure 6.27** and **Figure 6.28**, respectively. The Calibration #1 modeled peak stage is 2.16-ft (NAVD88), which is approximately 1.1-inches above the measured peak stage (2.07-ft, NAVD88). The peak stage for Calibration #2 is 2.10-ft (NAVD88), which is 0.4-inches above the measured peak stage.




Figure 6.27: Gage SG19 PICA North Calibration #1 Comparisons




Figure 6.28: Gage SG19 PICA North Calibration #2 Comparisons

Like the SG18 comparisons, both simulations show very good correlation between the measured and modeled data as shown in **Table 6.18** below.

Table 6.18: Calibration Statistical Metrics SG19

Metric Parameter	Calibration Simulation #1	Quality #1	Calibration Simulation #2	Quality #2
R²	0.975	Very Good	0.951	Very Good
NSE	0.950	Very Good	0.891	Very Good
ME	-0.074	Very Good	-0.155	Very Good
MAE	0.104	Very Good	0.195	Very Good
RMSE	0.142	Very Good	0.209	Very Good
RSR	0.220	Very Good	0.325	Very Good
1/2 Standard Deviation Obs.	3	Very Good	3	Very Good

Note: Number of pair data (observed and simulated) = 30

6.4 Verification Analysis

The verification period of record is from 10/01/2017 – 11/03/2017. Like the calibration, the verification analysis included comparisons between measured and modeled results for each of these staff gages. The results of the final verification analyses are provided in the subsequent sections. Like the calibration, there are two verification analyses for each gage unless otherwise stated. Verification #1 is the simulation that includes the calibration parameter adjustments and the adjusted boundary conditions provided by AEI. Verification #2 is identical to Verification #1 except internal boundary conditions were incorporated into the model at the locations specified in **Table 6.2**.

6.4.1 Gage SG1 Sykes Creek at Sea Ray Dr. – Verification Results

The verification analysis at SG1 indicates good correlation between the measured and modeled results (**Figure 6.29**), especially for the larger storm event in early October. Additionally, the modeled peak stage (1.49-ft, NAVD88) is approximately 0.72-inches above the measured peak stage (1.42-ft, NAVD88), however, the model does have a tendency to over-predict the stage for the smaller storm event in mid to late October. With that said, the average difference is fairly minor (3-inches). No comparisons were conducted for this particular gage for Verification #2 since this location in the model was converted to a time-stage node for that analysis.




Figure 6.29: Gage SG1 Sykes Creek at Sea Ray Dr. Verification #1 Comparisons

The statistical metrics listed in **Table 6.19** also show acceptable correlation between the measured and modeled stages. Most parameters are good to very good. The only exception is the satisfactory NSE.

Table 6.19: Verification Statistical Metrics SG1

Metric Parameter	Verification Simulation #1	Quality #1
R²	0.941	Very Good
NSE	0.675	Satisfactory
ME	-0.229	Very Good
MAE	0.244	Very Good
RMSE	0.282	Very Good
RSR	0.562	Good
1/2 Standard Deviation Obs.	2	Good

Note: Number of pair data (observed and simulated) = 37

6.4.2 Gage SG2 East Hall Rd. North – Verification Results

The verification analysis for SG2 shows excellent correlation between measured and model data for both verification simulations (**Figure 6.30**). The stages are within 4.2-inches for the modeled peak stage (2.27-ft, NAVD88) compared to the measured peak stage (1.92-ft, NAVD88) for the Verification #1 simulations.




Figure 6.30: Gage SG2 East Hall Rd. North Verification #1 Comparisons

North Merritt Island H&H Modeling Study

Section 6.0 – Model Calibration and Verification

There is a much better correlation between the modeled and measured stages for the Verification #2 simulation. Like the calibration analyses, this gage is sensitive to the operation of the East Hall Road Pumps. This is evident looking at the Verification #2 results in **Figure 6.31**. In fact, the modeled peak stage (2.07-ft, NAVD88) is only 1.8-inches above the measured peak stage.




Figure 6.31: Gage SG2 East Hall Rd. North Verification #2 Comparisons

The statistical results in **Table 6.20** show very good correlation between the model results and the measured stages for both simulations at this gage location.

Table 6.20: Verification Statistical Metrics SG2

Metric Parameter	Verification Simulation #1	Quality #1	Verification Simulation #2	Quality #2
R²	0.915	Very Good	0.987	Very Good
NSE	0.846	Very Good	0.961	Very Good
ME	-0.147	Very Good	-0.089	Very Good
MAE	0.177	Very Good	0.095	Very Good
RMSE	0.224	Very Good	0.113	Very Good
RSR	0.387	Very Good	0.196	Very Good
1/2 Standard Deviation Obs.	3	Very Good	3	Very Good

Note: Number of pair data (observed and simulated) = 37

6.4.3 Gage SG3 East Hall Rd. Pump House – Verification Results

The verification analysis for SG3 shows good correlation between measured and model data (**Figure 6.32**). The peak for the Verification #1 simulation is 2.32-ft (NAVD88) compared to the measured peak stage of 1.90-ft (NAVD88). This is a difference in peak stage of approximately 5.0-inches. The subsequent smaller storm event in late October also shows simulated stages higher than the measured stage. However, this gage is in close proximity of the East Hall Road Pumps. Therefore, it is sensitive to the pump operation. Keep in mind that the pumps at this location were modeled with best available information, however, the operation information specified in the model does not account for all pump operation changes that occurred during this verification time period as they were not documented. No comparisons were conducted for this gage for Verification #2 because node NFF2020 was converted to a time-stage node for the Verification #2 analysis.




Figure 6.32: Gage SG3 East Hall Rd. Pump House Verification #1 Comparisons

Regardless of the pump operation sensitivity, the results in **Table 6.21** show very good correlation between the measured and model stages at this location.

Table 6.21: Verification Statistical Metrics SG3

Metric Parameter	Verification Simulation #1	Quality #1
R^2	0.903	Very Good
NSE	0.842	Very Good
ME	-0.140	Very Good
MAE	0.168	Very Good
RMSE	0.233	Very Good
RSR	0.392	Very Good
1/2 Standard Deviation Obs.	3	Very Good

Note: Number of pair data (observed and simulated) = 37

6.4.4 Gage SG4 East Hall Rd. Barge Canal Ditch – Verification Results

Similar to the SG3 comparisons, the verification analysis for SG4 shows good correlation between measured and model data (**Figure 6.33**). The peak stage for Verification #1 is 2.32-ft (NAVD88) compared to the measured peak stage of 1.89-ft (NAVD88). This is a difference in peak stage of approximately 5.2-inches. The subsequent smaller storm event in late October also shows simulated stages higher than the measured stage like what occurred at SG3 for the Verification #1 simulation. However, this gage is in very close proximity of the Hall Road Pumps. Therefore, it is also sensitive to the pump operation. No comparisons were conducted for this gage for Verification #2 since this location was converted to a time-stage node for the Verification #2 analysis.




Figure 6.33: Gage SG4 East Hall Rd. Barge Canal Ditch Verification #1 Comparisons

The statistical results in **Table 6.22** show very good correlation between the measured and model stages.

Table 6.22: Verification Statistical Metrics SG4

Metric Parameter	Verification Simulation #1	Quality #1
R²	0.905	Very Good
NSE	0.841	Very Good
ME	-0.143	Very Good
MAE	0.163	Very Good
RMSE	0.231	Very Good
RSR	0.394	Very Good
1/2 Standard Deviation Obs.	3	Very Good

Note: Number of pair data (observed and simulated) = 37

6.4.5 Gage SG5 Chase Hammock at Judson Rd. – Verification Results

The verification analysis for SG5 shows good correlation between measured and model data (**Figure 6.34** and **Figure 6.35**). The difference between the modeled (2.27-ft, NAVD88) and measured peak stage (2.10-ft, NAVD88) is only 2.0-inches for the Verification #1 simulation. The subsequent smaller storm event in late October has a modeled peak stage within 5-inches of the measured value for Verification #1 as well.

The Verification #2 simulation shows even better correlation between the modeled and measured data. For example, the modeled peak stage is approximately 2.20-ft (NAVD88) which is within 1.2-inches of the measured peak stage. The statistical metrics shown in **Table 6.23** also show very good correlation between the modeled and measured stages for both simulations.




Figure 6.34: Gage SG5 Chase Hammock at Judson Rd. Verification #1 Comparisons




Figure 6.35: Gage SG5 Chase Hammock at Judson Rd. Verification #2 Comparisons

Table 6.23: Verification Statistical Metrics SG5

Metric Parameter	Verification Simulation #1	Quality #1	Verification Simulation #2	Quality #2
R²	0.891	Very Good	0.967	Very Good
NSE	0.883	Very Good	0.917	Very Good
ME	0.035	Very Good	0.070	Very Good
MAE	0.126	Very Good	0.112	Very Good
RMSE	0.172	Very Good	0.145	Very Good
RSR	0.337	Very Good	0.284	Very Good
1/2 Standard Deviation Obs.	3	Very Good	3	Very Good

Note: Number of pair data (observed and simulated) = 37

6.4.6 Gage SG6 Crisafulli at Judson Rd. – Verification Results

For both verification simulations, the model results agree quite well with the measured stage readings at SG6 (Figure 6.36 and Figure 6.37). The modeled peak stages for Verification #1 and Verification #2 are 2.44-ft (NAVD88) and 2.49-ft (NAVD88), respectively. Both are within approximately 2.3-inches of the measured maximum stage (2.30-ft, NAVD88). Additionally, the peak stages during the second storm event in October are within 6-inches of the measured peak stage for both verification simulations.




Figure 6.36: Gage SG6 Crisafulli at Judson Rd. Verification #1 Comparisons

The statistical metrics shown in Table 6.24, show both verification simulations agree well with the measured data. Although, the results for Verification #2 agree slightly better based on the statistical metric criteria.




Figure 6.37: Gage SG6 Crisafulli at Judson Rd. Verification #2 Comparisons

The statistical metrics shown in **Table 6.24** are mostly classified as very good, this shows that both verification simulations agree well with the measured data. Although, the results for Verification #2 agree slightly better based on the statistical metric criteria.

Table 6.24: Verification Statistical Metrics SG6

Metric Parameter	Verification Simulation #1	Quality #1	Verification Simulation #2	Quality #2
R²	0.893	Very Good	0.959	Very Good
NSE	0.680	Satisfactory	0.731	Good
ME	-0.234	Very Good	-0.261	Good
MAE	0.257	Very Good	0.261	Very Good
RMSE	0.309	Very Good	0.284	Very Good
RSR	0.558	Good	0.512	Good
1/2 Standard Deviation Obs.	2	Good	2	Good

Note: Number of pair data (observed and simulated) = 37

6.4.7 Gage SG7 East Crisafulli at Joseph Ct. – Verification Results

Like SG6, the model results at SG7 agree quite well with the measured stage readings (**Figure 6.38** and **Figure 6.39**). The modeled peak stages for Verification #1 and Verification #2 are 2.48-ft (NAVD88) and 2.53-ft (NAVD88), respectively. Both are within approximately 1.6-inches of the measured maximum stage (2.40-ft, NAVD88). Additionally, the peak stages during the second storm event in October are also within 6-inches of the measured peak stage for both verification simulations.




Figure 6.38: Gage SG7 East Crisafulli at Joseph Ct. Verification #1 Comparisons




Figure 6.39: Gage SG7 East Crisafulli at Joseph Ct. Verification #2 Comparisons

The statistical metrics shown in **Table 6.25** are mostly classified as very good, this shows that both verification simulations agree well with the measured data. However, the results for Verification #1 agree slightly better based on the statistical metrics.

Table 6.25: Verification Statistical Metrics SG7

Metric Parameter	Verification Simulation #1	Quality #1	Verification Simulation #2	Quality #2
R²	0.937	Very Good	0.968	Very Good
NSE	0.707	Good	0.735	Good
ME	-0.248	Very Good	-0.269	Good
MAE	0.248	Very Good	0.269	Very Good
RMSE	0.301	Very Good	0.287	Very Good
RSR	0.534	Good	0.508	Good
1/2 Standard Deviation Obs.	2	Good	2	Good

Note: Number of pair data (observed and simulated) = 37

6.4.8 Gage SG8 N Courtenay at Pine Island – Verification Results

The measured vs. modeled stage hydrograph comparisons for both verification simulations are provided in **Figure 6.40** and **Figure 6.41**. Both simulations compare extremely well based on visual inspection of the stage hydrographs. The maximum stages for Verification #1 and Verification #2 are 2.41-ft (NAVD88) and 2.49-ft (NAVD88), respectively. Both are within approximately 2.5-inches of the measured maximum stage (2.28-ft, NAVD88). Additionally, the measured peak stage for the second storm event in October is approximately within 6-inches of the modeled peak stage for both verification simulations.




Figure 6.40: Gage SG8 N Courtenay at Pine Island Verification #1 Comparisons




Figure 6.41: Gage SG8 N Courtenay at Pine Island Verification #2 Comparisons

The statistical metrics for this gage provided in **Table 6.26** range from satisfactory to very good. Both verification simulations agree well with the measured data, however, results for Verification #2 agree slightly better based on the statistical metrics.

Table 6.26: Verification Statistical Metrics SG8

Metric Parameter	Verification Simulation #1	Quality #1	Verification Simulation #2	Quality #2
R²	0.861	Very Good	0.960	Very Good
NSE	0.544	Satisfactory	0.597	Satisfactory
ME	-0.280	Good	-0.332	Good
MAE	0.315	Very Good	0.332	Very Good
RMSE	0.373	Very Good	0.350	Very Good
RSR	0.666	Satisfactory	0.626	Satisfactory
1/2 Standard Deviation Obs.	1	Satisfactory	1	Satisfactory

Note: Number of pair data (observed and simulated) = 37

6.4.9 Gage SG9 Pine Island 1 Mile North of North Courtenay – Verification Results

The model results for both verification simulations at SG9 agree well with the measured data as shown in **Figure 6.42** and **Figure 6.43**. There is one outlier in the measured data noted on 10/14/2017. The reading on this date seems inconsistent with the other readings suggesting either a misread when recording the stage or that blockage somewhere in the drainage system may have occurred which resulted in increased stages. Regardless, the peak stages for Verification #1 (2.29-ft, NAVD88) and Verification #2 (2.40-ft, NAVD88) are within 2.9-inches of the measured peak stage (2.16-ft, NAVD88). Additionally, the modeled peak stages for the second storm event are approximately within 6-inches of the measured peak stage for both verification simulations.




Figure 6.42: Gage SG9 Pine Island 1 Mile North of North Courtenay Verification #1 Comparisons




Figure 6.43: Gage SG9 Pine Island 1 Mile North of North Courtenay Verification #2 Comparisons

The statistical metrics for this gage provided in **Table 6.27** generally range from satisfactory to very good, however two metrics are classified as not satisfactory for Verification #1. Results for Verification #2 agree much better based on the statistical analysis indicating this area is also sensitive to the pump operation at Pine Island.

Table 6.27: Verification Statistical Metrics SG9

Metric Parameter	Verification Simulation #1	Quality #1	Verification Simulation #2	Quality #2
R²	0.699	Satisfactory	0.946	Very Good
NSE	0.380	Not Satisfactory	0.650	Satisfactory
ME	-0.273	Good	-0.305	Good
MAE	0.401	Very Good	0.313	Very Good
RMSE	0.457	Very Good	0.343	Very Good
RSR	0.776	Not Satisfactory	0.583	Good
1/2 Standard Deviation Obs.	1	Satisfactory	1	Satisfactory

Note: Number of pair data (observed and simulated) = 37

6.4.10 Gage SG10 Pine Island Harvey Grove Pump – Verification Results

As shown in **Figure 6.44**, the modeled peak stage for Verification #1 (1.99-ft, NAVD88) matches the measured value (1.86-ft, NAVD88) quite well. The Verification #1 peak stage for the second October storm event (1.02-ft, NAVD88) is identical to the measured maximum stage (1.02-ft). The recovery legs for both storm events are, however, inaccurate for this simulation. This is primarily attributed to the pump operation.




Figure 6.44: Gage SG10 Pine Island Harvey Grove Pump Verification #1 Comparisons

The impact of the pump operations is evident based on the stage hydrograph comparisons shown in **Figure 6.45**. The results for Verification #2 compare much better with the measure stages. The modeled peak stage for Verification #2 (1.94-ft, NAVD88) is 1-inch above the measured value (1.86-ft, NAVD88).




Figure 6.45: Gage SG10 Pine Island Harvey Grove Pump Verification #2 Comparisons

Additionally, the statistical analysis (**Table 6.28**) shows that Verification #1 has three parameters that are not satisfactory while Verification #2 has very good correlation between the measured and modeled stages.

Table 6.28: Verification Statistical Metrics SG10

Metric Parameter	Verification Simulation #1	Quality #1	Verification Simulation #2	Quality #2
R²	0.314	Not Satisfactory	0.988	Very Good
NSE	0.251	Not Satisfactory	0.965	Very Good
ME	-0.104	Very Good	-0.084	Very Good
MAE	0.465	Very Good	0.099	Very Good
RMSE	0.530	Very Good	0.114	Very Good
RSR	0.853	Not Satisfactory	0.184	Very Good
1/2 Standard Deviation Obs.	1	Satisfactory	3	Very Good

Note: Number of pair data (observed and simulated) = 37

6.4.11 Gage SG11 Pine Island West – Verification Results

The comparisons at SG11 are similar to those discussed for SG10. The modeled maximum stage matches the measured maximum stage (**Figure 6.46**), but the modeled recovery is much faster for Verification #1. Again, this is attributed to the unknowns related to the pump operation at Pine Island. When measured stages are compared to the modeled stages in Verification #2 (**Figure 6.47**), the modeled results compare much better. This is because of the internal boundary condition that was included at SG17 where water levels were set identical to those measured in the field. This approach forces stages downstream of SG11 to be consistent with the actual pump operation during the validation period. The modeled peak stage for Verification #2 (1.67-ft, NAVD88) is also within 0.03-ft of the measured peak stage.

Like the calibration analysis, node NPI1030 was converted to a time-stage node for the Verification #2 analysis. The comparisons for Verification #2 were included in this section to show how the stages upstream of the gage are fairly consistent with stages at the pump location (SG17 at node NPI1030). Additionally, this comparison demonstrates how sensitive the upstream stages are to the pumping operations at Pine Island.




Figure 6.46: Gage SG11 Pine Island West Verification #1 Comparisons




Figure 6.47: Gage SG11 Pine Island West Verification #2 Comparisons

Additionally, the statistical analysis (**Table 6.29**) shows that Verification #1 has three parameters that are not satisfactory. However, Verification #2 has very good correlation between the measured and modeled stages with the boundary condition at SG17 which is expected.

Table 6.29: Verification Statistical Metrics SG11

Metric Parameter	Verification Simulation #1	Quality #1	Verification Simulation #2	Quality #2
R²	0.040	Not Satisfactory	0.998	Very Good
NSE	0.011	Not Satisfactory	0.993	Very Good
ME	0.000	Very Good	0.041	Very Good
MAE	0.531	Good	0.044	Very Good
RMSE	0.607	Very Good	0.050	Very Good
RSR	0.980	Not Satisfactory	0.080	Very Good
1/2 Standard Deviation Obs.	1	Satisfactory	3	Very Good

Note: Number of pair data (observed and simulated) = 37

6.4.12 Gage SG12 PICA South – Verification Results

The model results at SG12 are similar to those at SG11 for Verification #1. The modeled peak stages tend to agree extremely well with the measured peak stages (**Figure 6.48**), but the modeled recovery is much faster for Verification #1. Again, this is attributed to unknowns in the pump operation at Pine Island. At this gage location, the modeled peak stage (1.70-ft, NAVD88) is within an inch of the measured peak stage (1.64-ft, NAVD88). Additionally, the measured peak stage (0.90-ft, NAVD88) and modeled peak stage (0.70-ft, NAVD88) for the second storm event in October agree very well. Like the previous location, however, the pump operation at Pine Island reflected in the model data does not appear to be consistent with actual operation conducted during the validation period. This is also evident in the statistical comparisons shown in **Table 6.30**. Consequently, this location (Node: NPI1030) is one where internal boundary conditions were defined for Verification #2. As such, no comparisons are included for this location.




Figure 6.48: Gage SG12 PICA South Verification #1 Comparisons

Table 6.30: Verification Statistical Metrics SG12

Metric Parameter	Verification Simulation #1	Quality #1
R²	0.043	Not Satisfactory
NSE	0.003	Not Satisfactory
ME	-0.070	Very Good
MAE	0.536	Good
RMSE	0.605	Very Good
RSR	0.984	Not Satisfactory
1/2 Standard Deviation Obs.	1	Satisfactory

Note: Number of pair data (observed and simulated) = 37

6.4.13 Gage SG13 W Hall Rd. West at N. Tropical Trail – Verification Results

Similar to the calibration results at this location, Verification #1 and Verification #2 results are nearly identical (**Figure 6.49** and **Figure 6.50**). Also, the modeled stages for both simulations tend to agree well with the measured stage data except during peak conditions. Statistically, however, the model adequately represents the measured data during the verification period for both verification simulations (**Table 6.31**).

It is recommended that model calibration in this area be revisited to incorporate current conditions at this location. As stated in the calibration analysis, the drainage system at this location was recently upgraded prior to the start of this study. Therefore, additional calibration/verification efforts are recommended to further improve the model accuracy at this gage location.




Figure 6.49: Gage SG13 W Hall Rd. West at N. Tropical Trail Verification #1 Comparisons




Figure 6.50: Gage SG13 W Hall Rd. West at N. Tropical Trail Verification #2 Comparisons

Table 6.31: Verification Statistical Metrics SG13

Metric Parameter	Verification Simulation #1	Quality #1	Verification Simulation #2	Quality #2
R²	0.749	Satisfactory	0.746	Satisfactory
NSE	0.634	Satisfactory	0.634	Satisfactory
ME	-0.002	Very Good	-0.006	Very Good
MAE	0.205	Very Good	0.205	Very Good
RMSE	0.285	Very Good	0.285	Very Good
RSR	0.596	Good	0.596	Good
1/2 Standard Deviation Obs.	2	Good	2	Good

Note: Number of pair data (observed and simulated) = 36

6.4.14 Gage SG17 PICA Basin – Verification Results

Gage SG17 is in the immediate vicinity of SG12. Consequently, the comparisons between the measured and model data display similar behavior. The modeled peak stage for Verification #1 (1.70-ft, NAVD88) corresponds extremely well to the measured peak stage (1.67-ft, NAVD88). However, the modeled stage recovery tends to occur much more quickly than what was measured (**Figure 6.51**). As previously stated, the pump operation is based on best available information, but it appears to be inconsistent with actual field conditions which affects the recovery in the model. This is apparent in the statistical analysis shown in **Table 6.32** as well.

As previously discussed, this model location was converted to a time-stage node for use as an internal boundary for the Verification #2 analysis. The time-stage data were based on measured information at SG17. The result is flood staging that accounts for the actual pump operation.

This was done to determine if comparisons between the modeled and measured data at the gage locations affected by the Pine Island pump operation would improve. Note that no comparisons are included for this gage location for Verification #2 since this model location was converted to a time-stage node for the Verification #2 analysis.




Figure 6.51: Gage SG17 PICA Basin Verification #1 Comparisons

Table 6.32: Verification Statistical Metrics SG17

Metric Parameter	Verification Simulation #1	Quality #1
R²	0.041	Not Satisfactory
NSE	0.010	Not Satisfactory
ME	-0.041	Very Good
MAE	0.541	Good
RMSE	0.613	Very Good
RSR	0.981	Not Satisfactory
1/2 Standard Deviation Obs.	1	Satisfactory

Note: Number of pair data (observed and simulated) = 37

6.4.15 Gage SG18 PICA Riverside – Verification Results

Modeled stages for both Verification #1 and Verification #2 compare extremely well to the measured stages at gage SG18 as shown in **Figure 6.52** and **Figure 6.53**. The peak stages for Verification #1 (1.59-ft, NAVD88) and Verification #2 (1.62-ft, NAVD88) are nearly identical to the measured peak stage (1.60-ft, NAVD88) for both simulations.




Figure 6.52: Gage SG18 PICA Riverside Verification #1 Comparisons




Figure 6.53: Gage SG18 PICA Riverside Verification #2 Comparisons

Additionally, the statistical results in **Table 6.33** show that both verification simulations compare well with the measured data. All the statistical parameters are classified as very good based on the metrics used for the study.

Table 6.33: Verification Statistical Metrics SG18

Metric Parameter	Verification Simulation #1	Quality #1	Verification Simulation #2	Quality #2
R²	0.959	Very Good	0.915	Very Good
NSE	0.858	Very Good	0.911	Very Good
ME	-0.103	Very Good	-0.026	Very Good
MAE	0.135	Very Good	0.110	Very Good
RMSE	0.172	Very Good	0.136	Very Good
RSR	0.372	Very Good	0.295	Very Good
1/2 Standard Deviation Obs.	3	Very Good	3	Very Good

Note: Number of pair data (observed and simulated) = 37

6.4.16 Gage SG19 PICA North – Verification Results

Model results for Verification #1 (Figure 6.54) and Verification #2 (Figure 6.55) compare extremely well to the measured data at gage SG19. Peak stages for Verification #1 (1.87-ft, NAVD88) and Verification #2 (1.79-ft, NAVD88) are both within 1.9-inches or less of the measured peak stage (1.71-ft, NAVD88). Verification #1, however, tends to compare much better to the measured data based on the very good correlation shown in Table 6.34. This may be partly related to using the estimated Pine Island pump operations while also specifying the time-stage data at the upstream end of the pump for the Verification #2 simulation. Regardless, both simulations are representative of the actual field conditions during the validation period based on the statistical metrics (Table 6.34).




Figure 6.54: Gage SG19 PICA North Verification #1 Comparisons




Figure 6.55: Gage SG19 PICA North Verification #2 Comparisons

Table 6.34: Verification Statistical Metrics SG19

Metric Parameter	Verification Simulation #1	Quality #1	Verification Simulation #2	Quality #2
R²	0.869	Very Good	0.871	Very Good
NSE	0.844	Very Good	0.646	Satisfactory
ME	-0.058	Very Good	0.066	Very Good
MAE	0.108	Very Good	0.187	Very Good
RMSE	0.145	Very Good	0.218	Very Good
RSR	0.390	Very Good	0.587	Good
1/2 Standard Deviation Obs.	3	Very Good	1	Satisfactory

Note: Number of pair data (observed and simulated) = 37

6.5 Calibration / Verification Conclusions

In general, the model results compare very well to the measured data at most of the gage locations for the calibration and verification simulations. The model peak stages, in particular, agree extremely well with measured peak stages at every gage location except SG13. There are some inconsistencies with the recovery behavior of the stage hydrographs at some gage locations for the Calibration #1 and Verification #1 simulations. However, Calibration #2 and Verification #2 model results generally compare much better with the measured data in most cases. The improvements shown in the Calibration #2 and Verification #2 results suggests unknown operations at East Hall Rd. Pumps and Pine Island Harvey Grove Pumps are the cause of the discrepancies.

Lastly, it is recommended that further calibration and verification analyses be conducted at SG13 using current site conditions and storm events subsequent to the stormwater improvements to improve the model comparisons. Also, it is recommended that further calibration be conducted during the dry season to more accurately represent the study area during dry conditions, if possible.

7.0 Existing Conditions Analysis

This section of the report details the work performed as part of the existing conditions analysis of the NMI Watershed, including existing conditions model updates, critical duration analysis, design storm simulation, and floodplain development. This section also presents a discussion on the results of the H&H analysis.

7.1 Existing Conditions Model Updates

Post-2017 Improvements: The model used for calibration/verification was based on conditions at the time of Hurricane Irma in September 2017. To conduct the existing conditions analysis, model updates were performed to incorporate post-2017 improvements. A summary of these improvements and the affected model features is included in **Table 7.1** below.

Table 7.1: Summary of Drainage Structure Updates for Post-2017 Improvements

Description of Update	Model Feature Changes
Pine Island temporary pump in place for Hurricane Irma removed from the model	Link Flow set to NONE: PICA_Temp
Pine Island Pumps Operating Tables simulating manual drawdown pre-Irma	Operating Tables NB.p1_Drawdown and NB.p2_Drawdown were deleted from the model
Hall Road temporary pump in place for Hurricane Irma removed from the model	Link Flow set to NONE: Hall_Temp_Pump
Hall Road Pump Station Improvements (Reference Document NMI_020)	Updated Pump Links: RO6 and RO6A and their associated operating tables Added new Hall Rd. Cross Culvert Link: PG1840_3
W. Hall Road Outfall Improvements (Reference Document NMI_074)	New/Updated Links: PEE1060 and PEE2061
Bottom Clip Table simulating 2017 operations schedule of flashboards for control structures discharging to the Barge Canal was removed	Bottom Clip Tables Removed for Links: DSykesS_1, DSykesS_2, DSykes_3, L-3470DS, L-3480DS, L-3520DS, L-3530DS, L-3240DS, L-3550DS, L-3560DS, L-3610DS, L-3620DS

Boundary Conditions: In addition to incorporating post-2017 improvements, the boundary stage data were also updated for the design storm simulations. Boundary data in the calibration/verification model simulations were based on analysis of tailwater conditions throughout 2017, as discussed in previous sections of this report. For existing conditions and design storm simulations, a constant tailwater condition was used based on the Mean Higher High Water (MHHW) elevation at the Trident Pier NOAA gage (Gage 8721604) located in Port Canaveral, Florida (See **Figure 7.1**). The Mean Higher-High Water elevation (el. 1.10 NAVD) was chosen as the tailwater elevation, as it most closely correlated to historical stages observed in the IRL. This value is also in-line with data from the 2017 tailwater analysis, which show an estimated peak stage in the Banana River of 1.06-feet during Hurricane Irma. Refer to **Appendix C** for more information on the tailwater analysis.

Node Initial Water Conditions: Initial water elevations were revised based on the updated model network and new boundary conditions. Initial stages for groundwater nodes, overland flow nodes, and 1D nodes are based on a “hot start” simulation. Preliminary initial water elevations were set at 1D Nodes based on the tailwater elevation of 1.10-ft. Preliminary initial water elevations for groundwater and overland flow nodes were based on the model results from the calibration model for the date August 1, 2017. Using these elevations, the hot start simulation was then run. The hot start simulation for the existing conditions model starts at time = 0 and ends at time = 40 hours. The Hall Road and Pine Island pumps are operational during the hot start simulation, as the County has stated that drawdown at these pump stations 24-hours prior to a forecasted storm event is part of their standard emergency operating protocol. The results of the hot start simulation at 24 hours were extracted and used to specify the final initial stages for the existing conditions model.




Figure 7.1: NOAA Trident Pier Gage Datum Information

Overland Flow Weirs: Upon completion of the model updates discussed above, the model was simulated using the 100-year storm event and 8 critical durations, as discussed in **Section 7.2** below. The peak stages at each node were used to generate floodplain polygons which were reviewed in detail for any “glass walls” within 1D areas or between control volumes. 1D overflow weir links were added at each identified glass wall to allow flow between the 1D basins and/or control volumes.

7.2 Critical Duration Analysis

A critical duration storm analysis was performed for the NMI watershed through evaluation of its responses to storms of varying duration and return frequencies. The critical duration storm is defined for this study as the duration that produces the highest flood stages throughout the study area. A total of 48 storm events were simulated with durations of 1, 2, 4, 8, 24, 72, 96, 168, and 240 hours for each return frequency of Mean Annual, 5, 10, 25, 50, and 100-year, consistent with the FDOT critical duration approach. Rainfall volumes for the critical duration storm events were obtained from NOAA Atlas-14 Precipitation Frequency Estimates at the approximate center of the watershed. The rainfall amounts used for each simulation are presented in **Table 7.2** below.

Table 7.2: Critical Duration Storm Rainfall Amounts (inches)

Duration	Mean	5-Year	10-Year	25-Year	50-Year	100-Year
1 Hour	2.20	2.65	3.01	3.50	3.88	4.25
2 Hour	2.74	3.29	3.74	4.35	4.81	5.28
4 Hour	3.20	3.89	4.47	5.29	5.95	6.62
8 Hour	3.71	4.65	5.47	6.69	7.70	8.77
24 Hour	4.68	6.10	7.44	9.51	11.3	13.2
72 Hour	5.98	7.59	9.13	11.5	13.6	15.9
168 Hour (7 day)	7.62	9.22	10.8	13.1	15.2	17.5
240 Hour (10 day)	8.67	10.3	11.9	14.3	16.4	18.6

Each return frequency was evaluated and the storm duration producing the highest peak stage at each 1D and 1D Interface Node was identified. In general, the 24-hour storm event was found to produce the highest peak stages for the majority of the watershed, with the exception of smaller storm events (5-year and Mean Annual), where the critical duration was found to be 8-hours. The results of the critical duration storm analysis are summarized in **Table 7.3** below, which presents the quantity of nodes experiencing peak stage for each critical duration event. For example, for the 100-year storm event, the peak stage produced during the 24-hour duration exceeded the peak stage produced during the other durations for 705 nodes. As a result, the 24-hour storm is considered the critical duration for those nodes.

Table 7.3: Critical Duration Storm Analysis Summary
Quantity of Nodes with Highest Stages for Each Critical Duration Event

Duration	Mean	5-Year	10-Year	25-Year	50-Year	100-Year
1 Hour	212	199	186	160	140	129
2 Hour	54	51	34	26	19	18
4 Hour	365	186	85	29	14	13
8 Hour	391	479	495	439	389	380
24 Hour	244	418	553	671	740	705
72 Hour	14	27	32	30	28	97
168 Hour (7 day)	12	21	13	12	12	12
240 Hour (10 day)	191	96	33	17	13	12

Lowest value  Highest value

Notes: 1. "Nodes" includes both 1D Nodes and 1D Interface Nodes.

2. Some nodes have more than 1 critical duration identified and are counted under each identified duration. For example, some nodes predicted equal peak stages for the Mean Annual 4-hr and Mean Annual 8-hr, so those nodes are counted twice under the Mean Annual storm, once for the 4-hr and once for the 8-hr duration. As such, node totals may not be equal for each return frequency.

The critical duration was also found to vary spatially across the watershed, appearing to be primarily related to landuse and ground elevation. For each return frequency, the 24-hour duration produced the highest stages for nodes located in undeveloped, wetland, low-lying, and rural areas of the watershed, while the majority of nodes located in urbanized and high elevation areas experienced an 8-hour critical duration. **Figures 7.2, 7.3 and 7.4** depict the spatial distribution of critical durations for the 10-year, 25-year, and 100-year return frequencies, respectively.

Peak stages for all critical duration storm simulations (1D and 1D Interface nodes) are included in the electronic deliverables accompanying this report, under "Support Data".

North Merritt Island H&H Modeling Study

Section 7.0 – Existing Conditions Analysis




Figure 7.2: Critical Duration Analysis (10-year event)

North Merritt Island H&H Modeling Study

Section 7.0 – Existing Conditions Analysis




Figure 7.3: Critical Duration Analysis (25-year event)

North Merritt Island H&H Modeling Study

Section 7.0 – Existing Conditions Analysis




Figure 7.4: Critical Duration Analysis (100-year event)

7.3 Existing Conditions Analysis and Floodplain Generation

7.3.1 Design Storm Simulations: Nine design storms were simulated to evaluate the existing conditions throughout the NMI watershed. The 24-hour duration event was simulated for return frequencies of Mean Annual, 10, 25, 50, and 100-years. For larger storm events (25-year and 100-year), the 96-hour storm was also simulated based on SJRWMD permit requirements for landlocked systems, along with the 72-hour storm event. Rainfall amounts were obtained from SJRWMD, NOAA Atlas-14, and Brevard County's Land Development Code (LDC) and reviewed to determine the highest rainfall amount for each simulated storm event based on present-day engineering literature. NOAA Atlas-14 rainfall amounts were based on the approximate center of the watershed. Rainfall amounts and distributions for each simulated storm event are shown in **Table 7.4** below.

Table 7.4: Design Storm Rainfall Amounts (inches)

Return Frequency	Storm Duration (hr)	Rainfall Distribution	Rainfall NOAA Atlas-14	Rainfall SJRWMD	Rainfall Brevard Co. LDC	Rainfall Amount Used	Source Used
Mean Annual	24	SCS Florida Modified	4.68	5.0	-	5.0	SJRWMD
10-Year	24	SCS Florida Modified	7.44	7.75	7.9	7.9	Brevard LDC
25-Year	24	SCS Florida Modified	9.5	9.5	9.0	9.5	SJRWMD / NOAA Atlas-14
50-Year	24	SCS Florida Modified	11.3	-	-	11.3	NOAA Atlas-14
100-Year	24	SCS Florida Modified	13.2	13.0	11.0	13.2	NOAA Atlas-14
25-Year	72	SFWMD-72	11.5	-	-	11.5	NOAA Atlas-14
100-Year	72	SFWMD-72	15.9	-	-	15.9	NOAA Atlas-14
25-Year	96	SJRWMD-96	12.1	12.5	12.5	12.5	SJRWMD
100-Year	96	SJRWMD-96	16.5	17.0	-	17.0	SJRWMD

7.3.2 Floodplain Mapping: Floodplains were developed for all nine design storm simulations. These floodplains were developed using two methods: ① Within the 1D areas (1D basins, pond control volumes, and channel control volumes), level-pool floodplains were mapped based on the maximum stage for the node assigned to that feature, and ② Within the 2D areas, floodplains were mapped based on the *Two-Dimensional Overland Flow Floodplain Development* document prepared by Streamline Technologies, Inc. which uses surfaces generated in ICPR4 based on a 0.25-ft (3-inch) flood depth threshold. This process uses the maximum elevation animation to generate a surface in ICPR4 and compares that surface to the project DEM and a "ground" DEM based on the ICPR4 triangular mesh. The resulting floodplains were processed to remove "spackle" areas (floodplain polygons less than 2,500-ft² in size). Note that a feature class named "New_Development_Areas" was included in the "BaseMap" geodatabase deliverable. This feature class identifies locations where new developments have been constructed since the original DEM's LiDAR collection date. Modifications have been made to the DEM in these locations to account for storage and groundwater interaction based on the best available data (as discussed in **Section 3**). However, the DEM is not completely representative of the current ground surface in these areas. Therefore, floodplains within these areas have been excluded. Floodplain graphics for the 10, 25, and 100-year 24-hour storm events, along with the 25 and 100-year 96-hour storm events are shown in attached **Exhibits 3, through 7** that accompany this report. Floodplains for all nine simulated design storm events are provided with the electronic deliverables that accompany this report.

8.0 Discussion

8.1 Floodplain Discussion

Design Storm Simulations: The floodplains for the NMI watershed depict significant inundation for most simulated storm events, particularly in the low-lying central wetland areas of the watershed. This includes the Sykes Cree/ mosquito impoundment area north towards East Crisafulli Road. Roadway flooding is shown along several collector roads during the 10-year storm event, including East Crisafulli Road (**Figure 8.1**) and West Crisafulli Road (**Figure 8.2**).



Figure 8.1: 10-Year, 24-hr Floodplain along E. Crisafulli Rd.



Figure 8.2: 10-Year, 24-hr Floodplain along W. Crisafulli Rd.

Both locations above, along with other areas such as East Hall Road below (**Figure 8.3**), are expected to experience significant inundation of low-lying yards and driveways during the 10-year event.



Figure 8.3: 10-Year, 24-hr Floodplain along E. Hall Rd.

It should be noted that, while the above instances highlight a few observed areas of concern, a complete level of service evaluation of the watershed was not conducted as part of this study.

FEMA Comparison: The 100-year, 24-hour floodplains were compared to the effective Federal Emergency Management Agency (FEMA) floodplains for the watershed (Effective 01/29/2021). The floodplains developed for this study are largely in agreement with the FEMA floodplains where mapped. The current study's floodplains also include areas not previously mapped by FEMA, including much of the area south of West Hall Road and west of State Road 3, and the relic dunes along the east side of the watershed that border the Banana River. As discussed in **Section 7** of this report, areas of new development were excluded from the floodplains. In total, the 100-year, 24-hour floodplains developed for this study removed about 850-acres of floodplain area compared to the effective FEMA floodplains and added over 4600-acres of floodplain area. **Figure 8.4** below presents a visual depiction of the developed NMI floodplains compared to the Effective FEMA floodplains.




Figure 8.4: FEMA vs. 100-year, 24-hr Floodplain Comparison

8.2 Groundwater Discussion

Groundwater in the NMI watershed is affected by both rainfall and backwater effects from the IRL and Banana River. During large storm events, soils in low-lying areas become saturated and groundwater levels rise to the ground surface becoming ponded surface water. In these instances, recovery of the groundwater is achieved through evapotranspiration and lateral seepage into adjacent outfall canals. This scenario is reflected in the calibration model results for Hurricane Irma.

In the plan and profile shown below (**Figure 8.5**), the modeled groundwater within the area south of Hall Road can be seen rising above the ground surface during Hurricane Irma. The predicted high groundwater levels in this area are consistent with observations made by both residents and County staff for this area.




Figure 8.5: Plan and Profile of Groundwater Model Results at Hall Road

Figure 8.6 below presents the time-series data for several groundwater nodes located north of Hall Road, each located in low-lying areas where the groundwater levels exceeded or nearly exceeded the ground surface during Hurricane Irma and the October rain events that followed. In this graph, groundwater nodes 15366 and 15379 are both located within 75-feet of a roadside canal which connects to the IRL, and groundwater node 13444 is located over 2,000-feet away from the canal bank. The time series data presented shows the recovery of these groundwater nodes after Hurricane Irma and the October rain events. Groundwater recovery at the two nodes located adjacent to the outfall canal (15366 and 15379) is

notably quicker than the recovery at groundwater node 13444. This can be attributed to increased lateral seepage from the adjacent nodes into the outfall canal given their close proximity to the ditch. Groundwater recovery at node 13444 is more limited and results in prolonged periods of high groundwater and saturated soils. High groundwater conditions are compounded with subsequent storm events, such as those seen in October 2017 following Hurricane Irma and can result in recurrent and more severe flooding than what is predicted under normal soil moisture conditions.

Conversely, dry season groundwater levels at Nodes 15366 and 15379 do not fall as low or as quickly as the node located further away. Groundwater levels in these areas are affected by surface water fluctuations in the adjacent outfall canal and IRL, whereas Node 13444 is further away and is buffered from the fluctuations thus exhibiting reduced levels of impact.




Figure 8.6: Groundwater Time-Series Graph for Nodes 13444, 15366, and 15379 from 2017 Calibration / Verification Model results

References

Collective Water Resources, LLC, 2019. Minimum Flows and Levels Program Hydrologic Modeling Services for Lakes Johns and Avalon in Orange County, St. Johns River Water Management District Contract 32922, Work Order 1 July 2019.

Downer, Charles W. and Ogden, F.L. 2006. Gridded Surface Subsurface Hydrologic Analysis (GSSHA) User's Manual. Army Corps of Engineers. ERDC/CHL SR-06-1,

Interflow Engineering, LLC, 2008. Myakka River Watershed Initiative, Water Budget Model Development and Calibration - Final Report. Tampa, Florida

Moriasi, D., Arnold, J., Van Liew, M., Bingner, R., Harmel, R. & Veith, T., 2007. Model evaluation guidelines for systemic quantification of accuracy in watershed simulations. Trans. ASABE, 50(3), 885-900.

Moriasi, D., Gitau, M., Pai, N., & Daggupati, P., 2015. Hydrologic and Water Quality Models: Performance Measures and Evaluation Criteria. Trans. ASABE, 58(6), 1763-1785.

NRCS, 1986. Technical Release 55 Urban Hydrology for Small Watersheds. United States Department of Agriculture. Washington, D.C.

Ree, W.O. and Palmer, V.J., 1949. Flow of Water in Channels Protected by Vegetative Linings. United States Department of Agriculture. Washington, D.C.

Singh, J., Knapp, H., & Demissie, M., 2004. Hydrologic modeling of the Iroquois River watershed using HSPF and SWAT. ISWS CR 2004-08. Champaign, Ill.: Illinois State Water Survey.

Smajstrla, A.G., 1990. Agricultural Field Scale Irrigation Requirements Simulation (AFSIRS) Model Technical Manual Version 5.5. Agricultural Engineering Department, University of Florida, Gainesville, FL.

Streamline Technologies, Inc., 2020. Southern Lee County Flood Mitigation Plan, ICPR4 Modeling of East of I-75 Overland Collection Drainageway Concept Project and Crew-Flint Pen Hydrologic Restoration Concept – Final Report. Winter Springs, Florida.

Streamline Technologies, Inc., 2021. ICPR4 Hydrologic Modeling Support For Johns and Avalon Lakes. Winter Springs, Florida.



BREVARD COUNTY
NATURAL RESOURCES
MANAGEMENT DEPARTMENT

NORTH MERRITT ISLAND
H&H MODELING STUDY

1D MODEL NETWORK

EXHIBIT
1

S&A SINGHOFEN & ASSOCIATES, INC.
STORMWATER MANAGEMENT AND CIVIL ENGINEERING





 SINGHOFEN & ASSOCIATES, INC. STORMWATER MANAGEMENT AND CIVIL ENGINEERING	BREVARD COUNTY NATURAL RESOURCES MANAGEMENT DEPARTMENT	NORTH MERRITT ISLAND H&H MODELING STUDY	EXISTING CONDITIONS FLOODPLAINS 25-YEAR, 96-HOUR	EXHIBIT 6
--	---	--	---	----------------------




 SINGHOFEN & ASSOCIATES, INC. STORMWATER MANAGEMENT AND CIVIL ENGINEERING	BREVARD COUNTY NATURAL RESOURCES MANAGEMENT DEPARTMENT	NORTH MERRITT ISLAND H&H MODELING STUDY	EXISTING CONDITIONS FLOODPLAINS 100-YEAR, 96-HOUR EXHIBIT 7
--	---	--	--

Appendix A

North Merritt Island

HydroDEM Update Memo

prepared by Atkins, September 2020



Memo

To: Allyson Hunt, PE


From: Joe Walter, PE	Email: joe.walter@atkinsglobal.com
Date: 28 September 2020	Phone: 407-806-4486
Ref: Atkins Project 100071502	cc: Chris Thompson, PE File

Subject: Draft North Merritt Island HydroDEM update

The purpose of this memo is to summarize the steps taken to develop the Hydro DEM. This DEM represents bathymetric updates for channels; natural inland submerged depressional areas; and Indian River Lagoon, Banana River and Canaveral Barge Canal area within the project domain. The purpose of the hydro corrections is to enable a connection between groundwater and surface waters within the 2D model domain and to cut irregular cross sections for channel segments in the 1D model domain.

Data Used

- Channel inverts and dimensions from ICPRv3 model updated by DRMP (*NMI_BREVARD_w_NASA.ICP*)
- NOAA navigational charts
- SWAMP database
- Morgan & Eklund Channel Cross Section Survey August 13, 2020
- 2007 DEM
- 2019 Aerials – to delineate extent of update



HydroDEM update process

1. Identify the Extent of the DEM update
 - Indian River Lagoon, Banana River, and Canaveral Barge Canal portions of the DEM, this extent represented the area in green in the figure below, which include portions of the 2007 DEM identified as NULL.



- For interior portions of the DEM, the update extent included modeled channels and naturally ponded areas identified from the DEM. Update extent is shown in pink in the image below.






2. Generate a 3D line at the boundary to tie the updated area into the existing topography.
 - The figure below shows the extent of the 3D line extracting elevations from the existing DEM. A similar data was generated for the interior area.




3. Develop 3D data points and breaklines to update the interior of the update extents
 - Indian River Lagoon and Banana River extent used data extracted from NOAA navigational charts and aerial imagery. NOAA navigational charts provided depths for boaters referenced to Mean-Lower-Low Water (MLLW). For the project area, using the Trident Pier as the closest reference elevation the MLLW was converted to NAVD88 using a -2.83 conversion factor. Depth points were digitized, MLLW depths recorded,

and adjusted. The images below show Datums at Trident Pier, NOAA navigational chart depths, and a represented section of the digitized depths.






- Canaveral Barge Canal update used a reference on the NOAA navigational chart to establish both a width and depth for the center of the canal. This depth was adjusted to NAVD88. The images below include an excerpt from the NOAA navigational chart and resulting DEM update for the canal.




- Interior DEM channel updates were based upon channel invert elevations and geometry. This data was supplemented with Morgan & Eklund cross section survey and invert data from the SWAMP database, in areas that included survey without existing modeled channel.
 - The majority of the channel segments in the model were simulated as trapezoidal. For these segments, the bottom width specified in the model was digitized and sloped based upon channel inverts and surveyed segments. The



image below shows the digitized lines (blue lines), the cross section survey (black triangles), and resulting terrain update piece. For channels that used irregular cross sections, the cross section data was evaluated and breaklines drawn consistent with the portion of the cross section below the water surface.



- In portions of the DEM update extent with only cross sectional survey, the survey was supplemented with invert data from the SWAMP database. The only area this was relevant was the segment of Hall Road west of Courtenay Parkway. It is of note that the SWAMP culvert inverts were consistent with the Morgan & Eklund survey. The image below shows the SWAMP culvert lines in purple and resulting DEM update in brown.





- Interior DEM ponding areas updated based upon the DEM extent of open water and aerial imagery to estimate the extent and depth of water. For the majority of areas a depth of -3.0 feet NAVD88 was used to approximate the open water portion. This depth is consistent with canals and provides sufficient connection for the groundwater model to interact with the surface water model. The interconnected lakes west of the Pine Island Stormwater Facility a depth of -5.0 feet was used based upon channel inverts in the model imagery. The resulting depth DEM was then used to "push down" the DEM an elevation of zero at the edge down to the approximated depths in the middle. The figure below shows a portion of the DEM update extent and resulting update.



4. Generate a DEM update piece and integrate the updated portion into the DEM.
 - Generation of an updated DEM piece includes generating a TIN from update pieces noted above then converting the TIN to a raster with the same raster cell size. The image below shows the TIN creation features and the corresponding height source for each element.

Input Features	Height Field	Type
NOAA_nauticalDepths	ElevNAVD88	Mass_Points
CanalLines2D	ElevNAVD88	Hard_Line
TieInLine3D	SHAPE.Z	Hard_Line
UpdateExtent	<None>	Soft_Clip

- The updated DEM piece is then Mosaiced back into the original DEM to create the hydrocorrected DEM for areas outside of ERPs. The resulting DEM is shown in the image below.
- It was noted that some areas, particularly in the NASA updated area on the East side of the watershed, the elevations resulting methodology specified above revealed isolated areas where the existing DEM was lower then the draft version of the hydrocorrected DEM, due to a dip in a shallow swale between the upstream and downstream ends of the modeled channel. In these cases the lower of the draft hydrocorrected DEM and the original DEM was used as the final hydrocorrected DEM.



Appendix B

ICPR4 Lookup and Reference Tables

Table B.1: Impervious Data Set

Land Use	% Impervious	% DCIA
1100: Residential, Low Density-Less than two dwelling units/acre	30%	15%
1180: Residential, Rural < or = 0.5 dwelling units/acre	12%	0%
1190: Low Density Under Construction	38%	20%
1200: Residential, Medium Density-Two-five dwelling units per acre	50%	30%
1300: Residential, High Density	65%	45%
1390: High Density Under Construction	72%	55%
1400: Commercial and Services	85%	70%
1480: Cemeteries	10%	0%
1550: Other Light Industrial	72%	55%
1560: Other Heavy Industrial	72%	55%
1700: Institutional (Educational, religious, health and military facilities)	65%	45%
1750: Governmental	65%	45%
1800: Recreational	2%	0%
1820: Golf Course	10%	0%
1840: Marinas and Fish Camps	25%	10%
1850: Parks and Zoos	10%	0%
1860: Community Recreational Facilities	10%	0%
1890: Other Recreational (Riding stables, go-cart tracks, skeet ranges, etc.)	10%	0%
1900: Open Land	2%	0%
2110: Improved Pasture	2%	0%
2130: Woodland Pasture	2%	0%
2200: Tree Crops	5%	0%
2210: Citrus groves	5%	0%
2240: Abandoned tree crops	5%	0%
2410: Tree nurseries	5%	0%
2430: Ornamentals	2%	0%
2510: Horse Farms	5%	0%
3100: Herbaceous Dry Prairie	0%	0%
3200: Shrub and Brushland	0%	0%
3300: Mixed Rangeland	0%	0%
4110: Pine flatwoods	0%	0%
4200: Upland Hardwood Forest	0%	0%
4210: Xeric oak	0%	0%
4280: Cabbage palm	0%	0%
4340: Hardwood Conifer Mixed	0%	0%
4370: Australian pine	0%	0%
5100: Streams and waterways	0%	0%
5200: Lakes	0%	0%
5201: Pond	0%	0%
5300: Reservoirs	0%	0%
5400: Bays and estuaries	0%	0%
5430: Enclosed saltwater ponds within a salt marsh	0%	0%

Land Use	% Impervious	% DCIA
6110: Bay swamps	0%	0%
6120: Mangrove swamp	0%	0%
6170: Mixed wetland hardwoods	0%	0%
6181: Cabbage palm hammock	0%	0%
6182: Cabbage palm savannah	0%	0%
6210: Cypress	0%	0%
6250: Hydric pine flatwoods	0%	0%
6300: Wetland Forested Mixed	0%	0%
6410: Freshwater marshes	0%	0%
6420: Saltwater marshes	0%	0%
6430: Wet prairies	0%	0%
6440: Emergent aquatic vegetation	0%	0%
6460: Mixed scrub-shrub wetland	0%	0%
6500: Non-vegetated Wetland	0%	0%
7400: Disturbed land	0%	0%
7430: Spoil areas	0%	0%
8120: Railroads	50%	30%
8140: Roads and Highways	65%	45%
8150: Port facilities	85%	70%
8180: Auto parking facilities - not directly related to other land uses	85%	70%
8200: Communications	0%	0%
8300: Utilities	72%	55%
8310: Electrical power facilities	72%	55%
8320: Electrical power transmission lines	0%	0%
8340: Sewage Treatment	50%	30%
8370: Surface Water Collection Basin	0%	0%

Table B.2: Initial Rainfall Excess parameters for Green-Ampt Infiltration Method (by MuKey)

Soil Zone	Kv Sat	Moisture Content Saturated	Moisture Content Residual	Moisture Content Initial	Moisture Content Field	Moisture Content Wilting	Pour Size Index	Bubble Pressure	Water Table Initial
1473327	70.0	0.389	0.011	0.079	0.079	0.021	0.586	1.641	5.413
1473441	26.0	0.382	0.013	0.081	0.081	0.026	0.595	1.768	0.000
1473288	26.0	0.382	0.013	0.081	0.081	0.026	0.595	1.768	1.509
1473305	9.3	0.416	0.047	0.170	0.170	0.093	0.397	2.549	4.003
1473290	70.0	0.392	0.006	0.044	0.044	0.012	0.588	1.671	6.594
1473299	3.4	0.391	0.043	0.166	0.166	0.086	0.334	2.595	0.000
1473349	26.0	0.397	0.009	0.049	0.049	0.017	0.595	1.613	4.987
1473302	15.1	0.436	0.038	0.149	0.149	0.076	0.363	3.413	0.262
1473356	11.4	0.415	0.045	0.166	0.166	0.090	0.416	2.049	4.003
1473340	21.4	0.384	0.019	0.101	0.101	0.038	0.574	1.715	2.986
1473314	20.4	0.391	0.017	0.090	0.090	0.033	0.578	1.658	4.003
1473341	58.3	0.407	0.016	0.087	0.087	0.031	0.555	1.566	0.000
1473308	8.4	0.438	0.070	0.214	0.214	0.140	0.333	2.567	0.984
1473322	22.2	0.386	0.015	0.085	0.085	0.029	0.581	1.905	2.001
1473338	26.1	0.392	0.008	0.052	0.052	0.015	0.579	1.691	3.510
1473306	16.0	0.416	0.020	0.096	0.096	0.040	0.435	1.379	0.492
3102932	48.1	0.375	0.009	0.071	0.071	0.017	0.603	1.853	4.167
1473292	70.0	0.404	0.013	0.068	0.068	0.026	0.586	1.544	0.000
1473289	26.1	0.430	0.032	0.141	0.141	0.063	0.531	1.400	0.262
1473296	70.0	0.475	0.017	0.089	0.089	0.034	0.567	1.067	3.740
1473324	17.1	0.428	0.015	0.087	0.087	0.029	0.569	1.354	0.000
1473376	26.1	0.430	0.032	0.141	0.141	0.063	0.531	1.400	0.262
1473351	17.7	0.689	0.063	0.358	0.358	0.195	0.273	0.554	0.000
1473344	14.4	0.703	0.018	0.352	0.352	0.183	0.145	1.865	0.000
1473294	13.8	0.436	0.043	0.168	0.168	0.085	0.334	1.496	1.017
1473348	26.1	0.515	0.046	0.267	0.267	0.099	0.527	0.861	0.492
1473310	13.6	0.411	0.030	0.127	0.127	0.060	0.410	1.543	0.000
1473337	26.0	0.374	0.007	0.067	0.067	0.014	0.609	1.864	4.003
1473309	13.6	0.418	0.054	0.182	0.182	0.108	0.406	1.358	0.984
1473293	26.0	0.390	0.015	0.090	0.090	0.029	0.576	1.616	4.003
1473295	70.0	0.475	0.017	0.089	0.089	0.034	0.567	1.067	1.936
1473331	70.0	0.443	0.005	0.027	0.027	0.009	0.575	1.247	6.594
1473329	70.0	0.384	0.005	0.056	0.056	0.009	0.603	1.752	6.594
1473354	17.1	0.428	0.015	0.087	0.087	0.029	0.569	1.354	1.017
1473307	16.0	0.416	0.020	0.096	0.096	0.040	0.435	1.379	0.000
1473346	26.1	0.451	0.018	0.091	0.091	0.035	0.514	1.201	2.264
1473333	13.5	0.398	0.027	0.130	0.130	0.053	0.486	2.324	4.003
1473336	50.9	0.414	0.006	0.046	0.046	0.012	0.586	1.459	2.756
1473332	17.5	0.428	0.031	0.132	0.132	0.062	0.382	1.503	1.017
1473291	70.0	0.392	0.006	0.044	0.044	0.012	0.588	1.671	6.594
1473342	70.0	0.408	0.005	0.057	0.057	0.010	0.589	1.508	6.594
1473325	17.1	0.428	0.015	0.087	0.087	0.029	0.569	1.354	1.017
1473345	26.1	0.449	0.006	0.040	0.040	0.011	0.554	1.213	6.594
1473377	26.0	0.382	0.013	0.081	0.081	0.026	0.595	1.768	0.000

Table B.3: Manning's Roughness Coefficient Data Set

Land Use / Roughness Zone	Shallow Manning's N	Deep Manning's N	Depth Range
1009: Mobile home units any density	0.12	0.06	1.5
1100: Residential, low density - less than 2 dwelling units/acre	0.12	0.06	1.5
1110: Low density residential (.2-2 DU/AC)	0.12	0.06	1.5
1120: Low density residential mobile	0.12	0.06	1.5
1130: Low density residential mixed	0.12	0.06	1.5
1140: Ranchettes fixed (>5 AC/DU)	0.12	0.06	1.5
1150: Ranchettes mobile	0.12	0.06	1.5
1160: Ranchettes mixed	0.12	0.06	1.5
1180: Rural residential	0.12	0.06	1.5
1190: Low density under construction	0.12	0.06	1.5
1200: Residential, medium density - 2-5 dwelling units/acre	0.12	0.06	1.5
1210: Medium density residential (2-5 DU/AC)	0.12	0.06	1.5
1220: Medium density residential mobile	0.12	0.06	1.5
1230: Medium density residential mixed	0.12	0.06	1.5
1280: Medium density residential	0.12	0.06	1.5
1290: Medium density under construction	0.12	0.06	1.5
1300: Residential, high density - 6 or more dwelling units/acre	0.12	0.06	1.5
1310: High density residential (>6 DU/AC)	0.12	0.06	1.5
1320: High density residential mobile	0.12	0.06	1.5
1330: Multiple DU low rise (<= 2 stories)	0.12	0.06	1.5
1340: Multiple DU high rise (>= 3 stories)	0.12	0.06	1.5
1350: High density residential mixed	0.12	0.06	1.5
1390: High density under construction	0.12	0.06	1.5
1400: Commercial and services	0.12	0.06	1.5
1410: Retail sales and services	0.12	0.06	1.5
1411: Shopping center	0.12	0.06	1.5
1420: Wholesale sales and services	0.12	0.06	1.5
1423: Junk yard	0.12	0.06	1.5
1424: Farmers market	0.12	0.06	1.5
1430: Professional services	0.12	0.06	1.5
1440: Cultural and entertainment	0.12	0.06	1.5
1443: Open air theater	0.12	0.06	1.5
1450: Tourist services	0.12	0.06	1.5
1452: Motel	0.12	0.06	1.5
1453: Travel trailer park	0.12	0.06	1.5
1454: Campground	0.12	0.06	1.5
1460: Oil & gas storage (except areas assoc. with industrial)	0.12	0.06	1.5
1470: Mixed commercial and services	0.12	0.06	1.5
1480: Cemeteries	0.12	0.06	1.5
1490: Commercial & services under construction	0.12	0.06	1.5
1500: Industrial	0.12	0.06	1.5
1510: Food processing	0.12	0.06	1.5
1513: Seafood processing	0.12	0.06	1.5
1514: Meat packing facility	0.12	0.06	1.5
1515: Poultry and/or egg processing	0.12	0.06	1.5
1516: Grain and legume processing	0.12	0.06	1.5
1520: Timber processing	0.12	0.06	1.5
1521: Sawmill	0.12	0.06	1.5
1522: Plywood and veneer mill	0.12	0.06	1.5

Land Use / Roughness Zone	Shallow Manning's N	Deep Manning's N	Depth Range
1523: Pulp and paper mills	0.12	0.06	1.5
1526: Log home prefabrication	0.12	0.06	1.5
1527: Woodyard	0.12	0.06	1.5
1530: Mineral processing	0.12	0.06	1.5
1532: Phosphate processing	0.12	0.06	1.5
1533: Limerock processing	0.12	0.06	1.5
1535: Heavy minerals processing	0.12	0.06	1.5
1540: Oil & gas processing	0.12	0.06	1.5
1544: Liquified gases	0.12	0.06	1.5
1545: Asphalt plant	0.12	0.06	1.5
1550: Other light industrial	0.12	0.06	1.5
1551: Boat building and repair	0.12	0.06	1.5
1552: Electronics	0.12	0.06	1.5
1554: Aircraft building and repair	0.12	0.06	1.5
1555: Container manufacturer	0.12	0.06	1.5
1556: Mobile home manufacturer	0.12	0.06	1.5
1560: Other heavy industrial	0.12	0.06	1.5
1561: Ship building & repair	0.12	0.06	1.5
1562: Pre-stressed concrete plants (includes 1564)	0.12	0.06	1.5
1563: Metal fabrication plants	0.12	0.06	1.5
1564: Cement plant	0.12	0.06	1.5
1565: Plastic pipe plant	0.12	0.06	1.5
1570: Chemical processing	0.12	0.06	1.5
1580: Industrial	0.12	0.06	1.5
1590: Industrial under construction	0.12	0.06	1.5
1600: Extractive	0.12	0.06	1.5
1610: Strip mines	0.12	0.06	1.5
1611: Clays	0.12	0.06	1.5
1612: Peat	0.12	0.06	1.5
1613: Heavy metals	0.12	0.06	1.5
1614: Phosphate mine	0.12	0.06	1.5
1620: Sand & gravel pits (must be active)	0.12	0.06	1.5
1630: Rock quarries	0.12	0.06	1.5
1631: Limerock quarry	0.12	0.06	1.5
1632: Limerock or dolomite	0.12	0.06	1.5
1633: Phosphates	0.12	0.06	1.5
1634: Heavy minerals	0.12	0.06	1.5
1640: Oil and gas fields	0.12	0.06	1.5
1650: Reclaimed lands	0.12	0.06	1.5
1660: Holding ponds	0.12	0.06	1.5
1670: Abandoned mining lands	0.12	0.06	1.5
1700: Institutional	0.12	0.06	1.5
1710: Educational facility	0.12	0.06	1.5
1720: Religious site	0.12	0.06	1.5
1730: Military	0.12	0.06	1.5
1736: National Guard installation	0.12	0.06	1.5
1740: Medical and health care	0.12	0.06	1.5
1741: Hospital	0.12	0.06	1.5
1742: Nursing home	0.12	0.06	1.5
1750: Governmental - for Kennedy Space Center only	0.12	0.06	1.5

Land Use / Roughness Zone	Shallow Manning's N	Deep Manning's N	Depth Range
1756: Maintenance yard	0.12	0.06	1.5
1760: Correctional facilities	0.12	0.06	1.5
1761: State prison	0.12	0.06	1.5
1765: Municipal prison	0.12	0.06	1.5
1770: Other institutional facility	0.12	0.06	1.5
1780: Commercial child care	0.12	0.06	1.5
1790: Institutional under construction	0.12	0.06	1.5
1800: Recreational	0.12	0.06	1.5
1810: Swimming beach	0.12	0.06	1.5
1820: Golf courses	0.12	0.06	1.5
1830: Race tracks	0.12	0.06	1.5
1831: Automobile racing track	0.12	0.06	1.5
1832: Horse racing track	0.12	0.06	1.5
1833: Dog racing track	0.12	0.06	1.5
1840: Marinas & fish camps	0.12	0.06	1.5
1850: Parks and zoos	0.12	0.06	1.5
1851: City park	0.12	0.06	1.5
1852: Zoo	0.12	0.06	1.5
1860: Community recreational facilities	0.12	0.06	1.5
1870: Stadiums - facilities not associated w/ high schools, colleges, universities	0.12	0.06	1.5
1880: Historical sites	0.12	0.06	1.5
1890: Under construction or other recreational	0.12	0.06	1.5
1900: Open land	0.12	0.06	1.5
1910: Undeveloped urban land	0.12	0.06	1.5
1920: Inactive development land (with streets)	0.12	0.06	1.5
1923: Inactive development land nonforested	0.12	0.06	1.5
1924: Inactive development land forested	0.12	0.06	1.5
1930: Urban land in transition, no indicators of intended activity	0.12	0.06	1.5
1940: Other open land	0.12	0.06	1.5
2100: Pasture	0.12	0.06	1.5
2110: Improved pastures (monocult, planted forage crops)	0.12	0.06	1.5
2111: Pasture	0.12	0.06	1.5
2120: Unimproved pastures	0.12	0.06	1.5
2130: Woodland pastures	0.12	0.06	1.5
2140: Row crops	0.12	0.06	1.5
2143: Potatoes and cabbage	0.12	0.06	1.5
2150: Field crops	0.12	0.06	1.5
2153: Hay fields	0.12	0.06	1.5
2156: Sugar cane	0.12	0.06	1.5
2160: Mixed crop	0.12	0.06	1.5
2200: Tree crops	0.12	0.06	1.5
2210: Citrus groves	0.12	0.06	1.5
2220: Fruit orchard	0.12	0.06	1.5
2221: Peaches	0.12	0.06	1.5
2224: Blueberries	0.12	0.06	1.5
2230: Other groves	0.12	0.06	1.5
2231: Pecans	0.12	0.06	1.5
2240: Abandoned tree crops	0.12	0.06	1.5
2300: Feeding operations	0.12	0.06	1.5
2310: Cattle feeding operations	0.12	0.06	1.5

Land Use / Roughness Zone	Shallow Manning's N	Deep Manning's N	Depth Range
2320: Poultry feeding operations	0.12	0.06	1.5
2330: Swine feeding operations	0.12	0.06	1.5
2400: Nurseries and vineyards	0.12	0.06	1.5
2410: Tree nurseries	0.12	0.06	1.5
2420: Sod farms	0.12	0.06	1.5
2430: Ornamentals	0.12	0.06	1.5
2431: Shade ferns	0.12	0.06	1.5
2432: Hammock ferns	0.12	0.06	1.5
2440: Vineyards	0.12	0.06	1.5
2450: Floriculture	0.12	0.06	1.5
2460: Timber nursery	0.12	0.06	1.5
2500: Specialty farms	0.12	0.06	1.5
2510: Horse farms	0.12	0.06	1.5
2520: Dairies	0.12	0.06	1.5
2530: Kennels	0.12	0.06	1.5
2540: Aquaculture	0.12	0.06	1.5
2550: Tropical fish farms	0.12	0.06	1.5
2590: Other specialty farm	0.12	0.06	1.5
2600: Other open land, rural	0.12	0.06	1.5
2610: Fallow cropland	0.12	0.06	1.5
2620: Old field	0.12	0.06	1.5
3100: Herbaceous upland nonforested	0.3	0.15	3
3200: Shrub and brushland	0.3	0.15	3
3210: Palmetto prairie	0.3	0.15	3
3220: Coastal scrub	0.3	0.15	3
3290: Other shrubs and brush	0.3	0.15	3
3300: Mixed upland nonforested	0.3	0.15	3
3430: Mixed upland	0.3	0.15	3
3460: Mixed upland	0.3	0.15	3
4100: Upland coniferous forests	0.3	0.15	3
4110: Pine flatwoods or mesic flatwoods	0.3	0.15	3
4119: Pine flatwoods - melaleuca infested	0.3	0.15	3
4120: Longleaf pine - xeric oak or longleaf sandhill	0.3	0.15	3
4130: Sand pine or sand pine scrub	0.3	0.15	3
4140: Pine - mesic oak	0.3	0.15	3
4190: Hunting plantation woodlands	0.3	0.15	3
4200: Upland hardwood forests	0.3	0.15	3
4210: Xeric oak or oak sandhill	0.3	0.15	3
4220: Brazilian pepper	0.3	0.15	3
4230: Oak - pine - hickory	0.3	0.15	3
4240: Melaleuca	0.3	0.15	3
4250: Temperate hardwood	0.3	0.15	3
4260: Tropical hardwood	0.3	0.15	3
4270: Live oak	0.3	0.15	3
4271: Oak - cabbage palm forest	0.3	0.15	3
4280: Cabbage palm	0.3	0.15	3
4290: Wax myrtle - willow	0.3	0.15	3
4300: Upland mixed forest	0.3	0.15	3
4310: Beech - magnolia	0.3	0.15	3
4320: Sand live oak or oak scrub	0.3	0.15	3

Land Use / Roughness Zone	Shallow Manning's N	Deep Manning's N	Depth Range
4330: Western Everglades hardwoods	0.3	0.15	3
4340: Upland mixed coniferous/hardwood	0.3	0.15	3
4350: Dead trees	0.3	0.15	3
4360: Trees	0.3	0.15	3
4370: Australian pine	0.3	0.15	3
4380: Mixed hardwoods	0.3	0.15	3
4390: Maritime hammock or other hardwoods	0.3	0.15	3
4400: Tree plantations	0.3	0.15	3
4410: Pine plantations	0.3	0.15	3
4420: Hardwood plantations	0.3	0.15	3
4430: Forest regeneration	0.3	0.15	3
4440: Experimental tree plots	0.3	0.15	3
4450: Seed plantations	0.3	0.15	3
4610: Upland	0.3	0.15	3
4630: Upland	0.3	0.15	3
5000: Water	0.06	0.06	1.5
5100: Streams and waterways	0.06	0.06	1.5
5110: Natural river, stream, waterway	0.06	0.06	1.5
5120: Channelized waterways	0.06	0.06	1.5
5200: Lakes	0.06	0.06	1.5
5210: Lakes larger than 500 acres (202 hectares)	0.06	0.06	1.5
5220: Lakes larger than 100 acres (40 hectares) but less than 500 acres	0.06	0.06	1.5
5230: Lakes larger than 10 acres (4 hectares) but less than 100 acres	0.06	0.06	1.5
5240: Lakes less than 10 acres (4 hectares) which are dominant features	0.06	0.06	1.5
5250: Open water within a freshwater marsh / Marshy Lakes	0.06	0.06	1.5
5300: Reservoirs - pits, retention ponds, dams	0.06	0.06	1.5
5310: Reservoirs larger than 500 acres (202 hectares)	0.06	0.06	1.5
5320: Reservoirs larger than 100 acres (40 hectares) but less than 500 ac.	0.06	0.06	1.5
5330: Reservoirs larger than 10 acres (4 hectares) but less than 100 acres	0.06	0.06	1.5
5340: Reservoirs less than 10 acres (4 hectares) which are dominant features	0.06	0.06	1.5
5400: Bays and estuaries	0.06	0.06	1.5
5410: Embayments opening directly to the gulf or ocean	0.06	0.06	1.5
5420: Embayments not opening directly to the gulf or ocean	0.06	0.06	1.5
5430: Enclosed saltwater ponds within a salt marsh	0.06	0.06	1.5
5500: Major springs	0.06	0.06	1.5
5600: Slough waters	0.06	0.06	1.5
5700: Ocean and gulf	0.06	0.06	1.5
5710: Atlantic Ocean	0.06	0.06	1.5
5720: Gulf of Mexico	0.06	0.06	1.5
6000: Wetlands	0.6	0.4	3
6100: Wetland hardwood forests	0.6	0.4	3
6110: Bay swamp (if distinct)	0.6	0.4	3
6111: Bayhead	0.6	0.4	3
6120: Mangrove swamps	0.6	0.4	3
6130: Gum swamps	0.6	0.4	3
6140: Titi swamps	0.6	0.4	3
6150: River/lake swamp (bottomland, may include cypress)	0.6	0.4	3
6160: Inland ponds and sloughs	0.6	0.4	3
6170: Mixed wetland hardwoods	0.6	0.4	3
6171: Mixed wetland hardwoods - willows	0.6	0.4	3

Land Use / Roughness Zone	Shallow Manning's N	Deep Manning's N	Depth Range
6172: Mixed wetland hardwoods - mixed shrubs	0.6	0.4	3
6180: Cabbage palm savannah	0.6	0.4	3
6181: Cabbage palm hammock	0.6	0.4	3
6182: Cabbage palm savannah	0.6	0.4	3
6191: Wet melaleuca	0.6	0.4	3
6200: Wetland coniferous forests	0.6	0.4	3
6210: Cypress	0.6	0.4	3
6215: Cypress - domes/heads	0.6	0.4	3
6216: Cypress - mixed hardwoods	0.6	0.4	3
6218: Cypress - melaleuca infested	0.6	0.4	3
6219: Cypress - with wet prairies	0.6	0.4	3
6220: Pond pine/wet flatwoods	0.6	0.4	3
6230: Southern red cedar/Atlantic white cedar	0.6	0.4	3
6240: Cypress - pine - cabbage palm	0.6	0.4	3
6250: Hydric pine flatwoods	0.6	0.4	3
6260: Wetlands savannah	0.6	0.4	3
6300: Wetland forested mixed	0.6	0.4	3
6310: Hydric hammock	0.6	0.4	3
6320: Tidal swamp	0.6	0.4	3
6400: Vegetated non-forested wetlands	0.6	0.4	3
6410: Freshwater marshes	0.6	0.4	3
6411: Sawgrass marshes	0.6	0.4	3
6412: Cattail marshes	0.6	0.4	3
6420: Saltwater marshes	0.6	0.4	3
6430: Wet prairies	0.6	0.4	3
6439: Wet prairies - with pine	0.6	0.4	3
6440: Emergent aquatic vegetation	0.6	0.4	3
6450: Submergent aquatic vegetation	0.6	0.4	3
6451: Hydrilla	0.6	0.4	3
6460: Mixed scrub-shrub wetland	0.6	0.4	3
6464: Wetland	0.6	0.4	3
6500: Non-vegetated wetland	0.6	0.4	3
6510: Tidal flats	0.6	0.4	3
6520: Intertidal areas	0.6	0.4	3
6530: Intermittent ponds	0.6	0.4	3
6540: Oyster bars	0.6	0.4	3
6600: Cut over wetlands	0.6	0.4	3
6900: Wetland scrub	0.6	0.4	3
7100: Beaches other than swimming beaches	0.12	0.06	1.5
7200: Sand other than beaches	0.12	0.06	1.5
7300: Exposed rock	0.12	0.06	1.5
7400: Disturbed land	0.12	0.06	1.5
7410: Rural land in transition without positive indicators of intended activity	0.12	0.06	1.5
7420: Borrow areas	0.12	0.06	1.5
7430: Spoil areas	0.12	0.06	1.5
7440: Levees/fill areas	0.12	0.06	1.5
7450: Burned areas	0.12	0.06	1.5
7470: Dikes and levees	0.12	0.06	1.5
7500: Riverine sandbars	0.12	0.06	1.5
8100: Transportation	0.12	0.06	1.5

Land Use / Roughness Zone	Shallow Manning's N	Deep Manning's N	Depth Range
8110: Airports	0.12	0.06	1.5
8111: Commercial airport	0.12	0.06	1.5
8112: General aviation	0.12	0.06	1.5
8113: Private airports	0.12	0.06	1.5
8115: Grass airports	0.12	0.06	1.5
8120: Railroads	0.12	0.06	1.5
8130: Bus and truck terminals	0.12	0.06	1.5
8140: Roads and highways (divided 4-lanes with medians)	0.12	0.06	1.5
8141: Limited access highway (interstate)	0.12	0.06	1.5
8142: Divided highway (federal-state)	0.12	0.06	1.5
8143: Two lane highway	0.12	0.06	1.5
8147: Transportation corridor	0.12	0.06	1.5
8150: Port facilities	0.12	0.06	1.5
8152: Piers	0.12	0.06	1.5
8153: Cargo terminals	0.12	0.06	1.5
8155: Repair facilities	0.12	0.06	1.5
8156: Shipyards	0.12	0.06	1.5
8160: Locks and dams	0.12	0.06	1.5
8170: Oil, water, or gas transmission lines	0.12	0.06	1.5
8180: Auto parking facilities	0.12	0.06	1.5
8190: Transportation facilities under construction	0.12	0.06	1.5
8191: Highways under construction	0.12	0.06	1.5
8192: Railroads under construction	0.12	0.06	1.5
8193: Airports under construction	0.12	0.06	1.5
8194: Port facilities under construction	0.12	0.06	1.5
8195: Pipelines under construction	0.12	0.06	1.5
8200: Communications	0.12	0.06	1.5
8210: Transmission towers	0.12	0.06	1.5
8220: Communication facilities	0.12	0.06	1.5
8290: Communication facilities under construction	0.12	0.06	1.5
8300: Utilities	0.12	0.06	1.5
8310: Electrical power facilities	0.12	0.06	1.5
8311: Coal-fired electrical power generating plant	0.12	0.06	1.5
8315: Electrical power substation	0.12	0.06	1.5
8320: Electrical power transmission lines	0.12	0.06	1.5
8330: Water supply plants	0.12	0.06	1.5
8340: Wastewater treatment	0.12	0.06	1.5
8350: Solid waste disposal	0.12	0.06	1.5
8360: Treatment ponds	0.12	0.06	1.5
8370: Surface water collection basins	0.12	0.06	1.5
8390: Utilities under construction	0.12	0.06	1.5
8410: Utilities	0.12	0.06	1.5
9110: Sea grass	0.12	0.06	1.5
9999: Missing	0.12	0.06	1.5
0: Unknown	0.12	0.06	1.5

Appendix C

Development of Input Rainfall and Stage Conditions Data for North Merritt Island

prepared by Applied Ecology, Inc., March 2021

DEVELOPMENT OF INPUT RAINFALL AND STAGE CONDITION DATA FOR NORTH MERRITT ISLAND

FINAL TECHNICAL REPORT

5/19/2021

Prepared For:



Prepared By:



Executive Summary

Applied Ecology's (AEI) objective for this project was to create rainfall and surface water stage estimated input datasets for use in the Interconnected Channel and Pond Routing Model (ICPR4) for North Merritt Island, FL (NMI). These input datasets provide year-long representations of either existing conditions (based on 2017 historical record) and future conditions (based on year 2040/2041).

The data produced by AEI provided the client the ability to run up to five long-term (annual) hydrologic simulation. The first scenario would be representative of 2017 conditions, a year that represented significant storm surge conditions due to Hurricane Irma. The other four scenarios correspond to synthetic estimated rainfall and water level conditions, in an attempt to represent all the combinations of El Niño/La Niña years and average or high storm conditions. The data provided by AEI can be incorporated into the North Merritt Island ICPR custom modeling and provide the following five scenarios:

Scenario Timeframe	Rainfall Condition	Storm Surge Condition
Historic/present (2017)	Measured 2017 conditions	Measured/estimated based on 2017 data
Future (20 years from current condition:2040)	El Niño conditions (wet year)	Intermediate high sea level rise scenario with average storm surge conditions
Future (20 years from current condition: 2040)	El Niño conditions (wet year)	Intermediate high sea level rise scenario with 13.1 ft (4 m) storm surge conditions (high storm surge)
Future (20 years from current condition: 2041)	La Niña conditions (dry year)	Intermediate high sea level rise scenario with average storm surge conditions
Future (20 years from current condition: 2041)	La Niña conditions (dry Year)	Intermediate high sea level rise scenario with 13.1 ft (4 m) storm surge conditions (high storm surge)

This project utilized the National Weather Service (NWS) Next Generation Radar (NEXRAD) to create bias-corrected 2017 rainfall estimates over NMI and then applied the Coupled Model Intercomparison Project Version 5 (CMIP5) climate projections to generate wet (El Niño) and dry (La Niña) rainfall estimates for 2040. The 2017 bias-corrected rainfall estimate was created using the NEXRAD Level 3 1-Hour Digital Accumulation Array (DAA) product from the NWS Melbourne, FL station (KMLB). A python script was written that created a 5-minute, 0.15 km² pixel rainfall time series and then applied a bias correction based on a SJRWMD 1-Hour radar rainfall product. The resulting product was validated against the SJRWMD Ransom Road rain gauge station, with a R² of 0.72 between the hourly bias-corrected rainfall estimates and gauge readings for all of 2017. A pattern of underestimation was identified with an annual rainfall of 63.4 inches (1,610 mm) measured at the rain gauge with the bias-corrected rainfall estimating 51.2 inches (1,300 mm).

The 2040 wet and dry rainfall projections were created by applying a monthly percent change based on the Multi-Model Mean (MMM) of the CMIP5 Local Constructed Analogs (LOCA) downscaled models to

the 2017 bias-corrected rainfall estimate. The 2017 MMM was chosen as the baseline and the projected annual increase of 3% to 2040 was used as the wet year, and 6% decrease to 2041 used for the dry year.

The North Indian River Lagoon (NIRL) and Banana River (BR) bound the NMI area to the west and east, respectively. The 2017 stage estimates for these two water bodies was created from the St Johns River Water Management District's (SJRWMD) Continuous Monitoring (CM) stations. A Coastal Modeling System (CMS-Flow) model was developed for 2017 and then for 2040 with a sea level rise offset identified from the National Oceanographic and Atmospheric Administration (NOAA) 2017 intermediate-high projections. The 2017 NIRL and BR surface water stage estimations were created from the SJRWMD CM depth of sensor readings and the CMS-Flow model. The CM depth of sensor readings were transformed into stage estimations through a demeaned transformation with the NOAA Trident Pier Atlantic Ocean stage station. The CMS-Flow model utilized three ocean boundaries at Ponce de Leon Inlet, Wabasso Bridge, and Sebastian Inlet, along with wind and freshwater inputs.

Both the CM and CMS-Flow stage estimations averaged -0.79 ft (-0.24 m) NAVD88 for both NIRL and BR from January to August, captured the storm surge from Hurricane Irma, and detected the late October Gulf Stream high sea levels. The CM estimated stages between NIRL and BR for several months ranged between 0.82 – 2.46 ft (0.25 – 0.75 m), compared to the 1-3 day long 0.32 in (10 cm) variation in the CMS-Flow model. The CMS-Flow model was validated against the United States Geological Survey (USGS) Haulover Canal station with a R^2 value of 0.84 with a 0.32 in (10 cm) underestimation of stage throughout the year.

The methods outlined in this report made use of the limited data available in the NMI area to generate the rainfall and surface water stage estimates for the ICPR4 model. The bias-corrected NEXRAD radar rainfall estimates underestimated both the annual rainfall and for intense rainfall such as Hurricane Irma, though a portion of this is due to the challenge of using radar rainfall estimates and the higher spatial resolution around a single validation location. The CM stage estimates of NIRL and BR are the only long-term measurements in those basins, however as they are indirect measurements and with potential errors from drift and sensor biofouling, they best represent short term variations in stage. The CMS-Flow model had good agreement with the Haulover Canal reference site and the underestimation is potentially due to the complex flows that pass through the canal which connects the NIRL to Mosquito Lagoon.

Contents

Executive Summary.....	1
Introduction	4
Rainfall	5
Surface Water Stage	5
Climate Modeling.....	6
Methods.....	7
Development of 2017 Historic Rainfall Conditions.....	7
Development of 2040 Rainfall Conditions	9
Development of 2017 Historic Surface Water Stage Conditions.....	12
Development CMS-Flow Surface Water Model	14
Grid Generation	14
Boundary Water Level and Discharge Time Series	14
Wind Time Series	16
Freshwater Time Series.....	17
Model Runs	17
Results & Discussion	18
2017 NEXRAD Rainfall Estimation.....	18
2040 Synthetic Simulation of Future Rainfall	22
2017 Stage Level Simulation	23
Continuous Monitoring Stations.....	23
Coastal Modeling System (CMS) Model.....	28
2040 Synthetic Simulation of Future Stage Level	33
Summary.....	36
References	37

Introduction

In 2019 Brevard County passed Ordinance 19-26 which requires future development projects on Merritt Island, FL to demonstrate that no adverse flooding impacts will occur as the result of new development. An Interconnected Channel and Pond Routing Model 4 (ICPR4) hydrological model was selected to be developed for the area to serve as a base model to evaluate potential flood control and natural system improvement projects and other physical changes to watershed. This model requires, as critical input datasets, rainfall and surface water stage time-series which, in turn, rely on the availability of sufficiently spatially and temporally dense data points.

This project focused on the North Merritt Island (NMI) watershed of between the NASA Parkway and Highway US-A1A (Figure 1). The NMI area is characterized by two north-south ridges with the Sykes Creek between draining into the east-west running Barge Canal. It is bordered by the Indian River Lagoon to the west and the Banana River to the east. There are clusters of agricultural and residential land cover on the ridges with scrub and wetland between, intercut with drainage ditches and canals.



Figure 1 – Location of the North Merritt Island study area

Rainfall

The creation of a rainfall surface can be accomplished through spatial interpolation of measurements from rain gauges or estimations from radar returns (Bredesen & Brown, 2018). Generation of areal rainfall estimates historically relied on rain gauges as accurate point measures and applied statistical methods to interpolate within a gauge network. This requires a dense network of gauges across a region to capture the spatial variability of storms and account for local factors.

Rainfall in Florida is characterized as highly seasonal with intense storms with small footprints during the wet season (Skinner *et al.*, 2009; Mahjabin & Abdul-Aziz, 2020). The wet season spans from June to October, when 2/3rds of the annual rainfall occurs. The storms during the wet season can vary from regionwide fronts to storms small enough to pass between rain gauges, complicating the accurate representation of local rainfall patterns when using rain gauges.

The Next Generation Radar (NEXRAD) network of the National Weather Service (NWS) was chosen to provide the rainfall surface for this study as radar rainfall estimates can provide a spatially contiguous rainfall surface. Radar rainfall estimates are based on the Z-R relationship which is the principal that more intense rainfall results in a stronger radar return (NOAA, 2017). Radar rainfall estimates can also incorporate available rain gauge data to determine a Gauge-Radar (GR) ratio, which is the ratio of rainfall measured at a rain gauge over the estimated radar rainfall over the rain gauge. This bias correction is required to account for how NEXRAD estimates rainfall from the cloud to the ground along with other errors and limitations. An accurate estimation of rainfall can be created with the GR bias correction, however error can still occur with extremely heavy or light rainfall (Bredesen & Brown, 2018; NOAA, 2017; Skinner *et al.*, 2009).

Surface Water Stage

Within the Indian River Lagoon (IRL) variations in surface water stages are driven by wind, rainfall runoff, and ocean tides. Of these forces wind has the strongest influence on the variation of surface water stage with the direction of the wind also having a significant impact. North and south winds can result in the stage of some segments of the IRL varying up to 40-50 cm (Weaver *et al.*, 2016). However, there is limited continuous surface water stage measurements in the IRL, with the USGS Haulover Canal and Wabasso stations being the only long-term stations in the IRL. The St Johns River Water Management District (SJRWMD) maintains a network of continuous monitoring stations which this study used to provide an indirect estimation of water surface stage through a depth measurement.

The Coastal Modeling System (CMS) was also selected to model water stage changes in this study, which was developed by the U.S. Army Engineer Research and Development Center (ERDC) and Coastal and Hydraulics Laboratory (CHL). CMS is a coupled group of numerical models for calculating waves, circulation, sediment transport, constituent transport, and morphological change. The water stage module, CMS-Flow, is a two dimensional (2-D), finite-volume model that solves the mass conservation and shallow-water momentum equations of water motion. CMS-Flow can be forced by water surface stage (e.g., from tide), wind and river discharge at the model boundaries, and wave radiation stress and wind field over the model computational domain. A significant study for model verification and validation of the CMS is documented in Demirbilek and Rosati (2011), Lin *et al.* (2011), Sanchez (2011a) and Sanchez (2011b). Further documentation of the CMS, including processes and numerics, are documented in Wu (2010) and Buttolph (2006).

Climate Modeling

In recent years climate projection information and methods have become more available and applicable on the smaller scale to Florida (Infanti *et al.*, 2020). The Lawrence Livermore National Laboratory Program's Coupled Model Intercomparison Project Version 5 (CMIP5) is a collection of global models with varying assumptions and conditions that when considered together can account for the inherent uncertainty in projecting future climates. One assumption the CMIP5 includes and is of particular concern to Florida, is the impact of the El Niño-Southern Oscillation (ENSO), which El Niño events can drive wetter conditions and La Niña result drier conditions (Wang & Asefa, 2018). Through the Localized Constructed Analogs (LOCA) a downscaling process was applied to the global CMIP5 models which used local climate observations in the United States to improve both the spatial resolution and accuracy in projecting the full range of future conditions (Pierce *et al.*, 2014). The CMIP5 LOCA projected precipitation was used to determine the likely change in precipitation from 2017 to 2040/2041 for NMI.

Similarly, future sea level rise (SLR) has been modeled and projected globally by the Intergovernmental Panel on Climate Change (IPCC) in 2014 and then by NOAA in 2017 with a focus on incorporating regional effects relevant to the United States. The South Florida Climate Compact evaluated these two sets of projected SLR to qualify their use in planning and provide guidance on how to select a projected sea level for a given project (Compact, 2019). These models account for a portion of uncertainty based on global climatic models like thermal expansion of the ocean and specific events such as the melting of various glaciers. Of the available models, the NOAA Intermediate-High Curve was selected as it recommended for inundation and infrastructure planning.

Methods

This report summarizes the methods utilized to generate estimations of rainfall and surface water conditions for the year 2017 and then future climatic projections in 2040. The year 2017 was selected as a historical input to capture the impact of Hurricane Irma on NMI. The rainfall of 2017 was estimated by NEXRAD radar rainfall and surface water stage estimated by indirect measurements and CMS hydraulic modeling. Four scenarios were created from the 2040 projections, based on high and low annual rainfall along with average and extreme storm surge. The future CMIP5 LOCA climate projections were evaluated to identify likely future conditions during El Niño (Wet) and La Niña (Dry) periods. Then CMS models were run with projected sea level rise and an additional extreme storm surge.

Development of 2017 Historic Rainfall Conditions

The creation of the simulated rainfall surface over the NMI area utilized radar rainfall estimates and limited rain gauge data for 2017. An inventory of existing rain gauges identified an insufficient number of stations in the region that collect hourly or better data. The National Weather Service (NWS) Next Generation Radar (NEXRAD) was chosen to provide rainfall estimates at 5-minute intervals. Also due to the lack of rain gauges in the NMI area to use for data correction, the SJRWMD processed hourly NEXRAD rainfall estimate was used as a stand-in for gauge readings to determine the bias correction.

To generate the 2017 radar rainfall of the NMI area, the nearest NEXRAD station (Melbourne KMLB 28°6'48"N 80°39'15"W) was selected. The daily rainfall archives for 2017 were downloaded from the NOAA National Centers for Environmental Information (NCEI) (<https://www.ncdc.noaa.gov/cdo-web/datasets/NEXRAD3/stations/NEXRAD:KMLB/detail>). The SJRWMD NEXRAD grid and the Ransom Road rain gauge data were acquired from the SJRWMD Bureau of Water Resource Information (<https://www.sjrwmd.com/data/hydrologic/>). The Kennedy Space Center (KSC) rain gauges were not used in this analysis due to systematic data gaps and the NOAA managed rain gauges were not used due to only being available at daily intervals.

The NEXRAD Level 3 product 1-Hour Digital Accumulation Array (DAA) was selected due to its higher spatial resolution. The DAA is available at a 0.13-nm x 1-degree grid, compared to the 1.1-nm x 1-degree grid of the One-Hour Accumulation (OHA) product. All available DAA rasters for 2017 were extracted as GeoTIFFs using the NOAA Weather and Climate Toolkit (WTC) and then resampled to a 380 m grid in ArcMap 10.8, which aligns as a 5x5 grid with the SJRWMD NEXRAD grid (Figure 2).

The DAA time series was recorded at KMLB in a variable time interval format, time steps could range from 3-5 minutes during a rain event. As each interval represented the accumulated rainfall for the last hour for a given grid cell, accumulated rainfall for a time step was determined by subtracting the current accumulation from the previous accumulation. A custom python script was created to standardize the time series and accumulated rainfall to a 5-minute interval.




Figure 2 – Location of the Ransom Road rain gauge in the North Merritt Island study area with the St Johns River Water Management District (SJRWMD) NEXRAD and National Weather Service NEXRAD grids overlain. The Kennedy Space Center (KSC) and NOAA rain gauges were evaluated and not used in the development of the rainfall surfaces due to formatting or data quality.

A second custom python script was created to summarize the 5-minute DAA radar rainfall pixels to an hourly average rainfall at the corresponding scale of the SJRWMD NEXRAD rainfall pixels. This script generated the Gauge-RADAR Ratio between the DAA and SJRWMD NEXRAD pixels, and then applied the hourly bias correction to the 5-minute DAA radar rainfall pixels. The output was formatted for use by the ICPR4 model as a CSV shown in Table 1. The bias-corrected NWS DAA NEXRAD radar rainfall estimates were then evaluated by their deviation from the Ransom Road rain gauge.

Table 1 - ICPR4 time series input format. The black, non-bolded text are the characters in the text file while the blue, bolded text describes what it represents.

A3 File Name (Grid reference)				
0 Data Type (Precipitation)				
5 Packet Time Increment (min)				
Year	Month	Day	Decimal Hour	Rainfall Amount (in)
2017	1	2	6.6667	0.012053
2017	1	2	6.75	0.013057
2017	1	2	6.8333	0.004269
2017	1	2	6.9167	0.003515
2017	1	2	7	0.003534

Development of 2040 Rainfall Conditions

Based on available literature, the CMIP5 Local Analogue (LOCA) downscaled models were selected to identify future climate projections for the NMI area (Bracken, 2016; Dessalegne *et al.*, 2016; Infanti *et al.*, 2020). A monthly percent change in precipitation was calculated between those years and 2017 and then applied to the NEXRAD radar rainfall estimates to generate projected rainfall.

The projected dry and wet precipitation conditions for NMI were generated through a monthly percent change determined from the Multi-Model Mean (MMM) of the CMIP5 LOCA models. The CMIP5 LOCAL rainfall projections were downloaded from the Lawrence Livermore National Laboratory Program's Downscaled CMIP3 and CMIP5 Climate and Hydrology Projections database (https://gdo-dcp.ucllnl.org/downscaled_cmip_projections/). The years 2040 and 2041 were chosen to represent a dry and wet season based on their relative variation from the 5 year mean in precipitation. These years were chosen as the MMM annual rainfall of 2040 was high (55.4 inches) and 2041 low (50.8 inches) relative to the 5-year average (53.8 inches).

To create the La Niña and El Niño projected rainfalls, monthly adjustments were calculated from the CMIP5 precipitation projections. These adjustments were determined by the percent change of monthly rainfall from the CMIP5 2017 for each of the 6 pixels that cover North Merritt Island (Figure 3). Each 2017 NWS NEXRAD ICPR grid cell was then apportioned to the CMIP5 grid. A custom python script was used to apply the corresponding percent adjustment for 2040 (Table 2) and 2041 (Table 3) to each of the previously generated ICPR 2017 precipitation files.




Figure 3 – Comparison of the CMIP5 grid cells with the NWS NEXRAD bias corrected grid cells.

Table 2 – Monthly percent adjustments calculated from the change between CMIP5 2017 and 2040 precipitation applied to the 2017 ICPR dataset to create a La Niña precipitation projection (drier conditions).

2040	Cell 1	Cell 2	Cell 3	Cell 4	Cell 5	Cell 6
Jan	66%	65%	65%	65%	64%	64%
Feb	94%	93%	94%	93%	92%	91%
Mar	110%	109%	109%	109%	111%	110%
Apr	78%	79%	79%	79%	79%	79%
May	78%	79%	79%	80%	80%	81%
Jun	94%	95%	95%	95%	95%	96%
Jul	87%	87%	87%	87%	87%	86%
Aug	98%	98%	98%	99%	99%	99%
Sep	92%	91%	91%	91%	90%	91%
Oct	99%	99%	99%	98%	98%	97%
Nov	127%	125%	123%	122%	119%	117%
Dec	137%	132%	132%	127%	125%	123%

Table 3 - Monthly percent adjustments calculated from the change between CMIP5 2017 and 2041 precipitation applied to the 2017 ICPR dataset to create a El Niño precipitation projection (wet conditions).

2041	Cell 1	Cell 2	Cell 3	Cell 4	Cell 5	Cell 6
Jan	87%	86%	86%	85%	83%	83%
Feb	88%	88%	90%	89%	91%	91%
Mar	114%	115%	116%	116%	119%	119%
Apr	86%	86%	87%	87%	87%	87%
May	90%	91%	92%	93%	94%	95%
Jun	134%	135%	135%	135%	135%	135%
Jul	104%	104%	105%	104%	103%	103%
Aug	101%	102%	102%	103%	103%	103%
Sep	98%	98%	99%	99%	100%	100%
Oct	99%	99%	99%	98%	99%	99%
Nov	105%	103%	104%	103%	103%	102%
Dec	125%	123%	123%	121%	121%	120%

Development of 2017 Historic Surface Water Stage Conditions

Within the Indian River Lagoon (IRL) there is limited surface water stage data, with no long-term stations present in the immediate area around NMI. The closest surface water stage data station is in the northernmost reach of IRL at the USGS Haulover Canal station in the North IRL, while NOAA has the Atlantic Ocean Trident Pier station east of Banana River. The SJRWMD Continuous Monitoring (CM) stations measure depth of sensor which was transformed into estimated stage using the Trident Pier time series.

To create an estimation of the surface water stage on the west and east sides of NMI, the SJRWMD CM station's depth of measurement was used (Figure 4). The North Indian River Lagoon estimated stage level is represented by the CM data collected at "Titusville Max Brewer Memorial Parkway (WQ)" (Station ID 33954622). The Banana River estimated stage level is represented by a composite time series of the CM "Merritt Island Causeway at SR 520 (WQ)" (Station ID 33964621) which was moved to "IRLB04 Banana River (WQ)" (Station ID 33844736) in April 2017. The CMs located at Cocoa and Melbourne were not used due to significant data gaps in 2017. Brevard County Natural Resources Management Department maintained a series of staff gauges within the NMI area but were only read daily in September and October 2017. A logging station was maintained by Florida Institute of Technology at Kars Park but was not available in NAVD88 and had data only for January and February 2017.

The SJRWMD CM stations utilize a YSI EXO2 multiparameter sonde with a vented strain gauge to determine depth of sensor. Strain gauge pressure transducers can have drift and calibration issues over their deployment. The CM sensors are deployed for three-to-five-week periods, after which maintenance is performed for calibration and removal of biofouling. The entire sensor system is removed and then replaced. The SJRWMD Bureau of Water Resource Information provided both depth of sensor readings and the maintenance periods (<https://www.sjrwmd.com/data/hydrologic/>). The depth of sensor value measured before and after maintenance activities was then evaluated for drift. An offset was applied to the data after each maintenance activity to account for variation in depth due to reinstallation.

Data gaps were identified for the CM stations and were replaced with USGS Haulover Canal stage levels obtained from the USGS Water Data service (https://waterdata.usgs.gov/usa/nwis/uv?site_no=02248380). The Haulover Canal data was first demeaned and then applied to the CM time series by a time weighted bias correction to account for drift.

The Banana River series is a composite of two stations along the SR 520 causeway. The series begins at "CM Merritt Island Causeway at SR 520 (WQ)" and was moved to "IRLB04 Banana River (WQ)" on 4/26/2017. Measurements between 4/19/2017 and 4/26/2017 at "CM Merritt Island Causeway at SR 520 (WQ)" was determined to be suspect when compared with trends at the other stations. The USGS Haulover Canal stage readings were first shifted to the Banana River stage of -0.018 m on 0:00 4/19/2017 and then over the next 192 hours shifted down by 0.139 m to -0.157 m at 23:00 4/26/2017.

The Indian River Lagoon station located near Titusville, FL had three data gaps between 4/10/2017 to 5/3/2017, 8/6/2017 to 8/8/2017, and 9/10/2017 to 10/11/2017. The first patch of USGS Haulover Canal stage readings were first shifted to the Titusville stage of -0.196 m at 19:00 4/19/2017 and did not need to be fitted. The second patch of USGS Haulover Canal stage readings were first shifted to the Titusville stage of -0.254 m at 01:00 8/6/2017 and then over the next 192 hours shifted down by 0.01 m to -0.270

m at 23:00 4/26/2017. The third patch of USGS Haulover Canal stage readings were first shifted to the Titusville stage of -0.212 m at 00:00 9/10/2017 and then over the next 742 hours shifted up by 0.166 m to 0.024 m at 12:00 4/26/2017.

The gap filled CM depth of sensor time series were then demeaned and shifted to estimated stage (NAVD88) using the NOAA Trident Pier dataset. The Trident Pier data were acquired from the NOAA Tides and Currents service (<https://tidesandcurrents.noaa.gov/stationhome.html?id=8721604>) and a 25-Hour low pass filter was applied to remove tidal signal.




Figure 4 – Locations of surface water measurement stations in the Indian River Lagoon listed by their managing entity. The USGS Haulover Canal and NOAA Trident Pier stations were used to adjust and correct the SJRWMD Titusville, Banana River, and Merritt Island Causeway stations. The Brevard County and Florida Institute of Technology (FIT) gauges were not used in the development of the surface water stage due to limited data availability.

Development CMS-Flow Surface Water Model

The CMS-Flow model was also utilized to generate stage estimates of North IRL (NIRL) and Banana River (BR) for 2017 and 2040. The CMS-Flow model utilized the closest ocean connections with monitoring stations at Ponce de Leon Inlet, Wabasso Bridge, and Sebastian Inlet as water level boundaries. The NOAA projection of 0.852 ft (0.259 m) of SLR for 2040 was chosen to inform the CMS-Flow model of future conditions around NMI and a second model was run with a potential extreme storm surge event of 13.1 ft (4 m).

Grid Generation

A CMS-Flow model grid was constructed covering the Mosquito Lagoon and the north compartment of the Indian River Lagoon and extending to the Sebastian Inlet area and ending at the Wabasso Bridge in north Indian River County (Figure 5). The CMS model grid resolution was set at 50 meters.

Boundary Water Level and Discharge Time Series

Water level boundary conditions for the model were set at the closest ocean connections at the north end of the model near Ponce de Leon Inlet (Volusia County) and at the south end of the model at the Wabasso Bridge (Indian River County) and Sebastian Inlet (Brevard County). The non-tidal portion of the record is also shown. At the three coastal ocean boundary locations, water level time series were established from a combination of predicted tides based on up to 34 tidal constituents along with measured lower frequency water level time series. Since sea levels outside of the tidal frequency can vary over a range of up to 3 feet in any given year, it was important for model water level boundary conditions to include all sea level components. The tidal component for model boundary water level time series was obtained from NOAA tidal prediction stations at New Smyrna, FL, Sebastian Inlet, and Wabasso FL. The non-tidal sea levels were acquired by filtering off the tidal signal from the National Oceanic and Atmospheric Administration (NOAA) Trident Pier water level gauge records. The Trident Pier records processes with a 25-hour low pass filter were then added to the predicted tides. Figure 6 shows the water level records applied at the north boundary of the model, including the storm surge from the passing of Hurricane Irma in 2017. Similarly, compiled water level records were applied to both Sebastian Inlet and the Wabasso Bridge model boundaries. The period of record for the model experiments was set to 2017 due to the completeness of the available data during this year to set appropriate model boundary conditions.




Figure 5. Configuration of the regional model grid. Water level boundary time series are shown at the New Smyrna Bridge (A), Sebastian Inlet (B) and the Wabasso Bridge (C).




Figure 6. Water level time series applied at the north boundary of the model. Data were derived from a combination on tidal predictions and measured non-tidal data.

Wind Time Series

CMS-Flow will assimilate wind data as multiple inputs over selected cells or as global input over the entire model domain. In this study, wind records from NOAA Station 8721604 located at Cape Canaveral were applied. Wind speed from the NOAA station is shown in Figure 7 and approaching wind directions with respect to true north are shown in Figure 8.




Figure 7. Wind speeds recorded at NOAA Station 8721604 Cape Canaveral, FL.




Figure 8. Wind direction recorded at NOAA Station 8721604 Cape Canaveral, FL.

Freshwater Time Series

Freshwater discharge time series were also applied as a boundary condition to the model. Records of major inflows were obtained from the United States Geological Survey (USGS) gauging stations maintained at the Eau Gallie River, Crane Creek, and Turkey Creek. In the Sebastian River, the gauged discharges from the S-157 structure and the Fellsmere Canal were combined. Gauges freshwater inflows in the north compartments of the IRL and the Banana are lacking. However, model outputs from the Spatial Watershed Iterative Loading Model or SWIL (Listopad, 2015; Zarillo & Listopad, 2018) were used to specify freshwater inflows flows for sub-basin surrounding the northern IRL and Banana River.

Model Runs

Three model runs were made starting with 2017 and then two more for conditions projected in 2040. The first run has a storm surge of about 1 meter in the coastal ocean water level boundary condition corresponding to the passage of Hurricane Irma over Florida in early September of 2017. The second model applied a projected sea level rise of 0.852 feet (0.259 meter) to the model boundary conditions according the intermediate-high projections from NOAA (Sweet *et al.*, 2017). Then the third model run had 13.1 ft (4 m) of storm surge applied in early September on top of the projected sea level rise.

Results & Discussion

2017 NEXRAD Rainfall Estimation

The bias corrected NWS NEXRAD rainfall estimates for 2017 were substantially improved over the non-bias corrected estimates (Table 4). The annual rainfall for the NEXRAD pixels in the Ransom Road area for unbiased was 25.9 inches, bias corrected was 51.2 inches, compared to the 63.4 inches recorded at the rain gauge. However, in comparison to the Ransom Road rain gauge and the SJRWMD NEXRAD estimation there was around a 12 in underestimation of rainfall. The SJRWMD NEXRAD rainfall estimation is close to the rain gauge as it was bias corrected by the OneRain proprietary process which utilized the SJRWMD rain gauge network.

Table 4 - Comparison of the annual rainfall at the Ransom Road rain gauge, SJRWMD NEXRAD 112745 cell, and the corresponding NWS NEXRAD bias corrected and non-bias corrected cells.

Site	Rainfall (in)
Ransom Road Rain Gauge	63.4
SJRWMD NEXRAD 112745	64.1
NWS NEXRAD Bias Corrected Average	51.2
NWS NEXRAD Unbiased Average	25.9

A portion of the underestimation between the NWS NEXRAD and the rain gauge can be explained by the spatial variability in the rainfall patterns between the ICPR cells (Table 5). Within the boundary of SJRWMD NEXRAD 112745 cell there was range of 18.8 in between the NEXRAD cells. The L19 cell which contains the Ransom Road rain gauge had an annual rainfall of 56.3 in while the M19 cell to the south had the much closer 63.9 in of annual rainfall. Due to the nature of a point measurement from the rain gauge and the characteristics of storms in Florida, it is not unexpected for this variability to occur (NOAA, 2017).

Table 5 - Annual rainfall of the ICPR rainfall cells in the SJRWMD NEXRAD 112745 cell. Cell L19 contains the Ransom Road rain gauge and is bolded.

Grid Y Axis	Grid X Axis				
	16	17	18	19	20
K	47.2	48.8	47.2	48.0	45.4
L	46.0	51.1	50.3	56.3	54.0
M	47.6	53.0	47.9	63.9	58.7
N	48.4	47.4	45.1	61.6	58.2
O	49.4	45.9	45.3	55.5	56.6

During 2017 the seasonality of rainfall was apparent with the wet (June-October) season totaling 53.9 in and the dry (November-May) season at 7.6 in measured at the Ransom Road rain gauge (Table 6). The dry season NWS NEXRAD bias corrected rainfall estimates were 6.9 in, similar to the Ransom Road rain gauge. The wet season estimates were 42.4 in, an underestimation of 11.5 in. The underestimation of larger and more severe storm events has been observed in Florida NEXRAD data and is partially due to wind patterns, the size of the storm, and the differing nature of how rain gauges and NEXRAD measure

rainfall (Skinner *et al.*, 2009). September and October had the highest rainfall of the year with Hurricane Irma in September and an unusually wet October. These two months also had the highest underestimation by the NWS NEXRAD bias corrected rainfall estimates.

Table 6 – 2017 Monthly rainfall accumulations between the Ransom Road rain gauge, SJRWMD NEXRAD rainfall, and the NOAA NEXRAD bias-corrected rainfall.

Month	SJRWMD Ransom Road Gauge	SJRWMD NEXRAD 112745	NOAA NEXRAD
Jan	2.1	1.9	1.9
Feb	2.7	2.6	2.1
Mar	0.9	1.0	1.0
Apr	0.1	0.2	0.2
May	1.8	1.8	1.7
Jun	9.6	9.4	8.1
Jul	6.1	6.4	6.3
Aug	8.2	8.2	8.1
Sep	16.5	16.9	12.0
Oct	13.7	13.8	7.9
Nov	1.5	1.5	1.4
Dec	0.4	0.5	0.5

Between September 8 – 11th Hurricane Irma passed over the region, with a total of 13.4 in of rainfall measured at the Ransom Road rain gauge. In ICPR cell L19, 9.3 in of rainfall was estimated to have fallen during the same period. As the spatial distribution of rainfall over the month was uniform (Table 7), it is likely that the NWS NEXRAD bias corrected rainfall estimate underestimated the hurricane rainfall.

Table 7 - Rainfall accumulation of September 2017 for the ICPR cells in the SJRWMD NEXRAD 112745 cell. Cell L19 contains the Ransom Road rain gauge and is bolded.

Grid Y Axis	Grid X Axis				
	16	17	18	19	20
K	12.9	11.9	11.6	11.7	11.2
L	13.2	12.7	12.0	11.7	11.5
M	13.2	12.3	11.9	12.1	11.7
N	13.1	11.7	11.4	12.1	11.8
O	12.8	11.5	11.3	11.5	11.8

During October 2017 there were several high rainfall storms that passed over NMI. As the spatial distribution of rainfall in Table 8 shows, these storms did not pass equally over the area and appear to have resulted in a higher accumulated rainfall in the east to southeast of the cell. The Florida wet season is characterized by intense storms with smaller footprints and the spatial variation in rainfall in the cells the result of one or more of these types of storms.

Table 8 - Rainfall accumulation of October 2017 for the ICPR cells in the SJRWMD NEXRAD 112745 cell. Cell L19 contains the Ransom Road rain gauge and is bolded.

Grid Y Axis	Grid X Axis				
	16	17	18	19	20
K	4.3	6.5	5.5	7.5	5.4
L	4.7	4.5	4.3	11.4	10.6
M	5.3	6.0	4.4	14.4	12.0
N	5.5	5.0	4.9	16.6	13.9
O	5.6	6.8	6.2	14.0	12.6

Overall hourly NWS NEXRAD bias corrected rainfall estimates exhibit a pattern of underestimation of rainfall in 2017 when compared to the measured rainfall at the Ransom Road rain gauge (Figure 9). With more intense storms there does appear to be a consistent pattern of over and under estimation between the two datasets. With a correlation of 0.72, there is still an overall good agreement between the estimated and measured rainfall.

Comparison of Hourly NOAA NEXRAD Bias Corrected Rainfall Estimates to the Ransom Road Rain Gauge




Figure 9 – Paired NWS NEXRAD bias corrected rainfall estimates in 2017 with measurements at the SJRWMD Ransom Road rain gauge.

August 16, 2017 was chosen to reflect the excellent agreement between measured and estimated rainfall during an average storm event. The day's accumulated rainfall was 4.1 in at the Ransom Road rain gauge and 4.3 in for the NWS NEXRAD bias corrected cell L19. There were two distinct periods of rain between 17:00 – 23:00. The NEXRAD estimation was summarized to every 15 minutes as the rain gauge collects data at this interval. Rainfall intensity varied over the course of the storm and between the measurement methods which is expected from the two systems.

Table 9 – Rainfall accumulations in inches at the SJRWMD Ransom Road rain gauge and the NWS NEXRAD bias corrected rainfall estimate for August 16, 2017 at a 15-minute timestep. Two storm events are shown, starting at 5 PM and 9:30 PM.

Date	Ransom Road Rain Gauge	NWS NEXRAD Bias Corrected Rainfall Estimate
8/16/2017 17:00	0.0	0.0
8/16/2017 17:15	0.7	0.8
8/16/2017 17:30	1.0	1.0
8/16/2017 17:45	0.3	0.2
8/16/2017 18:00	0.0	0.0
8/16/2017 21:30	0.0	0.1
8/16/2017 21:45	0.5	1.0
8/16/2017 22:00	0.9	0.7
8/16/2017 22:15	0.8	0.6
8/16/2017 22:30	0.0	0.0
8/16/2017 22:45	0.0	0.0
Daily Total	4.1	4.3

2040 Synthetic Simulation of Future Rainfall

CMIP5 projected rainfall patterns in 2040 and 2041 were able to represent a La Niña dry year and El Niño wet year, respectively (Figure 10). From 2017 to 2040 the annual precipitation is projected to decrease by 6% and to 2041 an increase of 3%. For both 2040 and 2041, the dry season (Nov-May) is projected to be drier overall. The 2041 wet year projection of June is to be 35% wetter than the 2017 project baseline.




Figure 10 – Comparison of projection adjusted NEXRAD rainfall estimates for 2040 (Dry year) and 2041 (Wet year) to 2017 NWS NEXRAD bias corrected rainfall estimates.

Table 10 – Projected percent rainfall over North Merritt Island in 2040 and 2041 relative to 2017.

Month	2040	2041
Jan	65%	85%
Feb	93%	90%
Mar	110%	117%
Apr	79%	86%
May	79%	93%
Jun	95%	135%
Jul	87%	104%
Aug	98%	102%
Sep	91%	99%
Oct	98%	99%
Nov	122%	103%
Dec	129%	122%
Annual	94%	103%

2017 Stage Level Simulation

Continuous Monitoring Stations

The estimated surface water stages monthly statistics for BR and NIRL in 2017 are shown in Table 11 and Table 12, respectively. The time series largely reflects the expected variability on both the short and long term. On a week-by-week basis, basin stages are expected to vary due to wind strength and direction along with rainfall (Weaver *et al.*, 2016). This is observed in both the BR (Figure 11) and NIRL (Figure 12) throughout the year. There is a notable deviation between NIRL and BR estimated stages starting in January and continuing to March, with BR estimated to be continually higher than NIRL (Figure 13). After Hurricane Irma in September the deviation in estimated stage between the two basins returns with NIRL having a higher estimated stage for the remainder of the year.

These surface water stages contain significant sources of error and represent the best available estimations of stage for the NIRL and BR around NMI. This data was created from measurement of sensor depth and the strain gauge style sensor that the CM stations use to measure depth can have drift and biofouling issues. The CM station location changed in Banana River in March, which corresponds with the decrease in estimated water stage for the basin. The estimated surface water stages from the CM stations can show general trends in the estimated stage but have notable error in the beginning and end of the time series.

Table 11 - Banana River Continuous Monitoring Stations "Merritt Island Causeway at SR 520 (WQ)" (Station ID 33964621) and "IRLB04 Banana River (WQ)" (Station ID 33844736) surface stage summary statistics by month in meters NAVD88.

Month	Average	Max	Min	Std Dev
Jan	-0.14	0.02	-0.39	0.09
Feb	-0.21	-0.03	-0.39	0.06
Mar	-0.18	-0.01	-0.38	0.08
Apr	-0.21	-0.15	-0.29	0.03
May	-0.33	-0.17	-0.45	0.05
Jun	-0.25	-0.05	-0.39	0.07
Jul	-0.31	-0.18	-0.42	0.05
Aug	-0.26	-0.14	-0.37	0.05
Sep	-0.03	0.32	-0.23	0.14
Oct	0.02	0.26	-0.29	0.14
Nov	-0.20	-0.08	-0.30	0.05
Dec	-0.30	-0.07	-0.47	0.11

Table 12 – North Indian River Lagoon (NIRL) Continuous Monitoring station "Titusville Max Brewer Memorial Parkway (WQ)" (Station ID 33954622) 2017 surface stage summary statistics by month in meters NAVD88.

Month	Average	Max	Min	Std Dev
Jan	-0.26	-0.09	-0.52	0.10
Feb	-0.36	-0.16	-0.53	0.07
Mar	-0.31	-0.18	-0.47	0.07
Apr	-0.19	-0.03	-0.36	0.07
May	-0.25	-0.05	-0.40	0.07
Jun	-0.17	-0.02	-0.26	0.05
Jul	-0.25	-0.06	-0.43	0.09
Aug	-0.30	-0.13	-0.40	0.06
Sep	0.01	0.29	-0.29	0.18
Oct	0.20	0.44	-0.17	0.13
Nov	-0.03	0.11	-0.16	0.06
Dec	-0.07	0.14	-0.28	0.09

Comparison of the SJRWMD Continuous Monitoring Banana River Estimated Elevation With NOAA Trident Park and USGS Haulover Canal for 2017




Figure 11- Water level estimations in m NAVD88 for the Banana River (East) side of North Merritt Island for 2017 from the SJRWMD Continuous Monitoring (CM) stations compared against the NOAA Trident Park and USGS Haulover Canal readings.

Comparison of the SJRWMD Continuous Monitoring North Indian River Lagoon Estimated Elevation With NOAA Trident Park and USGS Haulover Canal for 2017




Figure 12 – Water level estimations in m NAVD88 for the Indian River Lagoon (West) side of North Merritt Island for 2017 from the SJRWMD Continuous Monitoring (CM) stations compared against the NOAA Trident Park and USGS Haulover Canal readings.

Deviation of Estimated Elevation Between North Indian River Lagoon and Banana River for Continuous Monitoring Stations 2017




Figure 13 - Water level estimation deviation in m NAVD88 from the North Indian River Lagoon (West) and Banana River (East) side of North Merritt Island for 2017 from the SJRWMD Continuous Monitoring (CM) stations.

Coastal Modeling System (CMS) Model

The CMS model has been previously calibrated with respect to the match between predicted and measured water levels (Zarillo, 2015, 2018). To further verify the model calibration, measured water levels at the USGS monitoring station at Haulover Canal were compared to model predictions for 2017 (Figure 14). The Haulover Canal connects the north compartment of the IRL with the southern compartment of the Mosquito Lagoon and is the water level monitoring station closest to North Merritt Island (NMI). No vertical adjustments or filters were applied to either the measured or model data before making the comparison. The comparison is considered very good considering the limitations of both the model and measured data.

Both the model and measured data capture the annual sea level cycle that includes the typically low sea levels of late July, followed by high sea levels in late October. The sea level shifts are related to the dynamics of the Gulf Stream as explained by Ezer *et al.* (2013). There is little to no tidal signal in both the observed and model data. The low frequency season shifts of sea level in the coastal ocean are not filtered by the tidal inlets of the IRL system and propagate throughout the system. The annual sea level cycle can be as large as 1 meter and drives water mass exchanges with the coastal ocean over a 12-month period. Shorter term circulation patterns in the IRL can be attributed to wind forcing as well as tidal water flow near inlets. Although the trend of the model data is slightly below the observed data for portions of 2017, there is a good correlation between observed and model data.

Comparison of 2017 Haulover Canal and Modeled Surface Water Elevations



Figure 14 - Comparison of 2017 measured and model water level data at Haulover Canal. R-value is 0.91 and R2 value is 0.84.

The 2017 monthly summary statistics of the modeled stages for NIRL and BR are shown in Table 13 and Table 14, respectively. Over 2017 the modeled stage between the two basins trended closely (Figure 15) and under normal conditions typically varied less than 10 cm (Figure 16). This contrasts with the variation in the continuous monitoring estimated stages.

Table 13 – North Indian River Lagoon (NIRL) modeled surface stage summary statistics by month in meters NAVD88.

Month	Average	Max	Min	Std Dev
Jan	-0.23	-0.04	-0.33	0.06
Feb	-0.30	-0.20	-0.36	0.04
Mar	-0.31	-0.20	-0.40	0.03
Apr	-0.21	-0.11	-0.27	0.03
May	-0.26	-0.17	-0.33	0.03
Jun	-0.21	-0.12	-0.28	0.04
Jul	-0.23	-0.14	-0.32	0.04
Aug	-0.18	-0.06	-0.25	0.04
Sep	0.09	0.46	-0.12	0.13
Oct	0.11	0.30	-0.12	0.11
Nov	-0.03	0.13	-0.17	0.07
Dec	-0.15	0.04	-0.32	0.10
Annual	-0.16	0.46	-0.40	0.15

Table 14 – Banana River (BR) modeled surface stage summary statistics by month in meters NAVD88

Month	Average	Max	Min	Std Dev
Jan	-0.22	-0.03	-0.33	0.06
Feb	-0.30	-0.19	-0.37	0.04
Mar	-0.32	-0.15	-0.44	0.04
Apr	-0.21	-0.10	-0.27	0.04
May	-0.25	-0.13	-0.33	0.04
Jun	-0.21	-0.11	-0.28	0.04
Jul	-0.23	-0.14	-0.32	0.04
Aug	-0.18	-0.04	-0.26	0.05
Sep	0.09	0.47	-0.12	0.14
Oct	0.11	0.31	-0.13	0.10
Nov	-0.04	0.14	-0.19	0.07
Dec	-0.14	0.05	-0.33	0.11
Annual	-0.16	0.47	-0.44	0.15

2017 Modeled Elevations for North Indian River Lagoon and Banana River




Figure 15 – Comparison of the 2017 modeled stages of the North Indian River Lagoon (NIRL) and Banana River (BR).

2017 Modeled and Continuous Monitoring Estimated Elevation Difference Between Banana River and North Indian River Lagoon




Figure 16 – Comparison of the 2017 differences between Banana River (BR) and North Indian River Lagoon (NIRL) for modeled and continuous monitoring estimated stages.

2040 Synthetic Simulation of Future Stage Level

Summary statistics for 2040 under average conditions for NIRL and BR are listed in Table 15 and Table 16, respectively. The modeled 2040 surface water stages under average conditions are displayed in Figure 17 and with an extreme storm surge event in Figure 18. Model results for NIRL and BR were similar, varying in stage by not more than about 5 cm except under the extreme storm surge event. Maximum storm surge stages reached about 2 m above normal levels in the IRL west of Merritt Island. In the BR to the east of Merritt Island, maximum predicted surge levels are about 1.5 m above normal levels. Although storm surge is known to penetrate through the IRL system, storm surge is attenuated as it moves north through the narrow entrance to the BR.

Table 15 - North Indian River Lagoon (NIRL) 2040 modeled average condition surface stage summary statistics by month and annually in meters NAVD88.

Month	Average	Max	Min	Std Dev
Jan	0.02	0.13	-0.08	0.05
Feb	-0.04	0.08	-0.11	0.04
Mar	-0.05	0.07	-0.16	0.04
Apr	0.05	0.15	-0.02	0.03
May	0.00	0.09	-0.08	0.03
Jun	0.04	0.15	-0.04	0.04
Jul	0.02	0.12	-0.07	0.04
Aug	0.07	0.20	0.01	0.05
Sep	0.35	0.76	0.14	0.13
Oct	0.37	0.58	0.14	0.11
Nov	0.23	0.41	0.07	0.07
Dec	0.11	0.31	-0.07	0.10
Annual	0.10	0.76	-0.16	0.16

Table 16 - Banana River 2040 modeled average condition surface stage summary statistics by month and annually in meters NAVD88.

Month	Average	Max	Min	Std Dev
Jan	0.03	0.17	-0.07	0.05
Feb	-0.04	0.08	-0.12	0.05
Mar	-0.06	0.11	-0.18	0.05
Apr	0.05	0.16	-0.02	0.04
May	0.00	0.13	-0.07	0.04
Jun	0.05	0.15	-0.03	0.05
Jul	0.03	0.12	-0.07	0.05
Aug	0.08	0.22	0.00	0.05
Sep	0.35	0.74	0.14	0.14
Oct	0.37	0.58	0.14	0.10
Nov	0.22	0.41	0.07	0.07
Dec	0.11	0.32	-0.07	0.11
Annual	0.10	0.74	-0.18	0.15

2040 Average Conditions Modeled Elevations for North Indian River and Banana River




Figure 17 – Comparison of the 2040 North Indian River Lagoon (NTRL) and Banana River (BR) modeled stages under average conditions.

2040 Extreme Storm Surge Modeled Elevations for Indian River 5N and Banana River 2N




Figure 18 - Comparison of the 2040 North Indian River Lagoon (NIRL) and Banana River (BR) modeled stages with an extreme storm surge.

Summary

The estimation of rainfall and modeled surface water stage for 2017 and 2040 should provide reliable inputs to the ICPR4 model for the NMI area. Rainfall, surface water stage estimations, and models for NMI utilized a variety of datasets to overcome sparse data availability. The NWS NEXRAD rainfall estimates were able to provide a spatially and temporally high-resolution coverage over the NMI area. The SJRWMD Continuous Monitoring (CM) station 2017 estimated stages were able to capture the short-term variations in stage, but the Coastal Modeling System Flow (CMS-Flow) modeled stages were more representative of long-term trends.

The resulting rainfall surfaces were validated against the SJRWMD Ransom Road rain gauge station, with a R^2 of 0.72 between the hourly bias-corrected rainfall estimates and gauge readings for all of 2017. A pattern of underestimation was identified with an annual rainfall of 63.4 inches (1,610 mm) measured at the rain gauge, and the bias-corrected rainfall estimated 51.2 inches (1,300 mm). While there is underestimation of Hurricane Irma, this could be due to the extreme conditions experienced at the rain gauge and other factors confounding NEXRAD. Additionally, due to the higher spatial resolution of the NEXRAD DAA and the small footprint, intense storm characteristic of Florida could result in the one rain gauge missing storm events.

Both the CM and CMS-Flow stage estimations averaged -0.79 ft (-0.24 m) NAVD88 for both NIRL and BR from January to August, captured the storm surge from Hurricane Irma, and detected the late October Gulf Stream high sea levels. The CM estimated stages between NIRL and BR for several months ranged between 0.82 – 2.46 ft (0.25 – 0.75 m) NAVD88, compared to the 1-3 day long 0.32 in (10 cm) variation in the CMS-Flow model. The CMS-Flow model was validated against the USGS Haulover Canal station with a R^2 value of 0.84 though with a 0.32 in (10 cm) underestimation of stage throughout the year.

The 2017 Multi Model Mean (MMM) was chosen as the baseline and the projected annual increase of 3% to 2040 was used as the wet year and 6% decrease to 2041 used for the dry year. The 2040 surface water stages were generated in the CMS-Flow model using a 0.852 ft (0.259 m) sea level rise from the NOAA intermediate-high projection. NIRL and BR continued to have similar variations in the modeled 2040 series as they did in the 2017 model. A second 2040 model was run that applied an extreme storm surge of 13.1 ft (4 m) to the system, which identified BR as having a 1.6 ft (0.5 m) lower projected stage than NIRL during the storm surge.

References

- Bracken, C. (2016). Downscaled CMIP3 and CMIP5 Climate Projections - Addendum. Technical Service Center, Bureau of Reclamation, US Department of the Interior, Denver, CO, 1.
- Bredesen, A., & Brown, C. J. (2018). Comparison of Hydrologic Model Performance Statistics Using Rain Gauge and NEXRAD Precipitation Input at Different Watershed Spatial Scales and Rainfall Return Frequencies for the Upper St. Johns River, Florida USA. In Multidisciplinary Digital Publishing Institute Proceedings (Vol. 7, No. 1, p. 11).
- Buttolph, A. M., Reed, C. W., Kraus, N. C., Ono, N., Larson, M., Camenen, B., ... & Zundel, A. K. (2006). Two-dimensional depth-averaged circulation model CMS-M2D: Version 3.0, Report 2, sediment transport and morphology change. ENGINEER RESEARCH AND DEVELOPMENT CENTER VICKSBURG MS COASTAL AND HYDRAULICS LAB.
- Demirbilek, Z., & Rosati, J.D. (2011). "Verification and Validation of the Coastal Modeling System, Report 1: Executive Summary," ERDC/CHL-TR-11-10, US Army Engineer Research and Development Center, Coastal and Hydraulics Laboratory, Vicksburg, Mississippi.
- Dessalegne, T., Obeysekera, J., Nair, S., & Barnes, J. (2016). Assessment of CMIP5 Multi-Model Dataset to Evaluate Impacts on the Future Regional Water Resources of South Florida. In World Environmental and Water Resources Congress 2016 (pp. 586-596).
- Infanti, J. M., Kirtman, B. P., Aumen, N. G., Stamm, J., & Polsky, C. (2020). Assessment of uncertainty in multi-model means of downscaled South Florida precipitation for projected (2019–2099) climate. *International Journal of Climatology*, 40(5), 2764-2777.
- Lin, L., Demirbilek, Z., Thomas, R., & Rosati III, J. (2011). "Verification and Validation of the Coastal Modeling System, Report 2: CMS-Wave," ERDC/CHL-TR-11-10, US Army Engineer Research and Development Center, Coastal and Hydraulics Laboratory, Vicksburg, Mississippi.
- Listopad, C. (2015). Spatial Watershed Iterative Loading Model Methodology Report. Indialantic, FL: Applied Ecology, Inc. for Brevard County Natural Resources.
- Mahjabin, T., & Abdul-Aziz, O. I. (2020). Trends in the Magnitude and Frequency of Extreme Rainfall Regimes in Florida. *Water*, 12(9), 2582.
- NOAA Office of the Federal Coordinator for Meteorological Services and Supporting Research (2017). WSR-88D Meteorological Observations: Part C Products and Algorithms
- Pierce, D. W., Cayan, D. R., & Thrasher, B. L. (2014). Statistical downscaling using localized constructed analogs (LOCA). *Journal of Hydrometeorology*, 15(6), 2558-2585.
- Sanchez, A., Beck, T., Lin, L., Demirbilek, Z., Brown, M., & Li, H. (2012) CMS User Manual (DRAFT) ERDC/CHL, US Army Engineer Research and Development Center, Coastal and Hydraulics Laboratory, Vicksburg, Mississippi.
- Sanchez, A., Wu, W., Beck, T.M., Li, H., Rosati III, J., Thomas, R., Rosati, J.D., Demirbilek, Z., Brown, M., & Reed, C. (2011a). "Verification and Validation of the Coastal Modeling System, Report 3:


Hydrodynamics," ERDC/CHL-TR-11-10, US Army Engineer Research and Development Center, Coastal and Hydraulics Laboratory, Vicksburg, Mississippi.

- Sanchez, A., Wu, W., Beck, T.M., Li, H., Rosati, J.D., Demirbilek, Z., & Brown, M. (2011b). "Verification and Validation of the Coastal Modeling System, Report 4: Sediment Transport and Morphology Change," ERDC/CHL-TR-11-10, US Army Engineer Research and Development Center, Coastal and Hydraulics Laboratory, Vicksburg, Mississippi.
- Skinner, C., Bloetscher, F., & Pathak, C. S. (2009). Comparison of NEXRAD and rain gauge precipitation measurements in South Florida. *Journal of Hydrologic Engineering*, 14(3), 248-260.
- Southeast Florida Regional Climate Change Compact Sea Level Rise Work Group (Compact) (2020). A document prepared for the Southeast Florida Regional Climate Change Compact Climate Leadership Committee. 36p.
- Sweet, W. W. V., Kopp, R., Weaver, C. P., Obeysekera, J. T. B., Horton, R. M., Thieler, E. R., & Zervas, C. E. (2017). Global and regional sea level rise scenarios for the United States.
- Wang, H., & Asefa, T. (2018). Impact of different types of ENSO conditions on seasonal precipitation and streamflow in the Southeastern United States. *International Journal of Climatology*, 38(3), 1438-1451.
- Weaver, R. J., Johnson, J. E., & Ridler, M. (2016). Wind-driven circulation in a shallow microtidal estuary: The Indian river lagoon. *Journal of Coastal Research*, 32(6), 1333-1343.
- Wu, W., A. Sanchez, & M. Zhang. (2010). An Implicit 2-D Depth-Averaged Finite-Volume Model of Flow and Sediment Transport in Coastal Waters. June 30 – July 5, 2010, 32nd International Conference on Coastal Engineering (ICCE 2010) Shanghai, China.
- Zarillo, G. (2019). Numerical Model Flushing Experiments Addendum Report: submitted to the Indian River Lagoon National Estuary Program and Canaveral Port Authority.
- Zarillo, G., Listopad, C. (2018). Impacts of Environmental Muck Dredging 2014-2018 at Florida Institute of Technology Quarterly Progress Report, Subtask 6: Hydrologic and Water Quality Model for Management and Forecasting within Brevard County Waters of the Indian River Lagoon. Melbourne, FL: Florida Institute of Technology for Brevard County Natural Resource Management Office.

Appendix D

Field Data Collection Memorandum

prepared by Atkins, December 2020



Field Data Collection Memo

To: Allyson Hunt, PE

From: Joe Walter, PE

Email: joe.walter@atkinsglobal.com

Date: 30 December 2020

Phone: 407-806-4486

Ref: Atkins Project100071502

cc: Chris Thompson, PE
File

Subject: North Merritt Island Field Data Review

The purpose of this memo is to summarize the field data collection effort as part of the North Merritt Island Basin Update. Field crews visited 85 sites where data evaluated from SWAMP database or ERP documentation was inconsistent or absent. Field crews photographed and documented each hydraulic feature visited noting condition, material and dimensions. As appropriate crews also verified drainage patterns where available digital data proved inconclusive or did not provide enough information to determine the drainage pattern. Depending upon the field observations, recommendations were made to provide immediate maintenance and/or provide a survey of the observed structures. **Figure 1** provides a spatial view of the links visited.

Table 1 summarizes the data collection effort indicating model link name, type of structure, SWAMP feature ID, date surveyed, and the recommendation to survey or provide maintenance. Field data collection sheets, including field data collection notes and structure photograph are provided in **Appendix A**. As a separate attachment, the feature class for the field visits, survey recommendations, and maintenance recommendations are provided in the NMI_fieldCollection.mdb geodatabase.




Figure 1: North Merritt Island Field Data Collection Sites





Table 1: North Merritt Island Field Data Collection Summary


Link Name	Link Type	SWAMP ID	Date Visited	Survey	Maint
DSykesN_1	Drop Structure	BCE602CS110	05-Nov-20		
DSykesN_2	Drop Structure	BCE602CS109	05-Nov-20		
DSykesN_3	Drop Structure	BCE602CS108	05-Nov-20		
DSykesS_1	Drop Structure	BCE611CS012		Y	
DSykesS_2	Drop Structure	BCE611CS010		Y	
DSykesS_3	Drop Structure	BCE611CS008		Y	
DB1000_1	Drop Structure	233634CU44AB	03-Nov-20		
PB2020_1	Pipe	P016D634021022	03-Nov-20		Y
PB4040_1	Pipe	233634CU47AB	03-Nov-20	Y	Y
WB3060_1	Weir	Not in SWAMP	03-Nov-20		Y
PC1020_1	Pipe	P040E602086085	05-Nov-20		
PC1060_1	Pipe	0000CU0000	03-Nov-20		
PC1080_1	Pipe	NO FEATURE CODE	03-Nov-20		Y
PC1085_1	Pipe	P018D627035032	03-Nov-20		
PC1090_1	Pipe	In SWAMP wo Feature Code	03-Nov-20		
PC1092_1	Pipe	Not in SWAMP	03-Nov-20	Y	Y
PC1130_1	Pipe	Not in SWAMP	03-Nov-20	Y	Y
PC1160_1	Pipe	In SWAMP wo Feature Code	03-Nov-20	Y	Y
PCC1100_1	Pipe	Not in SWAMP	03-Nov-20		
PD1070_1	Pipe	0000CU0000	03-Nov-20		Y
PDD1002_1	Pipe	BC233624CU009	03-Nov-20	Y	Y
PDD1010_1	Pipe	BC233624CU008	03-Nov-20	Y	
PDD3315_1	Pipe	P015D623029030	03-Nov-20		Y
PDD3335_1	Pipe	P021D623042041	03-Nov-20		Y
PDD3345_1	Pipe	P012D623024023	03-Nov-20		Y
PDD3405_1	Pipe	P007D623013014	03-Nov-20		Y
DEE3100_1	Drop Structure	BCE611CS048	05-Nov-20		
PEE1060_1	Pipe	P094D634135133	03-Nov-20		Y
PEE3010_1	Pipe	Not in SWAMP	05-Nov-20		
PEE3010_2	Pipe	P052E602100081	05-Nov-20		
PEE3020_1	Pipe	In SWAMP wo feature code	03-Nov-20	Y	
PEE3030_2	Pipe	Not in SWAMP	05-Nov-20		
PEE3040_1	Pipe	In SWAMP wo feature code	03-Nov-20	Y	Y
PEE3110_1	Pipe	BCE611CS047	05-Nov-20		
PEE3280_1	Pipe	Not in SWAMP	03-Nov-20	Y	Y
PEE3310_1	Pipe	Not in SWAMP	05-Nov-20		
PEE4160_1	Pipe	P161E603217218	03-Nov-20	Y	Y
PEE5060_1	Pipe	P023E610033034	03-Nov-20	Y	Y



Link Name	Link Type	SWAMP ID	Date Visited	Survey	Maint
PEE5060_2	Pipe	P025E610039040	03-Nov-20	Y	Y
DF1180_1	Drop Structure	BCD623CS135	03-Nov-20		
PF2080_1	Pipe	P053D626110109	05-Nov-20		
PF2110_1	Pipe	NO FEATURE CODE	03-Nov-20		Y
PF2110_2	Pipe	Not in SWAMP	03-Nov-20		
DFF1060_1	Drop Structure	BCE602CS158	05-Nov-20		
DFF1090_1	Drop Structure	BCE602CS146	05-Nov-20		
DFF1230_1	Drop Structure	BCE611CS096	05-Nov-20		Y
PFF1010_2	Pipe	P047E602080077	05-Nov-20		
PFF1060_1	Pipe	P088E602133134	05-Nov-20	Y	
PFF1180_1	Pipe	P042E611074075	05-Nov-20		Y
PFF1210_1	Pipe	P045E611079080	05-Nov-20		Y
WFF2010_1	Weir	BCE602CS111	05-Nov-20		
DG1840_1	Drop Structure	BCE602CS069	05-Nov-20		
DG6050_1	Drop Structure	P130D63516816	03-Nov-20		
PG1790_1	Pipe	P035E602091088	05-Nov-20		
PG6040_1	Pipe	P110D635140141	05-Nov-20		
DGG1030_1	Drop Structure	BCE601CS001	05-Nov-20		
PGG1010_1	Pipe	P001E601011010	05-Nov-20	Y	
PGG1020_1	Pipe	0000CU0000	05-Nov-20		
PGG1060_2	Pipe	Not in SWAMP	05-Nov-20		Y
PGG1110_2	Pipe	P004E612005006	05-Nov-20		
PGG1150_1	Pipe	P014E612021022	05-Nov-20		Y
DJ1900_1	Drop Structure	BCE601CS086	05-Nov-20		
DL1270_1	Drop Structure	BCD625CS092	05-Nov-20		
DL1790_1	Drop Structure	BCD625CS099	05-Nov-20	Y	
PL1345_1	Pipe	BC233625CU010	03-Nov-20	Y	Y
PM2940_1	Pipe	0000CU0000	03-Nov-20		
PM2970_1	Pipe	P006D624008007	03-Nov-20		Y
PM2980_1	Pipe	0000CU0000	03-Nov-20	Y	Y
PM3000_1	Pipe	0000CU0000	03-Nov-20	Y	Y
PO1300_1	Pipe	Not in SWAMP	05-Nov-20		
PO2960_1	Pipe	Not in SWAMP	03-Nov-20	Y	
PO3030_2	Pipe	BC233636CU003	05-Nov-20	Y	
PP2641_1	Pipe	P024D626038037	05-Nov-20		
PP2641_2	Pipe	P023D626036039	05-Nov-20		
DPI1030_2	Drop Structure	BCE610CS011	03-Nov-20		
DPI1030_3	Drop Structure	BCD610CS001	03-Nov-20		
DPI2020_1	Drop Structure	0000CU000	03-Nov-20		



Link Name	Link Type	SWAMP ID	Date Visited	Survey	Maint
PPI2010_1	Pipe	0000CU0000	03-Nov-20	Y	Y
PPI2010_2	Pipe	0000CU0000	03-Nov-20	Y	Y
PPI2020_3	Pipe	P015D610016017	03-Nov-20		
PR3200_1	Pipe	0000CU0000	03-Nov-20	Y	
DS1140_1	Drop Structure	0000SC0000	03-Nov-20	Y	
PT2440_2	Pipe	0000CU0000	03-Nov-20		
DU4030_1	Drop Structure	Not in SWAMP	03-Nov-20		
PU1120_1	Pipe	Not in SWAMP	03-Nov-20		
PU2450_1	Pipe	0000CU0000	03-Nov-20		
PU4220_1	Pipe	0000CU0000	03-Nov-20	Y	Y
PZZ2010_1	Pipe	Not in SWAMP	03-Nov-20		



Appendix A: NMI Field Data Collection Forms




North Merritt Island Field Inspection Form

Link Name:DSykesN_1

Lat: 28.433942972

Long: -80.69646097

SWAMPid: BCE602CS110



Location



Field Photo

11/5/2020

Survey Need: No

SurveyDescription:

Maintenance Need: No

Field Visit Notes: Control Structure is a 48 inch half culvert. SWAMP top El 2.14 NAVD88. Weir opening 43" board 10" from top of structure. Per SWAMP 36" CMP 42 ft long -2.55 NAVD88 upstream - 1.92 NAVD88 downstream

Drainage Pattern Verification:

Drainage Pattern Comment:




North Merritt Island Field Inspection Form

Link Name:DSykesN_2

Lat: 28.433942972

Long: -80.69646097

SWAMPid: BCE602CS109



Location



Field Photo

11/5/2020

Survey Need: No

SurveyDescription:

Maintenance Need: No

Field Visit Notes: Aluminum box vertical structure 48" x 16 inches. SWAMP top 2.95 NAVD88. 44" opening 21" below top. 48" cmp 42' long upstream -2.21 NAVD88 downstream -2.05 NAVD88.

Drainage Pattern Verification:

Drainage Pattern Comment:




North Merritt Island Field Inspection Form

Link Name:DSykesN_3

Lat: 28.433942972

Long: -80.69646097

SWAMPid: BCE602CS108



Location



Field Photo

11/5/2020

Survey Need: No

SurveyDescription:

Maintenance Need: No

Field Visit Notes: Aluminum box vertical structure 48" x 16 inches. SWAMP top 3.08 NAVD88. 44" opening 25" below top. 48" cmp 42' long upstream -2.19 NAVD88 downstream-1.92 NAVD88.

Drainage Pattern Verification:

Drainage Pattern Comment:



North Merritt Island Field Inspection Form

Link Name:DSykesS_1

SWAMPid: BCE611CS012

Lat: 28.409655587

Long: -80.69401797



Location



Field Photo

Survey Need: Yes

SurveyDescription: Weir Structure

Maintenance Need: No

Field Visit Notes: Dual control structure with flashboards. Could not access in the field due to current construction activities.

Drainage Pattern Verification:

Drainage Pattern Comment:



North Merritt Island Field Inspection Form

Link Name:DSykesS_2

Lat: 28.409655587

Long: -80.69401797

SWAMPid: BCE611CS010



Location



Field Photo

Survey Need: Yes

SurveyDescription: Weir Structure

Maintenance Need: No

Field Visit Notes: Dual control structure with flashboards. Could not access in the field due to current construction activities.

Drainage Pattern Verification:

Drainage Pattern Comment:



North Merritt Island Field Inspection Form

Link Name:DSykesS_3

Lat: 28.409655587

Long: -80.69401797

SWAMPid: BCE611CS008



Location



Field Photo

Survey Need: Yes

SurveyDescription: Weir Structure

Maintenance Need: No

Field Visit Notes: Dual control structure with flashboards. Could not access in the field due to current construction activities.

Drainage Pattern Verification:

Drainage Pattern Comment:




North Merritt Island Field Inspection Form

Link Name:DB1000_1

Lat: 28.421908972

Long: -80.71693197

SWAMPid: 233634CU44AB



Location



Field Photo

11/3/2020

Survey Need: No

SurveyDescription:

Maintenance Need: No

Field Visit Notes: The structure is on private property. The homeowner indicated that the County had installed the box to drain his yard across the road into the ditch that outfalls into the IRL. This is a minor structure free of debris. Grate size measured is 12" x 12" cast iron with 15" culvert connecting across the roadway.

Drainage Pattern Verification: Y

Drainage Pattern Comment: Confirmed that this area connects across Hall Road.




North Merritt Island Field Inspection Form

Link Name:PB2020_1

SWAMPid: P016D634021022

Lat: 28.442315

Long: -80.717027



Location



Field Photo

11/3/2020

Survey Need: No

SurveyDescription:

Maintenance Need: Yes

Field Visit Notes: Represents multiple culverts along roadway. Use NorthGrove Dr as control 19x30 ERCP SWAMP inverts 1.04 NAVD88 and 0.97 NAVD88. Culverts in swale in disrepair and partially silted.

Drainage Pattern Verification:

Drainage Pattern Comment:




North Merritt Island Field Inspection Form

Link Name:PB4040_1

Lat: 28.445402972

Long: -80.715845

SWAMPid: 233634CU47AB



Location



Field Photo

11/3/2020

Survey Need: Yes

SurveyDescription: Survey pipe inverts

Maintenance Need: Yes

Field Visit Notes: Pipe across Tropical Trail is overgrown. The flow path leading to the County Park is in need of ditch maintenance to function optimally.

Drainage Pattern Verification: Y

Drainage Pattern Comment: Verified flow into County Park prior to discharge into lagoon.




North Merritt Island Field Inspection Form

Link Name:WB3060_1

Lat: 28.441891972

Long: -80.719127

SWAMPid: Not in SWAMP



Location



Field Photo

11/3/2020

Survey Need: No

SurveyDescription:

Maintenance Need: Yes

Field Visit Notes: Structure is Overgrown with vegetation and appears in disrepair. Field measured an 8 foot rectangular section for shape. Use invert elevation from construction plans.

Drainage Pattern Verification:

Drainage Pattern Comment:




North Merritt Island Field Inspection Form

Link Name:PC1020_1

SWAMPid: P040E602086085

Lat: 28.434506972

Long: -80.70850697



Location



Field Photo

11/5/2020

Survey Need: No

SurveyDescription:

Maintenance Need: No

Field Visit Notes: Confirmed hydraulic connection to node. Slot in box enables flow in ditch to connect to pipe crossing Hall Road.

Drainage Pattern Verification: Y

Drainage Pattern Comment: Confirmed that a slot in what appeared to be a junction manhole received surface flow from the NW corner of Hall Road and SR3.




North Merritt Island Field Inspection Form

Link Name:PC1060_1

SWAMPid: 0000CU0000

Lat: 28.448125972

Long: -80.710863



Location



Field Photo

11/3/2020

Survey Need: No

SurveyDescription:

Maintenance Need: No

Field Visit Notes: Crown of pipe below water line. Assume the pipe inverts are the same size as PC1060_2 (FeatureCode P127D63417918), which is a parallel pipe connecting across the road.

Drainage Pattern Verification:

Drainage Pattern Comment:




North Merritt Island Field Inspection Form

Link Name:PC1080_1

Lat: 28.457142972

Long: -80.711116

SWAMPid: NO FEATURE CODE



Location



Field Photo

11/3/2020

Survey Need: No

SurveyDescription:

Maintenance Need: Yes

Field Visit Notes: Culvert is completely silted and not functioning. Does not appear to be designed to continue a flowway across the road, rather to drain a roadside swale. The culvert does not appear to be an integral part of the overall drainage system, however may result in localized roadway flooding during intense rainfall events if not cleaned out.

Drainage Pattern Verification: Y

Drainage Pattern Comment: Does not connect regional flow across the road, rather this culvert is part of the roadway drainage system.




North Merritt Island Field Inspection Form

Link Name:PC1085_1

SWAMPid: P018D627035032

Lat: 28.460134887

Long: -80.70964745



Location



Field Photo

11/3/2020

Survey Need: No

SurveyDescription:

Maintenance Need: No

Field Visit Notes: In SWAMP without specified inverts. It is a significant structure connecting across SR3.
2x48 inch culverts. Use construction plans for elevations Pg 32 of 82 NMI_123_RD_01.pdf

Drainage Pattern Verification:

Drainage Pattern Comment:




North Merritt Island Field Inspection Form

Link Name:PC1090_1

Lat: 28.45767

Long: -80.71607197

SWAMPid: In SWAMP wo Feature Code



Location



Field Photo

11/3/2020

Survey Need: No

SurveyDescription:

Maintenance Need: No

Field Visit Notes: Minor drainage connection across. Estimate Crown of pipe as 1 ft below DEM. 4.1 ft NAVD88. Structure size in SWAMP database.

Drainage Pattern Verification:

Drainage Pattern Comment:




North Merritt Island Field Inspection Form

Link Name:PC1092_1

Lat: 28.455635

Long: -80.71648

SWAMPid: Not in SWAMP



Location



Field Photo

11/3/2020

Survey Need: Yes

SurveyDescription: Culvert and headwall

Maintenance Need: Yes

Field Visit Notes: Recent Maintenance placed a sandbag headwall to mitigate erosion of structure. Consider replacing with a more permanent structure. 36 inch CMP 3.0 ft below roadway crown.

Drainage Pattern Verification:

Drainage Pattern Comment:




North Merritt Island Field Inspection Form

Link Name:PC1130_1

Lat: 28.457737

Long: -80.71450097

SWAMPid: Not in SWAMP



Location



Field Photo

11/3/2020

Survey Need: Yes

SurveyDescription: Culvert crossing Ditch on the north side of Church Rd

Maintenance Need: Yes

Field Visit Notes: Ditch side culvert along Church Rd to provide access to property to the north. Estimate at 24 inch. DEM 6.4 culvert 36inch flowline 3.4 46ft long.

Drainage Pattern Verification: Y

Drainage Pattern Comment: Roadside Ditch is a significant conveyance way along Church Rd




North Merritt Island Field Inspection Form

Link Name:PC1160_1

Lat: 28.457689972

Long: -80.713076

SWAMPid: In SWAMP wo Feature Code



Location



Field Photo

11/3/2020

Survey Need: Yes

SurveyDescription: Connection between pond and ditch including culvert and high point in swale between roadway and pond

Maintenance Need: Yes

Field Visit Notes: Culvert does not appear to be the control between the pond and ditch, rather a high point in swale leading to pond. Recommend regrading for proper function. Culvert is silted on the upstream side.

Drainage Pattern Verification:

Drainage Pattern Comment:




North Merritt Island Field Inspection Form

Link Name:PCC1100_1

Lat: 28.492881

Long: -80.67534897

SWAMPid: Not in SWAMP



Location



Field Photo

11/3/2020

Survey Need: No

SurveyDescription:

Maintenance Need: No

Field Visit Notes: Field observations included 3 CMPs 36 inch. These structures are part of the NASA model under development at the time of this field work. Incorporate data from the NASA model when it is available for this location.

Drainage Pattern Verification:

Drainage Pattern Comment:




North Merritt Island Field Inspection Form

Link Name:PD1070_1

Lat: 28.492730972

Long: -80.71669197

SWAMPid: 0000CU0000



Location



Field Photo

11/3/2020

Survey Need: No

SurveyDescription: JEA RTK from NASA Model

Maintenance Need: Yes

Field Visit Notes: Tideflex product does not appear to be function optimally, the rubber appears still from oxidation. It is recommended that the manufacturer provide an opinion as to how well the structure will function in this condition. Upstream side is mostly silted. Estimate crown is 1 ft below roadway.

Drainage Pattern Verification:

Drainage Pattern Comment:




North Merritt Island Field Inspection Form

Link Name:PDD1002_1

SWAMPid: BC233624CU009

Lat: 28.463620972

Long: -80.678937



Location



Field Photo

11/3/2020

Survey Need: Yes

SurveyDescription: Culvert and access overtopping elevation

Maintenance Need: Yes

Field Visit Notes: Sandbag headwall beginning to crumble. Channel is full of vegetation. Estimate crown 2 ft below DEM 3.2 NAVD88. CMP until survey confirms.

Drainage Pattern Verification:

Drainage Pattern Comment:




North Merritt Island Field Inspection Form

Link Name:PDD1010_1

SWAMPid: BC233624CU008

Lat: 28.463671441

Long: -80.68375196



Location



Field Photo

11/3/2020

Survey Need: Yes

SurveyDescription: Culvert and Access Rd overtopping

Maintenance Need: No

Field Visit Notes: ABS pipe, dimension in SWAMP without elevation. Estimate invert at flowline -2.9 NAVD88, until survey confirms

Drainage Pattern Verification: Y

Drainage Pattern Comment: Previous model did not have any obstruction to flow here. Field observation confirmed culvert under access road will serve as a restriction to flow.




North Merritt Island Field Inspection Form

Link Name:PDD3315_1

SWAMPid: P015D623029030

Lat: 28.465185

Long: -80.69622497



Location



Field Photo

11/3/2020

Survey Need: No

SurveyDescription:

Maintenance Need: Yes

Field Visit Notes: Upstream end of culvert partially silted. Tideflex pipe end treatment. Tideflex product does not appear to be function optimally, the rubber appears still from oxidation. It is recommended that the manufacturer provide an opinion as to how well the structure will function in this condition.

Drainage Pattern Verification:

Drainage Pattern Comment:




North Merritt Island Field Inspection Form

Link Name:PDD3335_1

Lat: 28.465195

Long: -80.69381797

SWAMPid: P021D623042041



Location



Field Photo

11/3/2020

Survey Need: No

SurveyDescription:

Maintenance Need: Yes

Field Visit Notes: Upstream end of culvert partially silted. Tideflex pipe end treatment. Tideflex product does not appear to be function optimally, the rubber appears still from oxidation. It is recommended that the manufacturer provide an opinion as to how well the structure will function in this condition.

Drainage Pattern Verification:

Drainage Pattern Comment:




North Merritt Island Field Inspection Form

Link Name:PDD3345_1

SWAMPid: P012D623024023

Lat: 28.465019972

Long: -80.698164



Location



Field Photo

11/3/2020

Survey Need: No

SurveyDescription:

Maintenance Need: Yes

Field Visit Notes: Tideflex pipe end treatment. Tideflex product does not appear to be function optimally, the rubber appears still from oxidation. It is recommended that the manufacturer provide an opinion as to how well the structure will function in this condition.

Drainage Pattern Verification:

Drainage Pattern Comment:



North Merritt Island Field Inspection Form

Link Name:PDD3405_1

Lat: 28.464973

Long: -80.69977297

SWAMPid: P007D623013014



Location



Field Photo

11/3/2020

Survey Need: No

SurveyDescription:

Maintenance Need: Yes

Field Visit Notes: Tideflex pipe end treatment. Tideflex product does not appear to be function optimally, the rubber appears still from oxidation. It is recommended that the manufacturer provide an opinion as to how well the structure will function in this condition.

Drainage Pattern Verification:

Drainage Pattern Comment:




North Merritt Island Field Inspection Form

Link Name:DEE3100_1

Lat: 28.419857

Long: -80.70748797

SWAMPid: BCE611CS048



Location



Field Photo

11/5/2020

Survey Need: No

SurveyDescription:

Maintenance Need: No

Field Visit Notes: The manhole type structure does not appear to be a significant hydraulic outfall, rather a structure only contains an orifice. Pond's primary discharges is to the west through a narrow concrete and brick lined channel controlled by a weir at the lake.

Drainage Pattern Verification: Y

Drainage Pattern Comment: Pond does not discharge into roadway channel, rather it discharges west into wetland through a weir structure.




North Merritt Island Field Inspection Form

Link Name: PEE1060_1

SWAMPid: P094D634135133

Lat: 28.434349972

Long: -80.718051



Location



Field Photo

11/3/2020

Survey Need: No

SurveyDescription:

Maintenance Need: Yes

Field Visit Notes: Channel leading to the culvert is overgrown. The area has survey flags, indicating that the area has been recently surveyed. The discharge pipe includes flow into a baffle box structure. Elevations are in the SWAMP database. Current water level based upon gauge at the upstream side of the culvert is 0.8 assume NAVD88

Drainage Pattern Verification:

Drainage Pattern Comment:




North Merritt Island Field Inspection Form

Link Name: PEE3010_1

Lat: 28.431654

Long: -80.70816497

SWAMPid: Not in SWAMP



Location



Field Photo

11/5/2020

Survey Need: No

SurveyDescription:

Maintenance Need: No

Field Visit Notes: Conveyance ditch with 18 inch RCP crown, estimated at one foot below driveway (7.5 NAVD88 Driveway per DEM). Invert of 18 inch RCP is 5.0 NAVD88. 60ft.

Drainage Pattern Verification: Y

Drainage Pattern Comment: Confirmed ditch flows north in swale to Hall Road




North Merritt Island Field Inspection Form

Link Name: PEE3010_2

SWAMPid: P052E602100081

Lat: 28.433851

Long: -80.708393



Location



Field Photo

11/5/2020

Survey Need: No

SurveyDescription:

Maintenance Need: No

Field Visit Notes: Culvert in SWAMP without downstream invert. Field observation estimate minimal change in elevation upstream to downstream. For the 36 inch RCP use upstream invert as downstream

Drainage Pattern Verification:

Drainage Pattern Comment:




North Merritt Island Field Inspection Form

Link Name: PEE3020_1

Lat: 28.426724821

Long: -80.70768053

SWAMPid: In SWAMP wo feature code



Location



Field Photo

11/3/2020

Survey Need: Yes

SurveyDescription: Culvert inverts

Maintenance Need: No

Field Visit Notes: 2 x 14 x 23ERCP crossing sunset lakes drive. Flowline based upon the DEM is 6.25 NAVD88, use as an approximate until survey confirmation

Drainage Pattern Verification:

Drainage Pattern Comment:




North Merritt Island Field Inspection Form

Link Name: PEE3030_2

Lat: 28.420352972

Long: -80.70716197

SWAMPid: Not in SWAMP



Location



Field Photo

11/5/2020

Survey Need: No

SurveyDescription:

Maintenance Need: No

Field Visit Notes: 14x23 ERCP. DEM El 8.5. Invert 6.0 NAVD88. 48ft long

Drainage Pattern Verification:

Drainage Pattern Comment:




North Merritt Island Field Inspection Form

Link Name: PEE3040_1

Lat: 28.426303972

Long: -80.70890797

SWAMPid: In SWAMP wo feature code



Location



Field Photo

11/3/2020

Survey Need: Yes

SurveyDescription: Culvert inverts and sandbag weir and sketch.

Maintenance Need: Yes

Field Visit Notes: 3 pipes each is a 24 inch RCP. The first one has sandbag weir as bottom clip. Silt partially blocks all culverts.

Drainage Pattern Verification:

Drainage Pattern Comment:




North Merritt Island Field Inspection Form

Link Name: PEE3110_1

SWAMPid: BCE611CS047

Lat: 28.419115972

Long: -80.70708897



Location



Field Photo

11/5/2020

Survey Need: No

Survey Description:

Maintenance Need: No

Field Visit Notes: 18 inch RCP invert 3 feet below pavement. DEM 9.2 NAVD88. Invert 6.2 NAVD88 72 ft long

Drainage Pattern Verification:

Drainage Pattern Comment:




North Merritt Island Field Inspection Form

Link Name: PEE3280_1

Lat: 28.412780972

Long: -80.71109197

SWAMPid: Not in SWAMP



Location



Field Photo

11/3/2020

Survey Need: Yes

SurveyDescription: Driveway culvert under 210 Grant Rd

Maintenance Need: Yes

Field Visit Notes: As water flows north across Grant Road this link represents the controlling (first) culvert in a series of culverts that conveys water to the west. This culvert under a driveway at 210 Grant Rd is rusted and the channel is overgrown

Drainage Pattern Verification:

Drainage Pattern Comment:




North Merritt Island Field Inspection Form

Link Name: PEE3310_1

Lat: 28.41449

Long: -80.70669

SWAMPid: Not in SWAMP



Location



Field Photo

11/5/2020

Survey Need: No

SurveyDescription:

Maintenance Need: No

Field Visit Notes: 24" RCP Invert 4 ft below roadway. DEM 8.5. invert 4.5. 24" RCP. 72ft long

Drainage Pattern Verification:

Drainage Pattern Comment:




North Merritt Island Field Inspection Form

Link Name: PEE4160_1

Lat: 28.421908972

Long: -80.71693197

SWAMPid: P161E603217218



Location



Field Photo

11/3/2020

Survey Need: Yes

SurveyDescription: Culvert inverts

Maintenance Need: Yes

Field Visit Notes: Roadway cross culvert is silted significantly on the downstream side. Field estimates culvert has approximately 8 inches of cover from the roadway centerline. Road 7.8 NAVD88. approximate invert 6.0 until survey

Drainage Pattern Verification: Y

Drainage Pattern Comment: Into the roadside ditch near the location of this cross culvert, was an additional outlet from development to the east. The outlet did not appear on the "as built" however it was included in the original design plans. Field investigation did not uncover




North Merritt Island Field Inspection Form

Link Name: PEE5060_1

SWAMPid: P023E610033034

Lat: 28.418195972

Long: -80.716853



Location



Field Photo

11/3/2020

Survey Need: Yes

Survey Description: Driveway culvert and low point in swale around bend in Spartia Ave between Driveway culverts down to Oak Place

Maintenance Need: Yes

Field Visit Notes: Swale silted and sodded partially blocking culvert. 24inch DEM 8ft NAVD88 invert 5ft NAVD until survey confirms.

Drainage Pattern Verification:

Drainage Pattern Comment:




North Merritt Island Field Inspection Form

Link Name: PEE5060_2

SWAMPid: P025E610039040

Lat: 28.418195972

Long: -80.716853



Location



Field Photo

11/3/2020

Survey Need: Yes

SurveyDescription: Driveway culvert and culvert crossing Oak Place

Maintenance Need: Yes

Field Visit Notes: Swale silted and sodded partially blocking culvert. Control maybe either driveway culvert or culvert crossing Oak Place. 14x23inch ERCP driveway 7.6 NAVD88, which estimates the culvert invert at 5.2 NAVD88, until survey confirms

Drainage Pattern Verification:

Drainage Pattern Comment:




North Merritt Island Field Inspection Form

Link Name:DF1180_1

Lat: 28.464559972

Long: -80.70871997

SWAMPid: BCD623CS135



Location



Field Photo

11/3/2020

Survey Need: No

SurveyDescription:

Maintenance Need: No

Field Visit Notes: FDOT pond 133 (ph 321-634-6100). SWAMP has elevations missing top dimension and orifice dimension. Field estimated as a Type C structure with a 3 inch orifice

Drainage Pattern Verification:

Drainage Pattern Comment:




North Merritt Island Field Inspection Form

Link Name:PF2080_1

SWAMPid: P053D626110109

Lat: 28.456416

Long: -80.70454997



Location



Field Photo

11/5/2020

Survey Need: No

SurveyDescription:

Maintenance Need: No

Field Visit Notes: Multiple culvert sizes and/or inverts confirmed, use SWAMP data and add additional culvert link to the model to simulate a total of 4 culverts. (2 sets of 2)

Drainage Pattern Verification:

Drainage Pattern Comment:




North Merritt Island Field Inspection Form

Link Name:PF2110_1

Lat: 28.466056972

Long: -80.707086

SWAMPid: NO FEATURE CODE



Location



Field Photo

11/3/2020

Survey Need: No

SurveyDescription:

Maintenance Need: Yes

Field Visit Notes: Culvert is in SWAMP, but no evidence of the culvert was found in the field. It is likely that the culvert has been silted for many years and no longer functions as the primary outlet for this area. Maintenance to restore functionality of structure.

Drainage Pattern Verification: Y

Drainage Pattern Comment: Water not crossing roadway couldn't find culvert assume fully silted and not functioning.




North Merritt Island Field Inspection Form

Link Name:PF2110_2

Lat: 28.466058513

Long: -80.70655614

SWAMPid: Not in SWAMP



Location



Field Photo

11/3/2020

Survey Need: No

SurveyDescription:

Maintenance Need: No

Field Visit Notes: Series of driveway culverts flowing along roadside ditch towards main channel. 15 inch 30 ft long CMP would simulate the conveyance for this model link. Flood water would likely overtop the roadway. Based upon DEM estimate flowline at 1.0 NAVD88.

Drainage Pattern Verification:

Drainage Pattern Comment:




North Merritt Island Field Inspection Form

Link Name:DFF1060_1

Lat: 28.427748972

Long: -80.707447

SWAMPid: BCE602CS158



Location



Field Photo

11/5/2020

Survey Need: Yes

SurveyDescription: Provide detailed sketch of structure to supplement SWAMP elevations.

Maintenance Need: No

Field Visit Notes: FDOT pond 131 (ph 321-634-6100). Could not gain access to the structure. SWAMP has elevations but not weir dimensions.

Drainage Pattern Verification:

Drainage Pattern Comment:




North Merritt Island Field Inspection Form

Link Name:DFF1090_1

Lat: 28.42685

Long: -80.70735

SWAMPid: BCE602CS146



Location



Field Photo

11/5/2020

Survey Need: No

SurveyDescription:

Maintenance Need: No

Field Visit Notes: The SWAMP database has structure elevations. Dimensions collected in the field to incorporate into the model include: 3" orifice, type C inlet, slot 23" x 7" 15"CMP outlet pipe

Drainage Pattern Verification:

Drainage Pattern Comment:




North Merritt Island Field Inspection Form

Link Name:DFF1230_1

Lat: 28.414923972

Long: -80.706218

SWAMPid: BCE611CS096



Location



Field Photo

11/5/2020

Survey Need: No

SurveyDescription:

Maintenance Need: Yes

Field Visit Notes: The SWAMP database has structure elevations without specified dimensions. Dimensions collected in the field to incorporate into the model include: top 54x37; 3 slots 1 and 2 are 36x11.5 and 3 is 54x12.5. orifice is 3". Noted that the Skimmer was damaged and in need of repair or replacement.

Drainage Pattern Verification:

Drainage Pattern Comment:




North Merritt Island Field Inspection Form

Link Name:PFF1010_2

SWAMPid: P047E602080077

Lat: 28.434314

Long: -80.70757897



Location



Field Photo

11/5/2020

Survey Need: No

SurveyDescription:

Maintenance Need: No

Field Visit Notes: Culvert in SWAMP without upstream invert. Field observation estimate minimal change in elevation upstream to downstream. Confirmed culvert connects across SR3. Use downstream invert -1.78 NAVD88 for upstream

Drainage Pattern Verification: Y

Drainage Pattern Comment: Confirmed culvert crosses SR3 connecting ditch on south side of Hall Road.




North Merritt Island Field Inspection Form

Link Name:PFF1060_1

SWAMPid: P088E602133134

Lat: 28.428699972

Long: -80.70756



Location



Field Photo

11/5/2020

Survey Need: No

SurveyDescription:

Maintenance Need: No

Field Visit Notes: Hydraulic confirmation that culvert is connected to Pond. Use SWAMP elevations.

Drainage Pattern Verification: Y

Drainage Pattern Comment: Confirmed swale is connected to pond directly.




North Merritt Island Field Inspection Form

Link Name:PFF1180_1

SWAMPid: P042E611074075

Lat: 28.419626972

Long: -80.706742



Location



Field Photo

11/5/2020

Survey Need: No

SurveyDescription:

Maintenance Need: Yes

Field Visit Notes: Confirmed 24 inch RCP connection to the south. Site just to the north is currently under development. Culverts partially silted and in need of maintenance to function properly.

Drainage Pattern Verification:

Drainage Pattern Comment:




North Merritt Island Field Inspection Form

Link Name:PFF1210_1

SWAMPid: P045E611079080

Lat: 28.418579

Long: -80.706698



Location



Field Photo

11/5/2020

Survey Need: No

SurveyDescription:

Maintenance Need: Yes

Field Visit Notes: Culverts partially silted and in need of maintenance to function property.

Drainage Pattern Verification:

Drainage Pattern Comment:




North Merritt Island Field Inspection Form

Link Name:WFF2010_1

SWAMPid: BCE602CS111

Lat: 28.433942972

Long: -80.69646097



Location



Field Photo

11/5/2020

Survey Need: No

SurveyDescription:

Maintenance Need: No

Field Visit Notes: Lower portion of weir 57". Correlating to SWAMP El -3.57 NAVD88. Top portion of weir per SWAMP top El 1.22 NAVD88

Drainage Pattern Verification:

Drainage Pattern Comment:




North Merritt Island Field Inspection Form

Link Name: DG1840_1

Lat: 28.434418972

Long: -80.69749897

SWAMPid: BCE602CS069



Location



Field Photo

11/5/2020

Survey Need: No

SurveyDescription:

Maintenance Need: No

Field Visit Notes: Structure is a large box with sealed top and slot opening on the ditch side. SWAMP Invert - 1.82 NAVD88. Field measurement of opening is 6 ft wide by 5 ft deep.

Drainage Pattern Verification:

Drainage Pattern Comment:




North Merritt Island Field Inspection Form

Link Name:DG6050_1

SWAMPid: P130D63516816

Lat: 28.441676972

Long: -80.708729



Location



Field Photo

11/3/2020

Survey Need: No

SurveyDescription:

Maintenance Need: No

Field Visit Notes: Initial desktop evaluation of this structure appears as though it was a Drop Structure, however field investigation indicated that the pond is actually just offline storage connected to the roadside swale along SR3 swale. The controlling culvert for this node is the pipe under WoodStork Dr, which is in SWAMP.

Drainage Pattern Verification:

Drainage Pattern Comment:




North Merritt Island Field Inspection Form

Link Name:PG1790_1

SWAMPid: P035E602091088

Lat: 28.434484972

Long: -80.70846297



Location



Field Photo

11/5/2020

Survey Need: No

SurveyDescription:

Maintenance Need: No

Field Visit Notes: 48" cross culvert is in SWAMP without invert elevations. Flow line specified as -0.63 NAVD88 (converted from NGVD29) per pg 24 of 82 NMI_123_RD_01

Drainage Pattern Verification:

Drainage Pattern Comment:




North Merritt Island Field Inspection Form

Link Name:PG6040_1

SWAMPid: P110D635140141

Lat: 28.441680972

Long: -80.70871497



Location



Field Photo

11/5/2020

Survey Need: No

SurveyDescription:

Maintenance Need: No

Field Visit Notes: Pond downstream is an offline retention facility rather than a stand alone pond with discharge structure. Controlling connection downstream is the culvert crossing the pond's access driveway. Culvert is 24 inches with inverts of 2.05 NAVD88 upstream/downstream 40 ft long.

Drainage Pattern Verification:

Drainage Pattern Comment:




North Merritt Island Field Inspection Form

Link Name:DGG1030_1

SWAMPid: BCE601CS001

Lat: 28.434179

Long: -80.678317



Location



Field Photo

11/5/2020

Survey Need: No

SurveyDescription:

Maintenance Need: No

Field Visit Notes: Construction plans and "as built" showed various modifications to outfall structure. Field investigation confirms that the box top is 177x44, left slot is regular; right slot has main slot and 2 steps. Elevations are in SWAMP.

Drainage Pattern Verification:

Drainage Pattern Comment:




North Merritt Island Field Inspection Form

Link Name: PGG1010_1

SWAMPid: P001E601011010

Lat: 28.432013972

Long: -80.67733697



Location



Field Photo

11/5/2020

Survey Need: Yes

Survey Description: Culvert size and inverts

Maintenance Need: No

Field Visit Notes: 18" HDPE 12" above water level. DEM water level 3.3 NAVD88. Invert 4.3 NAVD88

Drainage Pattern Verification:

Drainage Pattern Comment:




North Merritt Island Field Inspection Form

Link Name: PGG1020_1

SWAMPid: 0000CU0000

Lat: 28.434429

Long: -80.67643597



Location



Field Photo

11/5/2020

Survey Need: No

SurveyDescription:

Maintenance Need: No

Field Visit Notes: 18" RCP invert 4 ft below roadway. DEM 6.4, yielding an invert o 2.4 NAVD88

Drainage Pattern Verification:

Drainage Pattern Comment:




North Merritt Island Field Inspection Form

Link Name: PGG1060_2

Lat: 28.432387972

Long: -80.678184

SWAMPid: Not in SWAMP



Location



Field Photo

11/5/2020

Survey Need: No

SurveyDescription:

Maintenance Need: Yes

Field Visit Notes: Culvert is presented in construction plans as an equalizer pipe between subdivision ponds. Field measured a 36" culvert 1.0 ft of silt in the pipe. Homeowners says culvert periodically clogs. Elevation culvert invert is 24" above current water level for a resulting invert elevation of 0.75 NAVD88.

Drainage Pattern Verification:

Drainage Pattern Comment:




North Merritt Island Field Inspection Form

Link Name: PGG1110_2

SWAMPid: P004E612005006

Lat: 28.419405972

Long: -80.67958797



Location



Field Photo

11/5/2020

Survey Need: No

Survey Description:

Maintenance Need: No

Field Visit Notes: One foot of silt in 30 inch golf course cart path crossing culvert. Normal water level appears to half submerge the pipe. Crown of pipe is 0.5 feet to sidewalk. DEM 2.5. Water Level 1.0 NAVD88. Culvert invert EL -0.25 NAVD88

Drainage Pattern Verification:

Drainage Pattern Comment:




North Merritt Island Field Inspection Form

Link Name: PGG1150_1

SWAMPid: P014E612021022

Lat: 28.417087972

Long: -80.678257



Location



Field Photo

11/5/2020

Survey Need: No

SurveyDescription:

Maintenance Need: Yes

Field Visit Notes: 17" from water line to invert 2 x 12" HDPE. The upstream side of the pipe has split at a pipe joint. Water level is 0.57 NAVD88, yielding an invert flowline of -0.25 NAVD88 connecting the two golf course ponds

Drainage Pattern Verification:

Drainage Pattern Comment:




North Merritt Island Field Inspection Form

Link Name:DJ1900_1

Lat: 28.434394972

Long: -80.687825

SWAMPid: BCE601CS086



Location



Field Photo

11/5/2020

Survey Need: No

SurveyDescription:

Maintenance Need: No

Field Visit Notes: Structure is a large box with sealed top and slot opening on the ditch side. SWAMP Invert - 1.57 NAVD88. Field measurement opening 6 ft wide by 5 ft deep.

Drainage Pattern Verification:

Drainage Pattern Comment:




North Merritt Island Field Inspection Form

Link Name:DL1270_1

Lat: 28.451221

Long: -80.68288097

SWAMPid: BCD625CS092



Location



Field Photo

11/5/2020

Survey Need: No

SurveyDescription:

Maintenance Need: No

Field Visit Notes: The SWAMP database has structure elevations without specified dimensions. Field measurement of structure dimensions are: top 36x54. inside main weir 30" in addition to a notch that is 6 inches wide.

Drainage Pattern Verification:

Drainage Pattern Comment:




North Merritt Island Field Inspection Form

Link Name:DL1790_1

Lat: 28.448978

Long: -80.68679697

SWAMPid: BCD625CS099



Location



Field Photo

11/5/2020

Survey Need: Yes

SurveyDescription: Detailed Structure Sketch. Survey Structure and broad crest weir representing berm overtopping the pond into Chase Hammock Ditch

Maintenance Need: No

Field Visit Notes: The structure is in the SWAMP database, however, it was not able to be access for field measurements and does not appear to be a typical configuration. Need survey to validate slot openings and structure dimensions.

Drainage Pattern Verification:

Drainage Pattern Comment:




North Merritt Island Field Inspection Form

Link Name: PL1345_1

SWAMPid: BC233625CU010

Lat: 28.463529

Long: -80.67895697



Location



Field Photo

11/3/2020

Survey Need: Yes

Survey Description: Culvert and ditch on south side of road to confirm culvert invert is the controlling elevation for water getting to the ditch.

Maintenance Need: Yes

Field Visit Notes: Structure is partially silted and obscured by vegetation. Survey benchmark on the side of the roadway indicates 3.3 ft, no datum specified, assume NAVD88. Until survey confirms estimate invert at 3 ft below roadway edge El 0.3 NAVD88.

Drainage Pattern Verification:

Drainage Pattern Comment:




North Merritt Island Field Inspection Form

Link Name: PM2940_1

SWAMPid: 0000CU0000

Lat: 28.456983

Long: -80.68975297



Location



Field Photo

11/3/2020

Survey Need: No

Survey Description:

Maintenance Need: No

Field Visit Notes: Flow line 5 ft below roadway. DEM elevation of roadway is 2.5ft NAVD88 with pipe invert of -2.5ft NAVD88.

Drainage Pattern Verification:

Drainage Pattern Comment:




North Merritt Island Field Inspection Form

Link Name: PM2970_1

SWAMPid: P006D624008007

Lat: 28.463481972

Long: -80.68992697



Location



Field Photo

11/3/2020

Survey Need: No

SurveyDescription:

Maintenance Need: Yes

Field Visit Notes: Tideflex pipe end treatment. Tideflex product does not appear to be function optimally, the rubber appears still from oxidation. It is recommended that the manufacturer provide an opinion as to how well the structure will function in this condition.

Drainage Pattern Verification:

Drainage Pattern Comment:




North Merritt Island Field Inspection Form

Link Name:PM2980_1

Lat: 28.463554972

Long: -80.687509

SWAMPid: 0000CU0000



Location



Field Photo

11/3/2020

Survey Need: Yes

SurveyDescription: culvert inverts

Maintenance Need: Yes

Field Visit Notes: Tideflex pipe end treatment, submerged at current water level. Tideflex product does not appear to be function optimally, the rubber appears still from oxidation. It is recommended that the manufacturer provide an opinion as to how well the structure will function in this condition.

Drainage Pattern Verification:

Drainage Pattern Comment:




North Merritt Island Field Inspection Form

Link Name:PM3000_1

Lat: 28.463633

Long: -80.686356

SWAMPid: 0000CU0000



Location



Field Photo

11/3/2020

Survey Need: Yes

SurveyDescription: culvert inverts

Maintenance Need: Yes

Field Visit Notes: Tideflex pipe end treatment. Tideflex product does not appear to be function optimally, the rubber appears still from oxidation. It is recommended that the manufacturer provide an opinion as to how well the structure will function in this condition.

Drainage Pattern Verification:

Drainage Pattern Comment:




North Merritt Island Field Inspection Form

Link Name:PO1300_1

Lat: 28.450762

Long: -80.683862

SWAMPid: Not in SWAMP



Location



Field Photo

11/5/2020

Survey Need: No

SurveyDescription:

Maintenance Need: No

Field Visit Notes: Pipe submerged at normal water level. Assume 24". DEM elevation 2.3. Invert -0.5 NAVD88

Drainage Pattern Verification:

Drainage Pattern Comment:




North Merritt Island Field Inspection Form

Link Name:PO2960_1

Lat: 28.449003

Long: -80.68809697

SWAMPid: Not in SWAMP



Location



Field Photo

11/3/2020

Survey Need: Yes

SurveyDescription: Culvert Inverts

Maintenance Need: No

Field Visit Notes: 18 inch RCP. Submerged assume crown at DEM water level.

Drainage Pattern Verification:

Drainage Pattern Comment:




North Merritt Island Field Inspection Form

Link Name:PO3030_2

SWAMPid: BC233636CU003

Lat: 28.449031

Long: -80.68399497



Location



Field Photo

11/5/2020

Survey Need: Yes

SurveyDescription: Culvert under Chase Hammock Rd

Maintenance Need: No

Field Visit Notes: Pipe below water level. Assume 24" invert -0.5 NAVD88. until survey confirmation.

Drainage Pattern Verification:

Drainage Pattern Comment:




North Merritt Island Field Inspection Form

Link Name:PP2641_1

Lat: 28.455743972

Long: -80.70036797

SWAMPid: P024D626038037



Location



Field Photo

11/5/2020

Survey Need: No

SurveyDescription:

Maintenance Need: No

Field Visit Notes: Confirmed different size pipes here

Drainage Pattern Verification:

Drainage Pattern Comment:




North Merritt Island Field Inspection Form

Link Name:PP2641_2

SWAMPid: P023D626036039

Lat: 28.455743972

Long: -80.70036797



Location



Field Photo

11/5/2020

Survey Need: No

SurveyDescription:

Maintenance Need: No

Field Visit Notes: Confirmed different size pipes here

Drainage Pattern Verification:

Drainage Pattern Comment:




North Merritt Island Field Inspection Form

Link Name:DPI1030_2

Lat: 28.494029972

Long: -80.72119997

SWAMPid: BCE610CS011



Location



Field Photo

11/3/2020

Survey Need: No

SurveyDescription:

Maintenance Need: No

Field Visit Notes: Outfall connection between Pine Island North pond and outfall channel. The structure includes 2 pipes and headwall weir structure. This validates the data in SWAMP and the construction plans

Drainage Pattern Verification:

Drainage Pattern Comment:




North Merritt Island Field Inspection Form

Link Name:DPI1030_3

Lat: 28.492736

Long: -80.721162

SWAMPid: BCD610CS001



Location



Field Photo

11/3/2020

Survey Need: No

SurveyDescription:

Maintenance Need: No

Field Visit Notes: Because of the presence of the skimmer on this structure, it was assumed it was a drop structure, however the trash skimmer has no elevation control for the pipe connecting to the Pine Island South Pond.

Drainage Pattern Verification: Y

Drainage Pattern Comment: Confirmed, this provides a hydraulic connection between the ditch and Pine Island South Pond




North Merritt Island Field Inspection Form

Link Name:DPI2020_1

SWAMPid: 0000CU000

Lat: 28.50008

Long: -80.71876



Location



Field Photo

11/3/2020

Survey Need: No

SurveyDescription:

Maintenance Need: No

Field Visit Notes: SWAMP data indicated the presence of a drop structure, however there is no structure visible in the field, just an open channel

Drainage Pattern Verification:

Drainage Pattern Comment:




North Merritt Island Field Inspection Form

Link Name:PPI2010_1

Lat: 28.499110972

Long: -80.717482

SWAMPid: 0000CU0000



Location



Field Photo

11/3/2020

Survey Need: Yes

SurveyDescription: Culvert inverts

Maintenance Need: Yes

Field Visit Notes: Culvert crossing Dee Dr. Partially Blocked. DEM Road. 4.0. Assume invert 1.0 NAVD88 until Survey updates

Drainage Pattern Verification:

Drainage Pattern Comment:




North Merritt Island Field Inspection Form

Link Name:PPI2010_2

Lat: 28.497479972

Long: -80.717065

SWAMPid: 0000CU0000



Location



Field Photo

11/3/2020

Survey Need: Yes

SurveyDescription: Culvert inverts and inlet in Homeowners yard at the end of Fay St.

Maintenance Need: Yes

Field Visit Notes: Culvert from pond crossing dirt road portion of Fay Dr. Drainage path from lake is overgrown. Culvert silted. DEM overflow 3.5. Assume same inverts as outfall in other direction 1.0 NAVD88 until survey

Drainage Pattern Verification:

Drainage Pattern Comment:




North Merritt Island Field Inspection Form

Link Name:PPI2020_3

Lat: 28.496669

Long: -80.72060797

SWAMPid: P015D610016017



Location



Field Photo

11/3/2020

Survey Need: No

SurveyDescription:

Maintenance Need: No

Field Visit Notes: Use inverts in SWAMP for inverts, culvert and headwall

Drainage Pattern Verification: Y

Drainage Pattern Comment: Confirmed drainage pattern discharges lake south through this link



North Merritt Island Field Inspection Form

Link Name:PR3200_1


SWAMPid: 0000CU0000

Lat: 28.449018972

Long: -80.694974



Location



Field Photo

11/3/2020

Survey Need: Yes

SurveyDescription: Culvert and inverts

Maintenance Need: No

Field Visit Notes: Couldn't see culvert clearly, but likely discharges depressional area north into canal. DEM El 3.0 of Berm. Assume Culvert invert 0 NAVD88 until survey confirmation.

Drainage Pattern Verification:

Drainage Pattern Comment:




North Merritt Island Field Inspection Form

Link Name:DS1140_1

SWAMPid: 0000SC0000

Lat: 28.474769972

Long: -80.70226397



Location



Field Photo

11/3/2020

Survey Need: Yes

SurveyDescription: Provide detailed sketch of structure to supplement SWAMP elevations.

Maintenance Need: No

Field Visit Notes: DOT pond 134. Could not gain access to the structure. SWAMP has elevations but not weir dimensions.

Drainage Pattern Verification:

Drainage Pattern Comment:




North Merritt Island Field Inspection Form

Link Name:PT2440_2

Lat: 28.492453

Long: -80.71169997

SWAMPid: 0000CU0000



Location



Field Photo

11/3/2020

Survey Need: No

SurveyDescription:

Maintenance Need: No

Field Visit Notes: Old pump station without no culvert connection. Remove link from the model.

Drainage Pattern Verification:

Drainage Pattern Comment:




North Merritt Island Field Inspection Form

Link Name:DU4030_1

Lat: 28.474586776

Long: -80.70389571

SWAMPid: Not in SWAMP



Location



Field Photo

11/3/2020

Survey Need: No

SurveyDescription:

Maintenance Need: No

Field Visit Notes: Outfall structure appears overgrown yet consistent with development plans from church.
Rely upon construction plans for structure information.

Drainage Pattern Verification:

Drainage Pattern Comment:




North Merritt Island Field Inspection Form

Link Name:PU1120_1

Lat: 28.481733972

Long: -80.70872597

SWAMPid: Not in SWAMP



Location



Field Photo

11/3/2020

Survey Need: No

SurveyDescription:

Maintenance Need: No

Field Visit Notes: Rural connection across access road. 24 inch pipe submerged at normal water level. Per DEM 3.74 NAVD88 is the elevation of the roadway. Approximate Invert 0.5 NAVD88.

Drainage Pattern Verification:

Drainage Pattern Comment:




North Merritt Island Field Inspection Form

Link Name: PU2450_1

SWAMPid: 0000CU0000

Lat: 28.491672972

Long: -80.70057797



Location



Field Photo

11/3/2020

Survey Need: No

SurveyDescription: JEA RTK NASA Model

Maintenance Need: No

Field Visit Notes: DEM roadway 2.4 NAVD88. Field measure 2 ft from crown of pipe to top of road, which yields a structure invert of -1.0 NAVD88.

Drainage Pattern Verification:

Drainage Pattern Comment:




North Merritt Island Field Inspection Form

Link Name:PU4220_1

Lat: 28.492806972

Long: -80.70472497

SWAMPid: 0000CU0000



Location



Field Photo

11/3/2020

Survey Need: Yes

SurveyDescription: Culvert inverts

Maintenance Need: Yes

Field Visit Notes: 36 inch culvert. 7.5 ft from road to flow line. Culvert partially silted in need of maintenance to function optimally. DEM roadway 4.1 NAVD88. invert -3.4 NAVD88.

Drainage Pattern Verification:

Drainage Pattern Comment:




North Merritt Island Field Inspection Form

Link Name: PZZ2010_1

Lat: 28.492927972

Long: -80.67485397

SWAMPid: Not in SWAMP



Location



Field Photo

11/3/2020

Survey Need: No

SurveyDescription:

Maintenance Need: No

Field Visit Notes: 3 x 30 inch CMPs. These structures are part of the NASA model under development at the time of this field work. Incorporate data from the NASA model when it is available for this location.

Drainage Pattern Verification: Y

Drainage Pattern Comment: Connects Drainage across SR3